

Oracle® Fusion Middleware

Data Modeling Guide for Oracle Business Intelligence Publisher

11g Release 1 (11.1.1)

E22258-05

July 2014

Explains how to retrieve and structure data from a variety of sources to use as input to Oracle Business Intelligence Publisher reports.

Oracle Fusion Middleware Data Modeling Guide for Oracle Business Intelligence Publisher, 11g Release 1 (11.1.1)

E22258-05

Copyright © 2010, 2014, Oracle and/or its affiliates. All rights reserved.

Primary Author: Leslie Studdard

Contributing Author: Suzanne Gill

Contributor: Oracle Business Intelligence Publisher development, quality assurance, and product management teams.

This software and related documentation are provided under a license agreement containing restrictions on use and disclosure and are protected by intellectual property laws. Except as expressly permitted in your license agreement or allowed by law, you may not use, copy, reproduce, translate, broadcast, modify, license, transmit, distribute, exhibit, perform, publish, or display any part, in any form, or by any means. Reverse engineering, disassembly, or decompilation of this software, unless required by law for interoperability, is prohibited.

The information contained herein is subject to change without notice and is not warranted to be error-free. If you find any errors, please report them to us in writing.

If this is software or related documentation that is delivered to the U.S. Government or anyone licensing it on behalf of the U.S. Government, the following notice is applicable:

U.S. GOVERNMENT END USERS: Oracle programs, including any operating system, integrated software, any programs installed on the hardware, and/or documentation, delivered to U.S. Government end users are "commercial computer software" pursuant to the applicable Federal Acquisition Regulation and agency-specific supplemental regulations. As such, use, duplication, disclosure, modification, and adaptation of the programs, including any operating system, integrated software, any programs installed on the hardware, and/or documentation, shall be subject to license terms and license restrictions applicable to the programs. No other rights are granted to the U.S. Government.

This software or hardware is developed for general use in a variety of information management applications. It is not developed or intended for use in any inherently dangerous applications, including applications that may create a risk of personal injury. If you use this software or hardware in dangerous applications, then you shall be responsible to take all appropriate fail-safe, backup, redundancy, and other measures to ensure its safe use. Oracle Corporation and its affiliates disclaim any liability for any damages caused by use of this software or hardware in dangerous applications.

Oracle and Java are registered trademarks of Oracle and/or its affiliates. Other names may be trademarks of their respective owners.

Intel and Intel Xeon are trademarks or registered trademarks of Intel Corporation. All SPARC trademarks are used under license and are trademarks or registered trademarks of SPARC International, Inc. AMD, Opteron, the AMD logo, and the AMD Opteron logo are trademarks or registered trademarks of Advanced Micro Devices. UNIX is a registered trademark of The Open Group.

This software or hardware and documentation may provide access to or information on content, products, and services from third parties. Oracle Corporation and its affiliates are not responsible for and expressly disclaim all warranties of any kind with respect to third-party content, products, and services. Oracle Corporation and its affiliates will not be responsible for any loss, costs, or damages incurred due to your access to or use of third-party content, products, or services.

Contents

Preface	ix
Intended Audience.....	ix
Documentation Accessibility	ix
Related Documentation and Other Resources	x
Conventions	x
New Features for Data Model Designers	xi
New Features for Oracle BI Publisher 11g Release 1 (11.1.1.7).....	xi
New Features for Oracle BI Publisher 11g Release 1 (11.1.1.6).....	xii
New Features for Oracle BI Publisher 11g Release 1 (11.1.1.5)	xiii
New Features for Oracle BI Publisher 11g Release 1 (11.1.1.3).....	xiv
1 Using the Data Model Editor	
1.1 What Is a Data Model?	1-1
1.2 Components of a Data Model	1-1
1.3 Features of the Data Model Editor	1-2
1.4 About the Data Source Options	1-2
1.5 Process Overview for Creating a Data Model	1-3
1.6 Launching the Data Model Editor	1-4
1.6.1 About the Data Model Editor Interface	1-4
1.7 Setting Data Model Properties	1-5
1.7.1 XML Output Options	1-6
1.7.2 Attachments to the Data Model.....	1-7
1.7.2.1 Attaching Sample Data	1-7
1.7.2.2 Attaching Schema	1-7
1.7.2.3 Data Files	1-7
1.7.3 Managing Private Data Sources.....	1-7
2 Creating Data Sets	
2.1 Overview of Creating Data Sets.....	2-1
2.2 Editing an Existing Data Set	2-3
2.3 Creating a Data Set Using a SQL Query	2-3
2.3.1 Entering SQL Queries	2-3
2.3.2 Using the SQL Query Builder	2-4
2.3.2.1 Overview of the Query Builder	2-5

2.3.2.2	Understanding the Query Builder Process	2-6
2.3.2.3	Using the Object Selection Pane	2-6
2.3.2.4	Selecting a Schema.....	2-6
2.3.2.5	Searching and Filtering Objects.....	2-6
2.3.2.6	Selecting Objects	2-6
2.3.2.7	Supported Column Types	2-7
2.3.2.8	Adding Objects to the Design Pane	2-7
2.3.2.9	Resizing the Design and Results Pane.....	2-7
2.3.2.10	Removing or Hiding Objects in the Design Pane	2-8
2.3.2.11	Specifying Query Conditions.....	2-8
2.3.2.12	Creating Relationships Between Objects.....	2-9
2.3.2.12.1	About Join Conditions	2-9
2.3.2.12.2	Joining Objects Manually	2-9
2.3.2.13	Saving a Query	2-10
2.3.2.14	Editing a Saved Query	2-11
2.3.3	Adding a Bind Variable to a Query	2-11
2.3.4	Adding Lexical References to SQL Queries.....	2-13
2.3.5	Defining SQL Queries Against the Oracle BI Server	2-14
2.4	Creating a Data Set Using a MDX Query Against an OLAP Data Source	2-16
2.4.1	Creating a Data Set Using a MDX Query.....	2-16
2.5	Using MDX Query Builder	2-17
2.5.1	Understanding the MDX Query Builder Process.....	2-17
2.5.2	Using the Select Cube Dialog.....	2-17
2.5.3	Selecting Dimensions and Measures.....	2-17
2.5.3.1	Adding Dimension Members to the Slicer/POV Axis.....	2-18
2.5.4	Performing MDX Query Actions.....	2-18
2.5.5	Applying MDX Query Filters	2-19
2.5.6	Selecting MDX Query Options and Saving MDX Queries	2-19
2.6	Creating a Data Set Using an LDAP Query	2-20
2.7	Creating a Data Set Using a Microsoft Excel File	2-22
2.7.1	About Supported Excel Files.....	2-22
2.7.2	Guidelines for Accessing Multiple Tables per Sheet	2-22
2.7.3	Using a Microsoft Excel File Stored in a File Directory Data Source	2-23
2.7.4	Uploading a Microsoft Excel File Stored Locally	2-24
2.7.4.1	Refreshing and Deleting an Uploaded Excel File	2-25
2.8	Creating a Data Set Using an Oracle BI Analysis.....	2-26
2.8.1	Additional Notes on Oracle BI Analysis Data Sets.....	2-27
2.9	Creating a Data Set Using a View Object	2-27
2.9.1	Additional Notes on View Object Data Sets	2-28
2.10	Creating a Data Set Using a Web Service	2-28
2.10.1	Adding a Simple Web Service: Example.....	2-29
2.10.2	Adding a Complex Web Service.....	2-31
2.10.3	Additional Information on Web Service Data Sets	2-33
2.11	Creating a Data Set Using a XML File.....	2-33
2.11.1	About Supported XML Files	2-33
2.11.2	Using a XML File Stored in a File Directory Data Source.....	2-34
2.11.3	Uploading a XML File Stored Locally	2-34

2.11.3.1	Refreshing and Deleting an Uploaded XML File.....	2-35
2.12	Creating a Data Set Using a CSV File.....	2-36
2.12.1	About Supported CSV Files	2-36
2.12.2	Using a CSV File Stored in a File Directory Data Source.....	2-36
2.12.3	Uploading a CSV File Stored Locally	2-37
2.12.3.1	Editing the Data Type	2-38
2.12.3.2	Refreshing and Deleting an Uploaded CSV File.....	2-38
2.13	Using Data Stored as a Character Large Object (CLOB) in a Data Model.....	2-39
2.13.1	How the Data Is Returned.....	2-40
2.13.1.1	Additional Notes on Data Sets Using CLOB Column Data	2-41
2.13.2	Handling XHTML Data Stored in a CLOB Column.....	2-41
2.13.2.1	Retrieving XHTML Data Wrapped in CDATA.....	2-41
2.13.2.2	Wrapping the XHTML Data in CDATA in the Query	2-42
2.14	Creating a Data Set from an HTTP XML Feed	2-42
2.14.1	Additional Information on Data Sets Created from HTTP XML Feed	2-43
2.15	Creating a Data Set from an Oracle Endeca Query.....	2-43
2.15.1	Additional Notes on Oracle Endeca Query Data Sets.....	2-44
2.16	Testing Data Models and Generating Sample Data.....	2-44
2.17	Including User Information Stored in System Variables in Your Report Data	2-46
2.17.1	Adding the User System Variables as Elements	2-46
2.17.2	Sample Use Case: Limit the Returned Data Set by User ID	2-47
2.17.2.1	Creating Bind Variables from LDAP User Attribute Values	2-47
2.17.2.1.1	Prerequisite.....	2-47
2.17.2.1.2	How BI Publisher Constructs the Bind Variable	2-47

3 Structuring Data

3.1	Working with Data Models	3-1
3.1.1	About Multipart Unrelated Data Sets.....	3-1
3.1.2	About Multipart Related Data Sets	3-2
3.1.3	Guidelines for Working with Data Sets.....	3-3
3.2	Features of the Data Model Editor	3-4
3.3	About the Interface	3-5
3.4	Creating Links Between Data Sets.....	3-7
3.4.1	About Element-Level Links.....	3-7
3.4.2	About Group-Level Links.....	3-7
3.5	Creating Element-Level Links.....	3-8
3.5.1	Deleting Element-Level Links.....	3-9
3.6	Creating Group-Level Links.....	3-10
3.6.1	Deleting Group-Level Links.....	3-11
3.7	Creating Subgroups.....	3-11
3.8	Moving an Element Between a Parent Group and a Child Group	3-12
3.9	Creating Group-Level Aggregate Elements.....	3-13
3.10	Creating Group Filters	3-16
3.11	Performing Element-Level Functions	3-17
3.12	Setting Element Properties	3-17
3.13	Sorting Data	3-18
3.14	Performing Group-Level Functions	3-19

3.14.1	The Group Action Menu.....	3-19
3.14.2	Editing the Data Set.....	3-20
3.14.3	Removing Elements from the Group.....	3-20
3.14.4	Editing the Group Properties.....	3-20
3.15	Performing Global-Level Functions.....	3-21
3.15.1	Adding a Global-Level Aggregate Function.....	3-21
3.15.2	Adding a Group-Level or Global-Level Element by Expression.....	3-22
3.15.3	Adding a Global-Level Element by PL/SQL.....	3-24
3.16	Using the Structure View to Edit Your Data Structure.....	3-24
3.16.1	Renaming Elements.....	3-25
3.16.2	Adding Value for Null Elements.....	3-25
3.17	Function Reference.....	3-25

4 Adding Parameters and Lists of Values

4.1	About Parameters.....	4-1
4.2	Adding a New Parameter.....	4-2
4.2.1	Defining a Text Parameter.....	4-4
4.2.2	Defining a Menu Parameter.....	4-5
4.2.2.1	Customizing the Display of Menu Parameters.....	4-7
4.2.3	Defining a Date Parameter.....	4-7
4.3	About Lists of Values.....	4-8
4.4	Adding Lists of Values.....	4-8
4.4.1	Creating a List from a SQL Query.....	4-9
4.4.2	Creating a List from a Fixed Data Set.....	4-11
4.5	Adding Flexfield Parameters.....	4-12
4.5.1	Prerequisites for Using Flexfields.....	4-12
4.5.2	Adding a Flexfield Parameter and List of Values.....	4-12
4.5.2.1	Adding the Flexfield List of Values.....	4-13
4.5.2.2	Adding the Menu Parameter for the Flexfield List of Values.....	4-13
4.5.2.3	Using the Flexfield Parameter to Pass Values to a Flexfield Defined in the Data Model.....	4-14
4.5.2.4	Referencing the Flexfield in the SQL Query.....	4-15
4.5.2.5	Passing a Range of Values.....	4-16

5 Adding Event Triggers

5.1	About Triggers.....	5-1
5.2	Adding Before Data and After Data Triggers.....	5-1
5.2.1	Order of Execution.....	5-2
5.3	Creating Schedule Triggers.....	5-2

6 Adding Flexfields

6.1	About Flexfields.....	6-1
6.2	Adding Flexfields.....	6-2
6.2.1	Entering Flexfield Details.....	6-2

7 Adding Bursting Definitions

7.1	About Bursting	7-1
7.2	What is the Bursting Definition?.....	7-2
7.3	Adding a Bursting Definition to Your Data Model	7-2
7.4	Defining the Query for the Delivery XML	7-4
7.5	Passing a Parameter to the Bursting Query	7-7
7.6	Defining the Split By and Deliver By Elements for a CLOB/XML Data Set.....	7-9
7.7	Configuring a Report to Use a Bursting Definition	7-10
7.8	Sample Bursting Query	7-11
7.9	Creating a Table to Use as a Delivery Data Source.....	7-11

Index

Preface

Welcome to Release 11g (11.1.1) of the *Oracle Fusion Middleware Data Modeling Guide for Oracle Business Intelligence Publisher*. Oracle BI Publisher is an enterprise reporting solution for authoring, managing, and delivering all your highly formatted documents, such as operational reports, electronic funds transfer documents, government PDF forms, shipping labels, checks, sales and marketing letters, and much more.

Intended Audience

The *Oracle Fusion Middleware Data Modeling Guide for Oracle Business Intelligence Publisher* (this guide) describes how report developers use BI Publisher's data model editor to fetch and structure the data for use in the many different types of report layouts that BI Publisher supports. The following table provides more information about using BI Publisher for other business roles.

Role	Sample Tasks	Guide
Administrator	Configuring Security Configuring System Settings Diagnosing and Monitoring System Processes	<i>Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher</i>
Application developer or integrator	Integrating BI Publisher into existing applications using the application programming interfaces	<i>Oracle Fusion Middleware Developer's Guide for Oracle Business Intelligence Publisher</i>
Report consumer	Viewing reports Scheduling report jobs Managing report jobs	<i>Oracle Fusion Middleware User's Guide for Oracle Business Intelligence Publisher</i>
Report designer	Creating report definitions Designing layouts	<i>Oracle Fusion Middleware Report Designer's Guide for Oracle Business Intelligence Publisher</i>

Documentation Accessibility

For information about Oracle's commitment to accessibility, visit the Oracle Accessibility Program website at <http://www.oracle.com/pls/topic/lookup?ctx=acc&id=docacc>.

Access to Oracle Support

Oracle customers have access to electronic support through My Oracle Support. For information, visit

<http://www.oracle.com/pls/topic/lookup?ctx=acc&id=info> or visit <http://www.oracle.com/pls/topic/lookup?ctx=acc&id=trs> if you are hearing impaired.

Related Documentation and Other Resources

See the Oracle Business Intelligence documentation library for a list of related Oracle Business Intelligence documents.

In addition:

- Go to the Oracle Learning Library for Oracle Business Intelligence-related online training resources.
- Go to the Product Information Center Support note (Article ID 1338762.1) on My Oracle Support at <https://support.oracle.com>.

System Requirements and Certification

Refer to the system requirements and certification documentation for information about hardware and software requirements, platforms, databases, and other information. Both of these documents are available on Oracle Technology Network (OTN).

The system requirements document covers information such as hardware and software requirements, minimum disk space and memory requirements, and required system libraries, packages, or patches:

<http://www.oracle.com/technetwork/middleware/ias/downloads/fusion-requirements-100147.html>

The certification document covers supported installation types, platforms, operating systems, databases, JDKs, and third-party products:

<http://www.oracle.com/technetwork/middleware/ias/downloads/fusion-certification-100350.html>

Conventions

The following text conventions are used in this document:

Convention	Meaning
boldface	Boldface type indicates graphical user interface elements associated with an action, or terms defined in text or the glossary.
<i>italic</i>	Italic type indicates book titles, emphasis, or placeholder variables for which you supply particular values.
monospace	Monospace type indicates commands within a paragraph, URLs, code in examples, text that appears on the screen, or text that you enter.

New Features for Data Model Designers

This preface describes changes to Oracle BI Publisher data modeling features for Oracle Business Intelligence Publisher 11g Release 1 (11.1.1).

This preface contains the following topics:

- [New Features for Oracle BI Publisher 11g Release 1 \(11.1.1.7\)](#)
- [New Features for Oracle BI Publisher 11g Release 1 \(11.1.1.6\)](#)
- [New Features for Oracle BI Publisher 11g Release 1 \(11.1.1.5\)](#)
- [New Features for Oracle BI Publisher 11g Release 1 \(11.1.1.3\)](#)

New Features for Oracle BI Publisher 11g Release 1 (11.1.1.7)

This section describes new features for Oracle BI Publisher 11g Release 1 (11.1.1.7). It contains the following topics:

- [New Features for 11.1.1.7.16](#)
- [New Features for 11.1.1.7.10](#)
- [New Features for 11.1.1.7.0](#)

New Features for 11.1.1.7.16

Note: Information about Oracle BI Publisher 11g Release 1 (11.1.1.7.16 and later) is only applicable to customers using Oracle Fusion Applications 11g Release 9 (11.1.9) and to some customers using Oracle Fusion Applications 11g Release 8 (11.1.8).

New features for report data model developers in Oracle BI Publisher 11g Release 1 (11.1.1.7.16) include:

- [Support for Descriptive Flexfields](#)

Support for Descriptive Flexfields

Oracle Fusion Applications customers can now report on data stored in descriptive flexfields. For more information, see [Section 6.3, "Adding Descriptive Flexfields."](#)

New Features for 11.1.1.7.10

Note: Information about Oracle BI Publisher 11g Release 1 (11.1.1.7.10) is only applicable to customers using Oracle Fusion Applications 11g Release 8 (11.1.8).

New features for report data model developers in Oracle BI Publisher 11g Release 1 (11.1.1.7.10) include:

- [Support for Non-Standard SQL](#)
- [Support for Named, Shared Web Service as a Data Source](#)
- [Support for Named, Shared HTTP as a Data Source](#)

Support for Non-Standard SQL

The data engine now supports executing SQL statements that include anonymous blocks/procedure calls, conditional queries, and functions that return nested result sets or REF cursors. For more information, see [Section 2.3.2, "Creating Non-Standard SQL Data Sets."](#)

Support for Named, Shared Web Service as a Data Source

Previously, for web service-based data sets the connection to the web service was configured for each data set. This release introduces centrally administered web service connections. Web service connections set up by the administrator are available to data model developers through a list of values. Therefore data models can share the central connection and no longer require set up for each data set. For more information, see [Section 2.8, "Creating a Data Set Using a Web Service."](#)

Support for Named, Shared HTTP as a Data Source

Previously, for HTTP-based data sets the connection to the HTTP server was configured for each data set. This release introduces centrally administered HTTP connections. HTTP server connections set up by the administrator are available to data model developers through a list of values. Therefore data models can share the central connection and no longer require set up for each data set. For more information, see [Section 2.13, "Creating a Data Set from an HTTP XML Feed."](#)

New Features for 11.1.1.7.0

New features for report data model developers in Oracle BI Publisher 11g Release 1 (11.1.1.7.0) include:

- [MDX Query Builder](#)
- [Support for Local XML File Data Source](#)
- [Support for CSV File as a Data Source](#)
- [Support for Endeca as a Data Source](#)
- [Support for Private Data Sources](#)
- [Enhancements for Sample Data Usability](#)

MDX Query Builder

You can now use the MDX Query Builder to build a MDX query by selecting OLAP cube dimension members for Column, Row, Page, & slicer (for Point of View) axes. This feature enables you to build member selections in the MDX query by using

specific members, relations such as children and descendants, and layers such as levels and generations. For more information, see [Section 2.4, "Creating a Data Set Using a MDX Query Against an OLAP Data Source."](#)

Support for Local XML File Data Source

You can now use a locally stored XML or shared XML file as data source for data sets. This file can then be refreshed on demand from the data model definition. For more information, see [Section 2.10, "Creating a Data Set Using a XML File."](#)

Support for CSV File as a Data Source

You can now use a locally stored CSV or shared CSV file as data source for data sets. This file can then be refreshed on demand from the data model definition. For more information, see [Section 2.12, "Creating a Data Set Using a CSV File."](#)

Support for Endeca as a Data Source

You can now use Endeca as a data source. For more information, see [Section 2.14, "Creating a Data Set from an Oracle Endeca Query."](#)

Support for Private Data Sources

You can now use private JDBC or ODBC data source connections to create a data set with a BI Publisher data model. For more information, see [Section 1.8, "Managing Private Data Sources."](#)

Enhancements for Sample Data Usability

You can now view and save data model results on the new View tab without browser dependencies. These improvements are intended to make working with sample data in BI Publisher easier and more consistent.

New Features for Oracle BI Publisher 11g Release 1 (11.1.1.6)

New features for report data model developers in Oracle BI Publisher 11g Release 1 (11.1.1.6) include:

- [Schedule Triggers for Event-Driven Schedules](#)
- [Enhancements to Parameter Display Options](#)
- [Support for HTML Formatting in Data](#)

Schedule Triggers for Event-Driven Schedules

The execution of a scheduled report job can now be conditionalized based on an event. A report data model supports a new type of trigger called a Schedule Trigger. The schedule trigger that you create in the data model can then be enabled in the report job schedule. When the report job is scheduled to run, the trigger is executed. If no data is returned from the trigger, the job instance is skipped. If data is returned, the job instance runs as scheduled. For more information, see [Section 5.3, "Creating Schedule Triggers."](#)

Enhancements to Parameter Display Options

Enhancements to parameter display options include:

- Support for radio button and check box display of values

Parameters that are defined as a menu in the data model can now be configured to display the menu options as a list of radio buttons or check boxes. Parameters

configured to support one value support the option to display as radio buttons. Parameters configured to support multiple values support the option to display as check boxes.

- New options for placement of parameters in the report viewer
Previously the report viewer always displayed the parameters in a horizontal region across the top of the viewer. In this release, the display of the parameter region can also be configured in one of the following ways:
 - In a vertical region along the right side of the viewer
 - As a dialog
 - As a separate full page
- New report viewer toolbar button to show or hide parameters
This release adds a toolbar button to the report viewer to enable users to hide or show the parameter region. This enhancement complements the new parameter display options. When report parameters are configured to display as a dialog or in a separate full page, the parameter display region is dismissed when the viewer displays the report. Use the **Parameters** button to redisplay the parameter region to make new selections.
- Search added to menus
All parameter menus having more than a specified number of options provide a Search option.
- Option to remove the **Apply** button
Reports can now be configured to remove the parameter **Apply** button. In these reports the action of selecting a new parameter value automatically reruns the report.

Support for HTML Formatting in Data

You can now convert stored XHTML to XSL-FO to display the HTML formatting from your data in your generated report. The XHTML data must be extracted wrapped in a CDATA section. Specific syntax must also be used in the RTF template to render it. For more information, see [Section 2.15.2, "Handling XHTML Data Stored in a CLOB Column."](#)

New Features for Oracle BI Publisher 11g Release 1 (11.1.1.5)

New features in Oracle BI Publisher 11g Release 1 (11.1.1.5) include:

- [Support for CLOB as XML](#)
- [Upload Local Microsoft Excel File as Data Source](#)
- [Use LDAP Attributes as Bind Variables in Data Queries](#)

Support for CLOB as XML

The data engine can now extract well-formed XML data stored in a database column as a character large object (CLOB) data type and maintain its structure. This feature enables you to use XML data generated by a separate process and stored in your database as input to a BI Publisher data model. For more information, see [Section 2.15, "Using Data Stored as a Character Large Object \(CLOB\) in a Data Model."](#)

Upload Local Microsoft Excel File as Data Source

You can now upload a locally stored Excel file directly to a data model definition. This file can then be refreshed on demand from the data model definition. For more information, see [Section 2.11, "Creating a Data Set Using a Microsoft Excel File."](#)

Use LDAP Attributes as Bind Variables in Data Queries

LDAP attributes defined in the LDAP Security Model definition can be used as bind variables in data queries. For more information, see [Section 2.17.2.1, "Creating Bind Variables from LDAP User Attribute Values."](#)

New Features for Oracle BI Publisher 11g Release 1 (11.1.1.3)

New features in Oracle BI Publisher 11g Release 1 (11.1.1.3) include:

- [Major User Interface Improvements](#)
- [Shared BI Presentation Catalog](#)
- [Data Model Editor](#)
- [Data Model as a Sharable Object](#)
- [Support for Microsoft Excel File as a Data Source](#)
- [Support for View Object as a Data Source](#)

Major User Interface Improvements

The user interface has undergone major improvements in several areas, including a new Home page and redesigned editors and panes. These improvements are intended to make working with Oracle BI Publisher easier and more consistent. For information about working in the new interface, see *Oracle Fusion Middleware User's Guide for Oracle Business Intelligence Publisher*.

Shared BI Presentation Catalog

For installations of BI Publisher with the Oracle BI Enterprise Edition, BI Publisher now shares the same catalog with Oracle BI Presentation services. For information about the improved catalog, see *Oracle Fusion Middleware User's Guide for Oracle Business Intelligence Publisher*.

Data Model Editor

This release introduces the data model editor to create your report data models. The data model editor enables you to combine data from multiple data sets from different data sources, such as SQL, Excel files, Web services, HTTP feeds, and other applications into a single XML data structure. Data sets can either be unrelated or a relationship can be established between them using a data link. This guide describes in detail how to use the data model editor.

Data Model as a Sharable Object

The data model is saved as a distinct catalog object. This means that a single data model can now be used for multiple reports.

Support for Microsoft Excel File as a Data Source

A Microsoft Excel file can now be used to create a data set in a BI Publisher data model. For more information, see [Section 2.11, "Creating a Data Set Using a Microsoft Excel File."](#)

Support for View Object as a Data Source

BI Publisher enables you to connect to your custom applications built with Oracle Application Development Framework and use view objects in your applications as data sources for reports. For more information, see [Section 2.7, "Creating a Data Set Using a View Object."](#)

Using the Data Model Editor

This chapter describes the components and features supported by BI Publisher's data model editor.

This chapter includes the following sections:

- [Section 1.1, "What Is a Data Model?"](#)
- [Section 1.2, "Components of a Data Model"](#)
- [Section 1.3, "Features of the Data Model Editor"](#)
- [Section 1.4, "About the Data Source Options"](#)
- [Section 1.5, "Process Overview for Creating a Data Model"](#)
- [Section 1.6, "Launching the Data Model Editor"](#)
- [Section 1.7, "Setting Data Model Properties"](#)
- [Section 1.8, "Managing Private Data Sources"](#)

1.1 What Is a Data Model?

A data model is an object that contains a set of instructions for BI Publisher to retrieve and structure data for a report. Data models reside as separate objects in the catalog.

At the very simplest, a data model can be one data set retrieved from a single data source (for example, the data returned from the columns in the employees table). A data model can also be complex, including parameters, triggers, and bursting definitions as well as multiple data sets.

To build a data model, you use the data model editor.

1.2 Components of a Data Model

A data model supports the following components:

- **Data set**

A data set contains the logic to retrieve data from a single data source. A data set can retrieve data from a variety of data sources (for example, a database, an existing data file, a Web service call to another application, or a URL/URI to an external data provider). A data model can have multiple data sets from multiple sources.
- **Event triggers**

A trigger checks for an event. When the event occurs the trigger runs the PL/SQL code associated with it. The data model editor supports before data and after data triggers as well as schedule triggers. Before data and after data triggers consist of a call to execute a set of functions defined in a PL/SQL package stored in an Oracle database. A schedule trigger is executed for scheduled reports and tests for a condition that determines whether or not to run a scheduled report job.

- **Flexfields**

A flexfield is a structure specific to Oracle Applications. The data model editor supports retrieving data from flexfield structures defined in your Oracle Application database tables.

- **Lists of values**

A list of values is a menu of values from which report consumers can select parameter values to pass to the report.

- **Parameters**

A parameter is a variable whose value can be set at runtime. The data model editor supports several parameter types.

- **Bursting Definitions**

Bursting is a process of splitting data into blocks, generating documents for each data block, and delivering the documents to one or more destinations. A single bursting definition provides the instructions for splitting the report data, generating the document, and delivering the output to its specified destinations.

1.3 Features of the Data Model Editor

Use the data model editor to combine data from multiple data sets from different data sources, such as SQL, Excel files, Web services, HTTP feeds, and other applications into a single XML data structure. Data sets can either be unrelated or a relationship can be established between them using a data link.

The data model editor enables you to perform the following tasks:

- **Link data** — Define master-detail links between data sets to build a hierarchical data model.
- **Aggregate data** — Create group level totals and subtotals.
- **Transform data** — Modify source data to conform to business terms and reporting requirements.
- **Create calculations** — Compute data values that are required for your report that are not available in the underlying data sources.

1.4 About the Data Source Options

BI Publisher supports a variety of data source types for creating data sets. These can be categorized into three general types:

The first type are data sets for which BI Publisher can retrieve metadata information from the source. For these data set types, the full range of data model editor functions is supported. These data set types are:

- SQL queries submitted against Oracle BI Server, an Oracle database, or other supported databases

See [Section 2.3, "Creating a Data Set Using a SQL Query."](#)

For information on supported databases, see [System Requirements and Certification](#).

- Multidimensional (MDX) queries against an OLAP data source
See [Section 2.4, "Creating a Data Set Using a MDX Query Against an OLAP Data Source."](#)
- Queries against your LDAP repository to retrieve user data
You can report on this data directly, or join this to data retrieved from other sources. See [Section 2.9, "Creating a Data Set Using an LDAP Query."](#)
- Microsoft Excel spreadsheet data sources
The Excel spreadsheet can be either stored in a file directory set up as a data source by your administrator; or you can upload it directly from a local source to the data model. See [Section 2.11, "Creating a Data Set Using a Microsoft Excel File."](#)
- XML data file data sources
The XML file can be either stored in a file directory set up as a data source by your administrator; or you can upload it directly from a local source to the data model. See [Section 2.10, "Creating a Data Set Using a XML File."](#)
- CSV (comma separated value) file data sources
The CSV file can be either stored in a file directory set up as a data source by your administrator; or you can upload it directly from a local source to the data model. See [Section 2.12, "Creating a Data Set Using a CSV File."](#)

For the second type, BI Publisher can retrieve column names and data type information from the data source but it cannot process or structure the data. For these data set types, only a subset of the full range of data model editor functions is supported. These data set types are:

- Oracle BI Analyses
See [Section 2.6, "Creating a Data Set Using an Oracle BI Analysis."](#)
- View objects created using Oracle Application Development Framework (ADF)
See [Section 2.7, "Creating a Data Set Using a View Object."](#)
- Oracle Endeca
See [Section 2.14, "Creating a Data Set from an Oracle Endeca Query."](#)

For the third type, BI Publisher retrieves data that has been generated and structured at the source and no additional modifications can be applied by the data model editor. These data set types are:

- HTTP XML feeds off the Web
See [Section 2.13, "Creating a Data Set from an HTTP XML Feed."](#)
- Web services
See [Section 2.8, "Creating a Data Set Using a Web Service."](#)
Supply the Web service WSDL to BI Publisher and then define the parameters in BI Publisher to use a Web service to return data for the report.

1.5 Process Overview for Creating a Data Model

[Table 1–1](#) lists the process overview for creating a data model.

Table 1–1 Process of Creating a Data Model

Step	Reference
Launch the data model editor.	Section 1.6, "Launching the Data Model Editor"
Set properties for the data model. (Optional)	Section 1.7, "Setting Data Model Properties"
Create the data sets for the data model.	Chapter 2, "Creating Data Sets"
Define the data output structure. (Optional)	Chapter 3, "Structuring Data"
Define the parameters to pass to the query, and define lists of values for users to select parameter values. (Optional)	Section 4, "Adding Parameters and Lists of Values"
Define Event Triggers. (Optional)	Section 5.1, "About Triggers"
(Oracle Applications Only) Define Flexfields. (Optional)	Chapter 6, "Adding Flexfields"
Test your data model and add sample data.	Section 2.16, "Testing Data Models and Generating Sample Data"
Add a bursting definition. (Optional)	Chapter 7, "Adding Bursting Definitions"

1.6 Launching the Data Model Editor

Launch the data model editor from the BI Publisher global header or Home page in one of the following ways:

To launch the Data Model Editor from the global header:


1. Click **New** and then click **Data Model** to open the data model editor.

To launch the Data Model Editor from the Home page:

1. Under the **Create** region, click **Data Model**.

The Data Sets page is the default page displayed as shown in [Figure 1–2](#).

Figure 1–1 Data Sets Page



1.6.1 About the Data Model Editor Interface

The data model editor is designed with a component pane on the left and work pane on the right. Selecting a component on the left pane launches the appropriate fields for the component in the work area.


The data model editor toolbar, shown in [Figure 1–2](#), provides the following functions:

Figure 1–2 Data Model Editor Toolbar

- **Manage Private Data Sources** — Launches the Manage Private Data Sources dialog to create a private data source connection for use in SQL data sets.
- **View Data** — Displays the Data tab where you view and generate sample data.
- **Create Report** — Launches the Report Wizard to create a report and automatically populates the Data Model field with the current data model name.
- **Save / Save As** — Select **Save** to save your work in progress to the existing data model object or select **Save As** to save the data model as a new object in the catalog.
- **Help** — View online help for the data model editor.

1.7 Setting Data Model Properties

To access the Data Model Properties page as shown in [Figure 1–3](#), click the **Data Model** node in the components pane.

Figure 1–3 Data Model Properties

Enter the following properties for the data model:

Description — The description that you enter here displays in the catalog. This description is translatable.

Default Data Source — Select the data source from the list. Data models can include multiple data sets from one or more data sources. The default data source you select here is presented as the default for each new SQL data set you define. Select **Refresh Data Source List** to see any new data sources added since your session was initiated.

Oracle DB Default Package — If you define a query against an Oracle database, then you can include before or after data triggers (event triggers) in your data model. Event triggers make use of PL/SQL packages to execute RDBMS level functions. For data

models that include event triggers or a PL/SQL group filter, you must enter a default PL/SQL package here. The package must exist on the default data source.

Database Fetch Size — Sets the number of rows fetched at a time through the JDBC connection. This value overrides the value set in the system properties. If neither this value nor the server setting is defined, then a default value of 100 is used.

For more information, see "Setting General Properties" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.

Enable Scalable Mode — Processing large data sets requires the use of large amounts of RAM. To prevent running out of memory, activate scalable mode for the data engine. In scalable mode, the data engine takes advantage of disk space when it processes the data.

Backup Data Source — If you have set up a backup database for this data source, select **Enable Backup Connection** to enable the option; then select it when you want BI Publisher to use the backup.

- To use the backup data source only when the primary is down, select **Switch to Backup Data Source when Primary Data Source is unavailable**. Note that when the primary data source is down, the data engine must wait for a response before switching to the backup.
- To always use the backup data source when executing this data model, select **Use Backup Data Source Only**. Using the backup database may enhance performance.

Note: This feature requires that a backup data source has been enabled for the selected data source. For more information, see "About Backup Databases" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.

1.7.1 XML Output Options

These options define characteristics of the XML data structure. Note that any changes to these options can impact layouts that are built on the data model.

- **Include Parameter Tags** — If you define parameters for your data model, select this box to include the parameter values in the XML output file. See [Section 4, "Adding Parameters and Lists of Values"](#) for information on adding parameters to your data model. Enable this option when you want to use the parameter value in the report.
- **Include Empty Tags for Null Elements** — Select this box to include elements with null values in your output XML data. When you include a null element, then a requested element that contains no data in your data source is included in your XML output as an empty XML tag as follows: <ELEMENT_ID\>. For example, if the element MANAGER_ID contained no data and you chose to include null elements, it would appear in your data as follows: <MANAGER_ID />. If you do not select this option, no entry appears for MANAGER_ID.
- **Include Group List Tag** — (This property is for 10g backward compatibility and Oracle Report migration.) Select this box to include the rowset tags in your output XML data. If you include the group list tags, then the group list appears as another hierarchy within your data.
- **XML Tag Display** — Select whether to generate the XML data tags in upper case, in lower case, or to preserve the definition you supplied in the data structure.

1.7.2 Attachments to the Data Model

The Attachment region of the page displays data files that you have uploaded or attached to the data model.

1.7.2.1 Attaching Sample Data

After you build your data model, it is required that you attach a small, but representative set of sample data generated from your data model. The sample data is used by BI Publisher's layout editing tools. Using a small sample file helps improve performance during the layout design phase.

The data model editor provides an option to generate and attach the sample data. For more information, see [Section 2.16, "Testing Data Models and Generating Sample Data."](#)

1.7.2.2 Attaching Schema


The data model editor enables you to attach sample schema to the data model definition. The schema file is not used by BI Publisher, but can be attached for developer reference. The data model editor does not support schema generation.

1.7.2.3 Data Files

If you have uploaded a local Microsoft Excel, CSV, or XML file as a data source for this report, the file displays here. Use the refresh button to refresh this file from the local source. For information on uploading files to use as data sources, see [Chapter 2, "Creating Data Sets"](#).

[Figure 1-4](#) shows the Attachments region with sample data and data files attached:

Figure 1-4 Attachments Region with Attached Sample Data and Files




1.8 Managing Private Data Sources

Data model developers can create and manage private JDBC, OLAP, Web service, and HTTP data source connections without having to depend on an Administrator user. However, Administrator users can still view, modify, and delete private data source connections, if needed.

To create a private data source connection:

1. From the data model editor toolbar, click **Manage Private Data Sources**.
2. Select the connection type tab, and click **Add Data Source** as shown in [Figure 1-5](#).

Figure 1–5 Creating Private Data Source Connections

Note: If you are logged in as an Administrator, all data source connections will display for you in this dialog; however, you can only create or modify JDBC, OLAP, HTTP, and web service data sources from this dialog.

3. Enter the private connection name, and the required fields.
4. Click **Test Connection**. A confirmation is displayed.
5. Click **Apply**. The private data source connection is now available for use in your data sets.

Private data source connections are identified by the word (Private) appended to the end of the data source name. For example, if you create a private JDBC connection called My JDBC Connection, it is displayed as My JDBC Connection (Private) in the data source drop-down lists.

If your user has the Administrator role, you can only create public data sources, even if you create the data source from the Manage Private Data Sources page. For more information about private data source connections, see "About Private Data Source Connections" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.

For more information on setting up the data source types, see "Setting Up Data Sources" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.

Creating Data Sets

This chapter describes creating data sets, testing data models, and saving sample data in BI Publisher.

This chapter includes the following sections:

- [Section 2.1, "Overview of Creating Data Sets"](#)
- [Section 2.2, "Editing an Existing Data Set"](#)
- [Section 2.3, "Creating a Data Set Using a SQL Query"](#)
- [Section 2.4, "Creating a Data Set Using a MDX Query Against an OLAP Data Source"](#)
- [Section 2.5, "Using MDX Query Builder"](#)
- [Section 2.6, "Creating a Data Set Using an Oracle BI Analysis"](#)
- [Section 2.7, "Creating a Data Set Using a View Object"](#)
- [Section 2.8, "Creating a Data Set Using a Web Service"](#)
- [Section 2.9, "Creating a Data Set Using an LDAP Query"](#)
- [Section 2.10, "Creating a Data Set Using a XML File"](#)
- [Section 2.11, "Creating a Data Set Using a Microsoft Excel File"](#)
- [Section 2.12, "Creating a Data Set Using a CSV File"](#)
- [Section 2.13, "Creating a Data Set from an HTTP XML Feed"](#)
- [Section 2.14, "Creating a Data Set from an Oracle Endeca Query"](#)
- [Section 2.15, "Using Data Stored as a Character Large Object \(CLOB\) in a Data Model"](#)
- [Section 2.16, "Testing Data Models and Generating Sample Data"](#)
- [Section 2.17, "Including User Information Stored in System Variables in Your Report Data"](#)


2.1 Overview of Creating Data Sets

Oracle BI Publisher can retrieve data from multiple types of data sources.

To create a data set:


1. On the component pane of the data model editor, click **New Data Set** as shown in [Figure 2-1](#).

Figure 2–1 Creating a Data Set



2. Select the data set type from the list to launch the appropriate dialog, as shown in [Figure 2–2](#).

Figure 2–2 Selecting the Data Set Type



3. Complete the required fields to create the data set. See the corresponding section in this chapter for information on creating each data set type.
 - [Section 2.3, "Creating a Data Set Using a SQL Query"](#)
 - [Section 2.4, "Creating a Data Set Using a MDX Query Against an OLAP Data Source"](#)
 - [Section 2.6, "Creating a Data Set Using an Oracle BI Analysis"](#)
 - [Section 2.7, "Creating a Data Set Using a View Object"](#)
 - [Section 2.8, "Creating a Data Set Using a Web Service"](#)
 - [Section 2.9, "Creating a Data Set Using an LDAP Query"](#)
 - [Section 2.10, "Creating a Data Set Using a XML File"](#)
 - [Section 2.11, "Creating a Data Set Using a Microsoft Excel File"](#)
 - [Section 2.12, "Creating a Data Set Using a CSV File"](#)
 - [Section 2.13, "Creating a Data Set from an HTTP XML Feed"](#)
 - [Section 2.14, "Creating a Data Set from an Oracle Endeca Query"](#)

- [Section 2.15, "Using Data Stored as a Character Large Object \(CLOB\) in a Data Model"](#)

2.2 Editing an Existing Data Set

To edit an existing data set:

1. On the component pane of the data model editor click **Data Sets**. All data sets for this data model display in the working pane.
2. Click the data set that you want to edit.
3. Click **Edit Selected Data Set**. The dialog for the data set opens. For information about each type of data set, see the corresponding section in this chapter.
4. Make changes to the data set and click **OK**.
5. Save the data model.
6. Test your edited data model and add new sample data. See [Section 2.16, "Testing Data Models and Generating Sample Data"](#) for more information about testing and generating sample data.

2.3 Creating a Data Set Using a SQL Query

This section includes the following topics:

- [Section 2.3.1, "Entering SQL Queries"](#)
- [Section 2.3.2, "Creating Non-Standard SQL Data Sets"](#)
- [Section 2.3.3, "Using the SQL Query Builder"](#)
- [Section 2.3.4, "Adding a Bind Variable to a Query"](#)
- [Section 2.3.5, "Adding Lexical References to SQL Queries"](#)
- [Section 2.3.6, "Defining SQL Queries Against the Oracle BI Server"](#)


2.3.1 Entering SQL Queries

Note: Release 11.1.1.7.10 adds support for more complex SQL queries and introduces the "Type of SQL" menu selection. This feature may not be available in earlier versions of BI Publisher. For more information about Oracle BI Publisher 11.1.1.7.10, see "[New Features for 11.1.1.7.10](#)."

To enter a SQL query:

1. Click **New Data Set** and then click **SQL Query**. The Create Data Set - SQL dialog opens, as shown in [Figure 2-3](#).

Figure 2-3 New Data Set - SQL Query Dialog



2. Enter a name for the data set.
3. The data source defaults to the default data source that you selected on the Properties page. If you are not using the default data source for this data set, select the **Data Source** from the list.

You can also use your private data source connections as data sources for SQL query data sets. See [Section 1.8, "Managing Private Data Sources"](#) for information about private data source connections.

4. The SQL type defaults to **Standard SQL** used for normal SELECT statements interpreted to understand database schema. See [Section 2.3.2, "Creating Non-Standard SQL Data Sets"](#) for information on using other types of SQL.
5. Enter the SQL query or click **Query Builder** to launch the Query Builder page. See [Section 2.3.3, "Using the SQL Query Builder"](#) for more information about the Query Builder utility.
6. If you are using Flexfields, bind variables, or other special processing in your query, edit the SQL returned by the Query Builder to include the required statements.

Note: If you include lexical references for text that you embed in a SELECT statement, then you must substitute values to get a valid SQL statement.

7. After entering the query, click **OK** to save. For Standard SQL queries the data model editor validates the query.

If your query includes a bind variable, you are prompted to create the bind parameter. Click **OK** to have the data model editor create the bind parameter.

See [Chapter 4, "Adding Parameters and Lists of Values"](#) for more information on editing parameters.


2.3.2 Creating Non-Standard SQL Data Sets

In addition to creating data sets using basic SQL commands, you can create data sets using more complex commands as follows:

Procedure Call

Use this query type to call a database procedure. For example, for PL/SQL for Oracle, statements start with BEGIN. Note that when you use this SQL data type, no metadata is displayed on the data model structure tab, therefore you cannot modify the data structure or data fields. To construct your SQL with a procedure call either enter the code directly in the text box or copy and paste from another SQL editor; the Query Builder cannot be used to modify or build these types of queries.

Figure 2–4 Procedure Call SQL Type



Non-standard SQL

Use this query type to issue SQL statements that can include the following:

- Cursor statements that return nested results sets

For example:

```

Ex:SELECT TO_CHAR(sysdate,'MM-DD-YYYY') CURRENT_DATE ,
CURSOR
  (SELECT d.order_id department_id,
        d.order_mode department_name ,
        CURSOR
          (SELECT e.cust_first_name first_name,
                e.cust_last_name last_name,
                e.customer_id employee_id,
                e.date_of_birth hire_date
          FROM customers e
          WHERE e.customer_id IN (101,102)
          ) emp_cur
    FROM orders d
    WHERE d.customer_id IN (101,102)
  ) DEPT_CUR FROM dual

```

- Functions returning REF cursors

For example:

```

create or replace PACKAGE REF_CURSOR_TEST AS
  TYPE refcursor IS REF CURSOR;
  pCountry VARCHAR2(10);
  pState VARCHAR2(20);
  FUNCTION GET( pCountry IN VARCHAR2, pState IN VARCHAR2) RETURN REF_CURSOR_
TEST.refcursor;
  END;

create or replace PACKAGE BODY REF_CURSOR_TEST AS
FUNCTION GET(
  pCountry IN VARCHAR2,
  pState IN VARCHAR2)
RETURN REF_CURSOR_TEST.refcursor
IS
  l_cursor REF_CURSOR_TEST.refcursor;
BEGIN
  IF ( pCountry = 'US' ) THEN
    OPEN l_cursor FOR
      SELECT TO_CHAR(sysdate,'MM-DD-YYYY') CURRENT_DATE ,
             d.order_id department_id,
             d.order_mode department_name
      FROM orders d
      WHERE d.customer_id IN (101,102);
  ELSE
    OPEN l_cursor FOR
      SELECT * FROM EMPLOYEES;
  END IF;
  RETURN l_cursor;
END GET;
END REF_CURSOR_TEST;

```

To use REF cursor in BI Publisher:

```

create SQL dataset with query as SELECT REF_CURSOR_TEST.GET(:PCNTRY, :PSTATE)
AS CURDATA FROM DUAL

```

- Anonymous blocks/Stored procedures

BI Publisher supports executing PL/SQL anonymous blocks. You can write DML or DDL commands, populate temp tables, or perform calculations in the PL/SQL block and return the result set. BI Publisher uses callable statements to execute anonymous blocks.

Note the following requirements:

- The PL/SQL block must return a result set of type REF cursor
- You must declare the out variable with name "xdo_cursor"; if not, the first bind variable is treated as an out variable type and binds with REF cursor
- Declare the data model parameter with name "xdo_cursor". This name is reserved for out variable type for procedure/anonymous blocks.

Example:

```

DECLARE
  type refcursor is REF CURSOR;
  xdo_cursor refcursor;
  empno number;

```

```

BEGIN
  INSERT into procTest values (:P1);
  UPDATE EMPLOYEES SET COMMISSION_PCT = .28
  WHERE EMPLOYEE_ID = :P2;
  OPEN :xdo_cursor FOR
  SELECT *
  FROM procTest d, EMPLOYEES E
  WHERE E.EMPLOYEE_ID = :P2;
  COMMIT;
END;

```

- Conditional queries can be executed if you use an if-else expression. You can define multiple SQL queries in a single data set, but only one query will execute at run time depending on the expression value. The expression validates and returns a boolean value, which if true, executes that section of the SQL query.

Note the following limitations:

- The following syntax is supported to evaluate expressions: \$if{, \$elseif{, \$else{
- The expression must return true, false
- Only the following operators are supported:

```

== <= >= < >

```

Example:


```

create sql dataset with following query
$if{ (:P_MODE == PRODUCT) }$
  SELECT PRODUCT_ID
  , PRODUCT_NAME
  , CATEGORY_ID
  , SUPPLIER_ID
  , PRODUCT_STATUS
  , LIST_PRICE
  FROM PRODUCT_INFORMATION
  WHERE ROWNUM < 5
$elseif{ (:P_MODE == ORDER ) }$
  SELECT ORDER_ID
  , ORDER_DATE
  , ORDER_MODE
  , CUSTOMER_ID
  , ORDER_TOTAL
  , SALES_REP_ID
  FROM ORDERS
  WHERE ROWNUM < 5
$else{
  SELECT PRODUCT_ID
  , WAREHOUSE_ID
  , QUANTITY_ON_HAND
  FROM INVENTORIES
  WHERE ROWNUM < 5
}$
$endif$

```

When your data set is created using non-standard SQL statements, no metadata is displayed on the data model structure tab, therefore you cannot modify the data structure or data fields. The Query Builder cannot be used to modify or build these types of queries.

Figure 2–5 shows a sample Non-standard SQL query.

Figure 2–5 Non-standard SQL Query

2.3.3 Using the SQL Query Builder

Use the Query Builder to build SQL queries without coding. The Query Builder enables you to search and filter database objects, select objects and columns, create relationships between objects, and view formatted query results with minimal SQL knowledge.

This section describes how to use the Query Builder and includes the following topics:

- [Section 2.3.3.1, "Overview of the Query Builder"](#)
- [Section 2.3.3.2, "Understanding the Query Builder Process"](#)
- [Section 2.3.3.3, "Using the Object Selection Pane"](#)
- [Section 2.3.3.4, "Selecting a Schema"](#)
- [Section 2.3.3.5, "Searching and Filtering Objects"](#)
- [Section 2.3.3.6, "Selecting Objects"](#)
- [Section 2.3.3.7, "Supported Column Types"](#)
- [Section 2.3.3.8, "Adding Objects to the Design Pane"](#)
- [Section 2.3.3.9, "Resizing the Design and Results Pane"](#)
- [Section 2.3.3.10, "Removing or Hiding Objects in the Design Pane"](#)
- [Section 2.3.3.11, "Specifying Query Conditions"](#)
- [Section 2.3.3.12, "Creating Relationships Between Objects"](#)
- [Section 2.3.3.13, "Saving a Query"](#)
- [Section 2.3.3.14, "Editing a Saved Query"](#)


2.3.3.1 Overview of the Query Builder

The Query Builder page is divided into two sections:

- Object Selection pane contains a list of objects from which you can build queries. Only objects in the current schema display.

- Design and output pane consists of four tabs:
 - **Model** — Displays selected objects from the Object Selection pane.
 - **Conditions** — Enables you to apply conditions to your selected columns.
 - **SQL** — Displays the query.
 - **Results** — Displays the results of the query.

Figure 2–6 Design and Output Pane



2.3.3.2 Understanding the Query Builder Process

To build a query, perform the following steps:

1. Select objects from the Object Selection pane.
2. Add objects to the Design pane and select columns.
3. (Optional) Establish relationships between objects.
4. Add a unique alias name for any duplicate column.
5. (Optional) Create query conditions.
6. Execute the query and view results.

2.3.3.3 Using the Object Selection Pane

In the Object Selection pane you can select a schema and search and filter objects.

To hide the Object Selection pane, select the control bar located between it and the Design pane. Select it again to unhide it.

2.3.3.4 Selecting a Schema

The Schema list contains all the available schemas in the data source. Note that you may not have access to all that are listed.

2.3.3.5 Searching and Filtering Objects

Use the Search field to enter a search string. Note that if more than 100 tables are present in the data source, you must use the Search feature to locate and select the desired objects.

2.3.3.6 Selecting Objects

The Object Selection pane lists the tables, views, and materialized views from the selected schema (for Oracle databases, synonyms are also listed). Select the object from the list and it displays on the Design pane. Use the Design pane to identify how the selected objects are used in the query.

2.3.3.7 Supported Column Types

Columns of all types display as objects in the Design pane. Note the following column restrictions:

- You can select no more than 60 columns for each query.
- Only the following column types are selectable:
 - VARCHAR2, CHAR
 - NUMBER
 - DATE, TIMESTAMP

Note: The data type `TIMESTAMP WITH LOCAL TIMEZONE` is not supported.

- Binary Large Object (BLOB)

Note: The BLOB must be an image. When you execute the query in the Query Builder, the BLOB does not display in the Results pane; however, the query is constructed correctly when saved to the data model editor.

- Character Large Object (CLOB)

See [Section 2.15, "Using Data Stored as a Character Large Object \(CLOB\) in a Data Model"](#) for more information about working with CLOB data in the data model.

2.3.3.8 Adding Objects to the Design Pane

To add objects to the design pane:

1. Select an object.

The selected object displays in the Design pane. An icon representing the data type displays next to each column name.

2. Select the check box for each column to include in your query.

When you select a column, it appears on the **Conditions** tab. Note that the **Show** check box on the **Conditions** tab controls whether a column is included in query results. By default, this check box is selected.

To select the first twenty columns, click the small icon in the upper left corner of the object and then select **Check All**.

3. To execute the query and view results, select **Results**.

Tip: You can also execute a query using the key strokes CTRL + ENTER.

2.3.3.9 Resizing the Design and Results Pane

As you select objects, you can resize the Design and Results panes by selecting and dragging the gray horizontal rule dividing the page.

2.3.3.10 Removing or Hiding Objects in the Design Pane

To remove an object:

1. Click **Remove** in the upper right corner of the object.

To temporarily hide the columns within an object:

1. Click **Show/Hide Columns**.

2.3.3.11 Specifying Query Conditions

Conditions enable you to filter and identify the data you want to work with. As you select columns within an object, you can specify conditions on the Conditions tab. You can use these attributes to modify the column alias, apply column conditions, sort columns, or apply functions. [Figure 2-7](#) shows the **Conditions** tab.

Figure 2-7 Conditions Tab

Column	Alias	Object	Condition	Sort Type	Sort Order
EMPLOYEE_ID	EMPLOYEE_ID	EMPLOYEES		ASC	<input type="checkbox"/>
FIRST_NAME	FIRST_NAME	EMPLOYEES		ASC	<input type="checkbox"/>
LAST_NAME	LAST_NAME	EMPLOYEES		ASC	<input type="checkbox"/>
HIRE_DATE	HIRE_DATE	EMPLOYEES		ASC	<input type="checkbox"/>
SALARY	SALARY	EMPLOYEES		ASC	<input type="checkbox"/>
MANAGER_ID	MANAGER_ID	EMPLOYEES		ASC	<input type="checkbox"/>
DEPARTMENT_NAME	DEPARTMENT_NAME	DEPARTMENTS		ASC	<input type="checkbox"/>
DEPARTMENT_ID	DEPARTMENT_ID	EMPLOYEES		ASC	<input type="checkbox"/>
LAST_NAME	LAST_NAME_1	EMPLOYEES_1		ASC	<input type="checkbox"/>

[Table 2-1](#) describes the attributes available on the **Conditions** tab.

Table 2-1 Attributes Available on the Conditions Tab

Condition Attribute	Description
Up and Down Arrows	Controls the display order of the columns in the resulting query.
Column	Displays the column name.

Table 2–1 (Cont.) Attributes Available on the Conditions Tab

Condition Attribute	Description
Alias	Specify an optional column alias. An alias is an alternative column name. Aliases are used to make a column name more descriptive, to shorten the column name, or prevent possible ambiguous references. Note that multibyte characters are not supported in the alias name.
Object	Displays the object name.
Condition	The condition modifies the query's WHERE clause. When specifying a column condition, you must include the appropriate operator and operand. All standard SQL conditions are supported. For example: ≥ 10 $= 'VA'$ IN (SELECT dept_no FROM dept) BETWEEN SYSDATE AND SYSDATE + 15
Sort Type	Select ASC (Ascending) or DESC (Descending).
Sort Order	Enter a number (1, 2, 3, and so on) to specify the order in which selected columns should display.
Show	Select this check box to include the column in your query results. You do not need to select Show to add a column to the query for filtering only. For example, to create following query: <code>SELECT ename FROM emp WHERE deptno = 10</code> To create this query in Query Builder: <ol style="list-style-type: none"> From the Object list, select EMP. In the Design Pane, select ename and deptno. For the deptno column, in Condition enter =10 and clear the Show check box.
Function	Available argument functions include: <ul style="list-style-type: none"> ■ Number columns — COUNT, COUNT DISTINCT, AVG, MAXIMUM, MINIMUM, SUM ■ VARCHAR2, CHAR columns — COUNT, COUNT DISTINCT, INITCAP, LENGTH, LOWER, LTRIM, RTRIM, TRIM, UPPER ■ DATE, TIMESTAMP columns- COUNT, COUNT DISTINCT
Group By	Specify columns to be used for grouping when an aggregate function is used. Only applicable for columns included in output.
Delete	Deselect the column, excluding it from the query.

As you select columns and define conditions, Query Builder writes the SQL for you.

To view the underlying SQL:

1. Select the **SQL** tab.

2.3.3.12 Creating Relationships Between Objects

You can create relationships between objects by creating a join. A join identifies a relationship between two or more tables, views, or materialized views.

2.3.3.12.1 About Join Conditions When you write a join query, you specify a condition that conveys a relationship between two objects. This condition is called a join

condition. A join condition determines how the rows from one object combine with the rows from another object.

Query Builder supports inner, outer, left, and right joins. An inner join (also called a simple join) returns the rows that satisfy the join condition. An outer join extends the result of a simple join. An outer join returns all rows that satisfy the join condition and returns some or all of those rows from one table for which no rows from the other satisfy the join condition.

2.3.3.12.2 Joining Objects Manually Create a join manually by selecting the Join column in the Design pane.

To join objects manually:

1. From the Object Selection pane, select the objects you want to join.
2. Identify the columns you want to join.

You create a join by selecting the Join column adjacent to the column name. The Join column displays to the right of the data type. When your cursor is in the appropriate position, the following help tip displays:

Click here to select column for join


3. Select the appropriate Join column for the first object.

When selected, the Join column is darkened. To deselect a Join column, simply select it again or press ESC.

4. Select the appropriate Join column for the second object.

When joined, a line connects the two columns. An example is shown in [Figure 2–8](#).

Figure 2–8 *Joined Columns*




5. Select the columns to be included in your query. You can view the SQL statement resulting from the join by positioning the cursor over the join line.
6. Click **Results** to execute the query.

2.3.3.13 Saving a Query

Once you have built the query, click **Save** to return to the data model editor. The query appears in the SQL Query box. Click **OK** to save the data set.

Figure 2–9 Query Displayed in SQL Query Box



2.3.3.14 Editing a Saved Query

When you have saved the query from the Query Builder to the data model editor, you can also use the Query Builder to edit the query.

To use the Query Builder to edit the query:

1. Select the SQL data set.
2. On the toolbar, click **Edit Selected Data Set** to launch the **Edit Data Set** dialog.
3. Click **Query Builder** to load the query to the Query Builder.

Note: If you have made modifications to the query, or did not use the Query Builder to construct it, you may receive an error when launching the Query Builder to edit it. If the Query Builder cannot parse the query, you can edit the statements directly in the text box.

4. Edit the query and click **Save**.

2.3.4 Adding a Bind Variable to a Query

Now you have a basic query, but in the report you want users to be able to pass a parameter to the query to limit the results. For example, in the employee listing, you want users to be able to choose a specific department.

You can add the variable using either of the following methods:

- Add the bind variable using the Query Builder Conditions tab

To add the bind variable in the Query Builder Conditions tab:

1. Add the following Condition for the column:

```
in (:P_DEPTNAME)
```

where P_DEPTNAME is the name you choose for the parameter. This is shown in [Figure 2–10](#).

Figure 2–10 Adding the Bind Variable Using the Query Builder Conditions Tab

Column	Alias	Object	Condition	Sort Type	Sort Order
EMPLOYEE_ID	EMPLOYEE_ID	EMPLOYEES		ASC	
FIRST_NAME	FIRST_NAME	EMPLOYEES		ASC	
LAST_NAME	LAST_NAME	EMPLOYEES		ASC	
HIRE_DATE	HIRE_DATE	EMPLOYEES		ASC	
SALARY	SALARY	EMPLOYEES		ASC	
MANAGER_ID	MANAGER_ID	EMPLOYEES		ASC	
DEPARTMENT_NAME	DEPARTMENT_NAME	DEPARTMENTS	in (:P_DEPTNAME)	ASC	
DEPARTMENT_ID	DEPARTMENT_ID	EMPLOYEES		ASC	
LAST_NAME	LAST_NAME_1	EMPLOYEES_1		ASC	

- Update the SQL query directly in the text box.

Important: After manually editing the query, the Query Builder can no longer parse it. Any further edits must also be made manually.

To update the SQL query directly in the text box:

1. Add the following after the where clause in your query:


```
and "COLUMN_NAME" in (:PARAMETER_NAME)
```

for example:

```
and "DEPARTMENT_NAME" in (:P_DEPTNAME)
```


where P_DEPTNAME is the name you choose for the parameter. This is shown in [Figure 2–11](#).

Figure 2–11 Editing the Generated SQL Query



2. When you click **Save**, the data model editor prompts you to create the parameter that you entered with the bind variable syntax, as shown in [Figure 2–12](#).

Figure 2–12 Add Parameter Dialog



3. Select the parameter, and click **OK** to enable the data model editor create the parameter entry for you. See [Chapter 4, "Adding Parameters and Lists of Values"](#) for more information on defining parameter properties.

2.3.5 Adding Lexical References to SQL Queries

You can use lexical references to replace the clauses appearing after SELECT, FROM, WHERE, GROUP BY, ORDER BY, or HAVING. Use a lexical reference when you want the parameter to replace multiple values at runtime. Lexical references are supported in queries against Oracle applications only.

Create a lexical reference in the SQL query using the following syntax:

```
&parametername
```

Note: You also use lexical references to include flexfields in your query. For more information about using flexfields, see [Chapter 6, "Adding Flexfields."](#)

To define a lexical parameter:

1. Before creating your query, define a parameter in the PL/SQL default package for each lexical reference in the query. The data engine uses these values to replace the lexical parameters.
2. In the data model editor, on the Properties page, specify the **Oracle DB Default Package**.
3. In the data model editor, create a **Before Data** event trigger to call the PL/SQL package. See [Section 5.2, "Adding Before Data and After Data Triggers"](#) for more information about procedures.
4. Create your SQL query containing lexical references.
5. When you click **OK** to close your SQL query, you are prompted to enter the parameter.

For example, create a package called `employee`. In the `employee` package, define a parameter called `where_clause`:

```
Package employee
AS
  where_clause varchar2(1000);
  .....


Package body employee
AS
  .....
where_clause := 'where DEPARTMENT_ID=10';
.....
```

Reference the lexical parameter in the SQL query where you want the parameter to be replaced by the code defined in the package. For example:

```
select "EMPLOYEES"."EMPLOYEE_ID" as "EMPLOYEE_ID",
       "EMPLOYEES"."FIRST_NAME" as "FIRST_NAME",
       "EMPLOYEES"."LAST_NAME" as "LAST_NAME",
       "EMPLOYEES"."SALARY" as "SALARY",
from"OE"."EMPLOYEES" "EMPLOYEES"
&where_clause
```

When you click **OK** on the Create SQL Data Set dialog box, the lexical reference dialog box prompts you to enter a value for lexical references you entered in the SQL query, as shown in [Figure 2-13](#). Enter the value of the lexical reference as it is defined in the PL/SQL package.

Figure 2-13 Lexical Reference Dialog



At runtime, the data engine replaces `&where_clause` with the contents of `where_clause` defined in the package.

2.3.6 Defining SQL Queries Against the Oracle BI Server

When you launch the Query Builder against the Oracle BI server, the Query Builder displays the subject areas from the catalog. You can drag the subject areas to the Query Builder workspace to display the columns. Select the columns to include in your data model.

Keep the following points in mind when creating a data set against the Oracle BI server:

- When you create a SQL query against the Oracle BI server using the SQL Data Editor or the Query Builder, logical SQL is generated, not physical SQL like other database sources.
- Hierarchical columns are not supported. The highest level is always returned.
- Within a subject area, the join conditions between tables are already created; it is therefore not necessary to create joins in the Query Builder. The Query Builder does not expose the primary key.

It is possible to link data sets using the data model editor's **Create Link** function. See [Section 3.5, "Creating Element-Level Links."](#) For data sets created from the BI Server, there is a limit of two element-level links for a single data model.

- In the Query Builder, the functions **Sort Order** and **Group By** shown on the **Conditions** tab are not supported for queries against the Oracle BI server. If you enter a Sort Order or select the Group By check box, the Query Builder will construct the SQL, and write it to the BI Publisher SQL Query text box, but when you attempt to close the Data Set dialog, the query will fail validation.

To apply grouping to the data retrieved by the SQL query, you can use the data model editor's **Group by** function instead. See [Section 3.7, "Creating Subgroups."](#)

- If you pass parameters to the Oracle BI server and you choose Null Value Passed for Can Select All, you must ensure that you handle the null value in your query.


To create a SQL query against the Oracle BI server:

1. In the data model editor, click **New Data Set** and then click **SQL Query**.
2. Enter a name for the data set.
3. From the Data Source drop-down list, select the Oracle BI server connection (usually shown as Oracle BI EE).
4. Click **Query Builder** to launch the Query Builder page. See [Section 2.3.3, "Using the SQL Query Builder"](#) for more information about the Query Builder utility.

You can also enter the SQL syntax manually in the SQL Query text box, however you must use the logical SQL syntax used by the Oracle BI server.

5. From the Catalog drop-down list, select a subject area as shown in [Figure 2-14](#). The list displays the subject areas defined in the Oracle BI server.

Figure 2–14 *Selecting a Subject Area in the Query Builder*



6. Select tables and columns for the query.
7. Click **Save**.
8. Click **OK** to return to the data model editor. The SQL that is generated is logical SQL that follows a star schema. It is not physical SQL.
9. Save your changes to the data model.

2.4 Creating a Data Set Using a MDX Query Against an OLAP Data Source


BI Publisher supports Multidimensional Expressions (MDX) queries against OLAP data sources. MDX enables you to query multidimensional objects, such as Essbase cubes, and return multidimensional cell sets that contain the cube's data. You create MDX queries by manually entering the MDX query or by using MDX Query Builder to build the query.

2.4.1 Creating a Data Set Using a MDX Query

To create a data set using a MDX query:

1. On the toolbar, click **New Data Set** and then select **MDX Query**. The New Data Set - MDX Query dialog launches as shown in [Figure 2–15](#).

Figure 2–15 *New Data Set - MDX Query Dialog*



2. Enter a name for the data set.
3. Select the data source for the data set. Only the data sources defined as OLAP connections are displayed in the list.

Any private OLAP data source connections that you created will also be available in the Data Source drop-down list. For more information on creating private data source connections, see [Section 1.8, "Managing Private Data Sources"](#).
4. Enter the MDX query or click **Query Builder**. For more information on using MDX Query Builder, see [Section 2.5, "Using MDX Query Builder"](#).
5. Click **OK** to save. The data model editor validates the query.

Note: Ensure that in your OLAP data source that you do not use Unicode characters from the range U+F900 to U+FFFE to define any metadata attributes such as column names or table names. This Unicode range includes half-width Japanese Katakana and full-width ASCII variants. Using these characters results in errors when generating the XML data for a BI Publisher report.

For more information on writing MDX queries, see "Writing MDX Queries" in *Oracle Essbase Database Administrators Guide*.

2.5 Using MDX Query Builder

Use MDX Query Builder to build MDX basic queries without having to code them. MDX Query Builder enables you to add dimensions to columns, rows, pages, and point of view axes and preview the query results.

Note: MDX Query Builder only enables you to build data sets against Essbase data sources. For all other OLAP data sources, you must manually create the query.

2.5.1 Understanding the MDX Query Builder Process

To use MDX Query Builder to build a MDX query:

1. On the toolbar, click **New Data Set** and then select **MDX Query** to launch the New Data Set - MDX Query dialog.
2. Enter a name for the data set.
3. Select a data source.
4. Launch MDX Query Builder.
5. Select an Essbase cube for the query.
6. Select dimensions and measures by dragging and dropping them to the Columns, Rows, Slicer/POV, and the Pages axes.
7. (Optional) Use actions to modify the query.
8. (Optional) Apply filters.
9. Set the query options and save the query.

2.5.2 Using the Select Cube Dialog

In the Select Cube dialog, select the Essbase cube that you want to use to build the MDX query.

The MDX data source connection that you selected previously drives which Essbase cubes are available for selection.

2.5.3 Selecting Dimensions and Measures

You build MDX queries by selecting dimensions for the Columns, Rows, Slicer/POV, and Pages axes.

Account dimension members are listed individually by member name. All other dimension members are represented by generation name as shown in [Figure 2–16](#).

You can drag dimension generations and individual measures from the Account dimension to the Columns, Rows, Slicer/POV, and Pages axes.

Figure 2–16 Dimensions as Displayed in MDX Query Builder

The screenshot shows the MDX Query Builder interface. On the left is a 'Dimensions' tree with categories like Market, Product, Scenario, Year, Accounts, Profit, Sales, Cost_of_Goods, Marketing, Payroll, Miscellaneous, Profit_%, and Margin_%. The main area shows the query configuration: Columns (Gen2,Market), Rows (Gen3,Product, Margin, Sales, Total_Expenses), Slicer/POV (Scenario (Budget)), and Pages (Gen3,Year). Below this is the MDX query text and a data table for the month of January.

```
SELECT
NON EMPTY Hierarchize([Market].[Generations(2).Members] ON Axis(0),
NON EMPTY GROSSJOIN(Hierarchize([Product].[Generations(3).Members],[Accounts].[Margin],[Accounts].[Sales],[Accounts].[Total_Expenses])) ON Axis(1),NON EMPTY [Year].[Generations(3).Members] ON Axis(2)
FROM Demo.Basic
WHERE ([Budget])
```

		East	West	South
Stereo	Margin	1,239.00	1,680.00	
	Sales	2,950.00	4,000.00	
	Total_Expenses	1,145.00	1,580.00	
Compact_Disc	Margin	2,139.00	2,914.00	
	Sales	3,450.00	4,700.00	
	Total_Expenses	1,040.00	1,250.00	
Television	Margin	2,880.00	3,060.00	2,040.00
	Sales	4,800.00	5,100.00	3,400.00
	Total_Expenses	1,640.00	1,900.00	1,220.00
VCR	Margin	2,646.00	2,851.00	2,142.00
	Sales	4,200.00	4,650.00	3,400.00
	Total_Expenses	1,180.00	1,415.00	895.00
Camera	Margin	2,023.00	2,874.50	1,707.00
	Sales	2,850.00	4,050.00	2,400.00
	Total_Expenses	1,495.00	1,856.00	1,301.00

Build the query by dragging dimension members or measures from the Dimensions panel to one of the following axes areas:

- **Columns**— Axis (0) of the query
- **Rows** — Axis (1) of the query
- **Slicer/POV**— The slicer axis enables you to limit a query to only a specific slice of the Essbase cube. This represents the optional WHERE clause of a query.
- **Axis** — Axis (2) of the query

You can nest dimension members in the Columns and Rows axes, but you can only add a single dimension to the Slider/POV axis.

2.5.3.1 Adding Dimension Members to the Slicer/POV Axis

When you add a dimension to the Slicer/POV axis, the Member Selection dialog launches. You can only select one dimension member for this axis. Simply select the dimension in the Member Selection dialog, and then click **OK**.

The Member Selection dialog does not display if you add a measure to the Slicer/POV axis.

2.5.4 Performing MDX Query Actions

The MDX Query Builder toolbar contains the following buttons for modifying the MDX query:


- Click **Swap Rows and Columns** to flip dimensions between columns and rows.
- Click **Actions** to display the following menu items for selection:
 - **Select Cube** — Selects a different Essbase cube for the query.
 - **Set Alias Table** — Selects the alias table used for dimension display names. Alias names are used for display only and are not used in the query.
 - **Auto Refresh** — Displays the results as dimension members are placed in the Columns, Rows, Slicer/POV, and Pages axes and automatically refreshes the MDX query syntax.
 - **Clear Results** — Clears the results and removes member selections from all of the axes and any filters added to the query.
 - **Show Empty Columns** — Displays columns that do not contain data.
 - **Show Empty Rows** — Displays rows that do not contain data.
 - **Show Query** — Displays the MDX query syntax resulting from how the dimensions are placed in the Columns, Rows, Slicer/POV, and Pages axes.

2.5.5 Applying MDX Query Filters

You can create filters for dimensions on the Columns, Rows, and Pages axes in MDX Query Builder to further streamline your MDX query.

To create a filter, click the down-arrow button to the right of a dimension in the Columns, Rows, or Pages axes to display it in the Filters area. You create the filter by selecting the desired dimension member as shown in [Figure 2-17](#).

Figure 2-17 MDX Query Builder Filters




You can create multiple filters for a query, but you can only create one filter for each Columns, Rows, or Pages axis.

2.5.6 Selecting MDX Query Options and Saving MDX Queries

Once you have built the query, click **Save** to display the Options dialog as shown in [Figure 2–18](#).

Figure 2–18 Options Dialog



Use the Options dialog to select the dimension properties to include in the query for each of the dimensions in the Columns, Rows, and Pages axes. By default, none of the properties are selected.

The dimension properties are as follows:

- Member Alias — Dimension member alias names as listed in the Essbase outline.
- Ancestor Names — Ancestor dimension names as listed in the Essbase outline.
- Level Number — Dimension level numbers as listed in the Essbase outline.
- Gen Number — Generation number of the dimensions as listed in the Essbase outline.


For example, if you select the Member Alias and Level Number properties for Columns, the MDX query results are as follows:

```
SELECT
NON EMPTY Hierarchize([Market].Generations(2).Members)
PROPERTIES MEMBER_ALIAS,LEVEL_NUMBER ON Axis(0),
NON EMPTY CROSSJOIN(Hierarchize([Product].Generations(3).Members),
{[Accounts].[Margin],[Accounts].[Sales],[Accounts].[Total_Expenses]})ON Axis(1),
NON EMPTY [Year].Generations(3).Members ON Axis(2) FROM Demo.Basic
```

For more information on Essbase dimension properties, see "Querying for Properties" in *Oracle Essbase Database Administrator's Guide*.

After you select options for the MDX query, click **OK** to return to the New Data Set - MDX Query dialog and review the MDX query output as shown in [Figure 2–19](#).

Figure 2–19 MDX Query Output



Click **OK** to return to the data model editor, and save your changes.

Important: If you modify a MDX query after you save it in BI Publisher, Oracle recommends that you manually change the syntax and not use MDX Query Builder to do so.

2.6 Creating a Data Set Using an Oracle BI Analysis


If you have enabled integration with Oracle Business Intelligence, then you can access the Oracle Business Intelligence Presentation catalog to select an Oracle BI analysis as a data source. An analysis is a query against an organization's data that provides answers to business questions. A query contains the underlying SQL statements that are issued to the Oracle BI Server.

For more information about creating analyses, see *Oracle Fusion Middleware User's Guide for Oracle Business Intelligence Publisher*.


Important: Hierarchical columns are not supported in BI Publisher data models.

To create a data set using an Oracle BI analysis:

1. Click the **New Data Set** toolbar button and select **Oracle BI Analysis**. The New Data Set - Oracle BI Analysis dialog launches.
2. Enter a name for this data set.
3. Click the browse icon to connect to the Oracle BI Presentation catalog, as shown in [Figure 2–20](#).

Figure 2–20 Connecting to the Oracle BI Presentation Catalog

4. When the catalog connection dialog launches, navigate through the folders to select the Oracle BI analysis to use as the data set for the report.
5. Enter a **Time Out** value in seconds, as shown in [Figure 2–21](#). If BI Publisher has not received the analysis data after the time specified in the time out value has elapsed, then BI Publisher stops attempting to retrieve the analysis data.

Figure 2–21 Creating a BI Analysis Data Set

6. Click OK.

2.6.1 Additional Notes on Oracle BI Analysis Data Sets

Parameters and list of values are inherited from the BI analysis and they display at run time.

The BI Analysis must have default values defined for filter variables. If the analysis contains presentation variables with no default values, it is not supported as a data source by BI Publisher.

If you want to structure the data based on Oracle BI Analysis Data Sets, the group breaks, data links and group-level functions are not supported.

The following are supported:

- Global level functions
- Setting the value for elements if null
- Group Filters

For more information about the above supported features, see [Chapter 3, "Structuring Data."](#)

2.7 Creating a Data Set Using a View Object

BI Publisher enables you to connect to your custom applications built with Oracle Application Development Framework and use view objects in your applications as data sources for reports.

Prerequisite: Before you can create a BI Publisher data model using a view object, you must first create the view object in your application following the guidelines in the chapter "Making a View Object Available to BI Publisher as a Data Source" in the *Oracle Fusion Middleware Developer's Guide for Oracle Business Intelligence Publisher*.

To create a data set using a view object:

1. Click the **New Data Set** toolbar button and select **View Object**. The New Data Set - View Object dialog launches.
2. Enter a name for this data set.
3. Select the **Data Source** from the list. The data sources that you defined in the providers.xml file display.
4. Enter the fully qualified name of the application module (for example: example.apps.pa.entity.applicationModule.AppModuleAM).
5. Click **Load View Objects**.
BI Publisher calls the application module to load the view object list.
6. Select the **View Object**.
7. Any bind variables defined are retrieved. Create a parameter to map to this bind variable See [Chapter 4, "Adding Parameters and Lists of Values."](#)
8. Click **OK** to save your data set.

2.7.1 Additional Notes on View Object Data Sets

To structure data based on view object data sets, the group breaks, data links and group-level functions are not supported.

The following is supported: Setting the value for elements if null.

For more information about this supported feature, see [Chapter 3, "Structuring Data."](#)

2.8 Creating a Data Set Using a Web Service

BI Publisher supports data sets that use simple and complex Web service data sources to return valid XML data.

To include parameters for Web service methods, it is recommended that you define the parameters first, so that the methods are available for selection when setting up the data source. See [Chapter 4, "Adding Parameters and Lists of Values."](#)

Multiple parameters are supported. Ensure the method name is correct and the order of the parameters matches the order in the method. To call a method in the Web service that accepts two parameters, you must map two parameters defined in the report to the two parameters in the method. Note that only parameters of simple type are supported, for example, string and integer.

Important: Only document/literal Web services are supported.

To specify a parameter, click **Add Parameter** and select the parameter from the drop-down list.

Note: The parameters must be set up in the Parameters section of the report definition. For more information, see [Chapter 4, "Adding Parameters and Lists of Values."](#)

In 11.1.1.7.10 the procedure for creating a data set from a Web service is enhanced. See the appropriate procedure for your release:

- [Section 2.8.1, "Creating a Data Set Using a Web Service in Release 11.1.1.7.10"](#)
- [Section 2.8.2, "Creating a Data Set Using a Web Service in Releases Prior to 11.1.1.7.10"](#)

2.8.1 Creating a Data Set Using a Web Service in Release 11.1.1.7.10

In Release 11.1.1.7.10, Web service data sources can be set up in the following ways:

- On the Administration page
Connections to Web service data sources can be set up on the Administration page and then used in multiple data models. For more information, see "Setting Up a Connection to a Web Service" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.
- As a private data source
You can also set up a private connection accessible only to you. See [Section 1.8, "Managing Private Data Sources"](#) for information about private data source connections.

You must set up the connection before you create the data model.

BI Publisher supports data sets that use simple and complex Web service data sources to return valid XML data:

- [Section 2.8.1.1, "Creating a Data Set Using a Simple Web Service"](#)
- [Section 2.8.1.2, "Creating a Data Set Using a Complex Web Service"](#)


2.8.1.1 Creating a Data Set Using a Simple Web Service

If you are not familiar with the available methods and parameters in the Web service to call, you can open the URL in a browser to view them.

To create a data set using a simple Web service:


1. Click the **New Data Set** toolbar button, and then select **Web Service**. The New Data Set - Web Service dialog launches, as shown in [Figure 2-22](#).

Figure 2–22 Creating a Data Set Using a Simple Web Service Connection




2. Enter the data set name.
3. Select the Data Source.
The WSDL URL, Web Service, and Method fields are automatically populated from the Web service data source.
4. Select the **Method** from the list of available methods in the Web service.
5. Click **OK**.
6. Define the parameters to make them available to the Web service data set as follows:
 - Select **Parameters** on the Data Model pane, click **Create New Parameter**, and then enter the following attributes:
 - **Name** — Enter an internal identifier for the parameter (for example, Symbol).
 - **Data Type** — Select String.
 - **Default Value** — If desired, enter a default for the parameter (for example, ORCL).
 - **Parameter Type** — Select Text.
 - **Row Placement** — Select a row placement value. The default is 1.
 - In the **New_Parameter_1:Type: Text** region, enter the following attributes:
 - **Display Label** — Enter the label you want displayed for your parameter (for example: Stock Symbol).
 - **Text Field Size** — Enter the size for the text entry field in characters.

Figure 2–23 Creating the Parameter



- (Optional) Select the following parameter options:
 - **Text field contains comma-separated values** — Select this option to enable the user to enter multiple comma-delimited values for this parameter.
 - **Refresh other parameters on change** — Performs a partial page refresh to refresh any other parameters whose values are dependent on the value of this one.
7. Return to the Web service data set and add the parameter as follows:
- Click the data set name.
 - On the toolbar, click **Edit Selected Data Set** to launch the Edit Data Set dialog.
 - In the **Edit Data Set** dialog, click **Add Parameter**. Your parameter displays, as shown in [Figure 2–24](#).
 - Name the parameter, and then click **OK** to close the Edit Data Set dialog.

Figure 2–24 Adding the Parameter to Web Service Data Set



8. Click **Save**.

2.8.1.2 Creating a Data Set Using a Complex Web Service

BI Publisher supports data sets that use complex Web service data sources to return valid XML data. A complex Web service type internally uses `soapRequest / soapEnvelope` to pass the parameter values to the destination host.

When a data set uses a complex Web service as a data source, the data model editor displays the WSDL URL, available Web service, and operations associated with the complex Web service. For each selected operation, the data model editor displays the structure of the required input parameters. If you choose **Show optional parameters**, all optional parameters are displayed as well.


If you are not familiar with the available methods and parameters in the Web service, open the WSDL URL in a browser to view them.

To add a complex Web service as a data source:

1. Enter the data set information as follows:
 - Enter the data set name.
 - Select the data source. The WSDL URL and Web service fields are automatically populated from the complex Web service data source.

- Select the **Method**.
The Methods available for selection are based on the complex Web service data source. When you select a method, the **Parameters** are displayed. To view optional parameters, select **Show optional parameters**.
 - **Response Data XPath** — If the start of the XML data for the report is deeply embedded in the response XML generated by the Web service request, use this field to specify the path to the data to use in the BI Publisher report.
2. Define the parameter to make it available to the Web service data set as follows:
 - Select **Parameters** on the **Report** definition pane, and then click **New** to create a parameter.
 - Define the following parameter attributes:
 - **Name** — Enter an internal identifier for the parameter.
 - **Data Type** — Select the appropriate data type for the parameter.
 - **Default Value** — If desired, enter a default value for the parameter.
 - **Parameter Type** — Select the appropriate parameter type.
 - **Display label** — Enter the label you want displayed for your parameter.
 - **Text Field Size** — Enter the size for the text entry field in characters.
 3. Return to the Web Service data set and add the parameter.
 - Select the Web service data set, and then click **Edit Selected Data Set** to launch the Edit Data Set dialog.
 - Select the parameters as shown in [Figure 2–25](#).

Figure 2–25 Entering Parameters for Complex Web Service



4. To test the Web service, see [Section 2.16, "Testing Data Models and Generating Sample Data."](#)

2.8.2 Creating a Data Set Using a Web Service in Releases Prior to 11.1.1.7.10

For releases prior to 11.1.1.7.10, connections to Web service data sources are created when you define the data set, for each data set. Use the following procedures for releases prior to 11.1.1.7.10:

- Section 2.8.2.1, "Adding a Simple Web Service"
- Section 2.8.2.2, "Adding a Complex Web Service"

2.8.2.1 Adding a Simple Web Service

This example shows how to add a Web service to BI Publisher as a data source. The Web service returns stock quote information. The Web service passes one parameter: the quote symbol for a stock.

The WSDL URL is:

<http://www.webservices.net/stockquote.asmx?WSDL>

If you are not familiar with the available methods and parameters in the Web service to call, you can open the URL in a browser to view them. This Web service includes a method called GetQuote. It takes one parameter, which is the stock quote symbol.

To add the Web service as a data source:

1. Click the **New Data Set** toolbar button and select **Web Service**. The New Data Set - Web Service dialog launches, as shown in [Figure 2-26](#).

Figure 2-26 *Creating a Simple Web Service Data Set*


2. Enter the Web service name.
3. Enter the Web service information as follows:
 - Select **False** for **Complex Type**.
 - Enter the **WSDL URL**: `http://www.webservices.net/stockquote.asmx?WSDL`
 - Enter the **Method**: `GetQuote`
 - If desired, enter a **Time Out** period in seconds. If the BI Publisher server cannot establish a connection to the Web service, the connection attempt times out after the specified time out period has elapsed.
4. Define the parameter to make it available to the Web service data set.

Select **Parameters** on the Data Model pane and click the **Create New Parameter** button. Enter the following:


- **Name** — Enter an internal identifier for the parameter (for example, `Symbol`).
- **Data Type** — Select `String`.

- **Default Value** — If desired, enter a default for the parameter (for example, ORCL).
 - **Parameter Type** — Select Text.
 - **Row Placement** — Select a row placement value. The default is 1.
5. In the **New_Parameter_1:Type: Text** region, enter the following:
- **Display Label** — Enter the label you want displayed for your parameter (for example: Stock Symbol).
 - **Text Field Size** — Enter the size for the text entry field in characters.


Figure 2–27 Creating the Parameter



6. Select the options that you want to apply:
- **Text field contains comma-separated values** — Select this option to enable the user to enter multiple comma-delimited values for this parameter.
 - **Refresh other parameters on change** — Performs a partial page refresh to refresh any other parameters whose values are dependent on the value of this one.
7. Return to your Web service data set and add the parameter as follows:
- Click the data set name, Stock Quote.
 - On the toolbar, click **Edit Selected Data Set** to launch the Edit Data Set dialog.
 - In the **Edit Data Set** dialog, click **Add Parameter**. The Quote parameter displays, as shown in [Figure 2–28](#).
 - Name the parameter, and click **OK** to close the Edit Data Set dialog.

Figure 2–28 Adding the Parameter to Web Service Data Set

8. Click **Save**.
9. Select the **Data** tab.
10. Enter a valid value for your Stock Symbol parameter, select the number of rows to return, and click **View**. [Figure 2–29](#) shows the data returned from the example.

Figure 2–29 Data Returned from Stock Quote Example

2.8.2.2 Adding a Complex Web Service

A complex Web service type internally uses soapRequest / soapEnvelope to pass the parameter values to the destination host.

To use a complex Web service as a data source, select Complex Type equal True, then enter the WSDL URL. After loading and analyzing the WSDL URL, the data model editor displays the available Web services and operations. For each selected operation, the data model editor displays the structure of the required input parameters. By choosing **Show Optional Parameters**, you can see all optional parameters as well.

If you are not familiar with the available methods and parameters in the Web service, open the WSDL URL in a browser to view them.

To add a complex Web service as a data source:

1. Enter the data set information as follows:
 - Enter a **Name** for the data set and select Web Service as the **Type**.

- Select True for **Complex Type**.
 - Select a security header as follows:
 - 2002 — Enables the "WS-Security" Username Token with the 2002 namespace:
`http://docs.oasis-open.org/wss/2004/01/oasis-200401-wss-wssecurity-secect-1.0.xsd`
 - 2004 — Enables the "WS-Security" Username Token with the 2004 namespace:
`http://docs.oasis-open.org/wss/2004/01/oasis-200401-wss-username-token-profile-1.0#PasswordText`
 - **Username and Password** — Enter the username and password for the Web service, if required.
 - If desired, enter a **Time Out** period in seconds. If the BI Publisher server cannot establish a connection to the Web service, then connection attempt times out after the specified time out period has elapsed.
 - Enter a **WSDL URL**. When you enter the WSDL, the Web Service list populates with the available Web services from the WSDL.
 - Choose a Web Service from the list. When you choose a Web service from the list, the **Method** list populates with the available methods.
 - Select the **Method**. When you select the method, the **Parameters** display. If you want to see optional parameters as well, then select **Show Optional Parameters**.
 - **Response Data XPath** — If the start of the XML data for the report is deeply embedded in the response XML generated by the Web service request, then use this field to specify the path to the data to use in the BI Publisher report.
2. Define the parameter to make it available to the Web service data set.
- Select **Parameters** on the **Report** definition pane and click **New** to create a parameter. Enter the following:
- **Name** — Enter an internal identifier for the parameter.
 - **Data Type** — Select the appropriate data type for the parameter.
 - **Default Value** — If desired, enter a default value for the parameter.
 - **Parameter Type** — Select the appropriate parameter type.
 - **Display label** — Enter the label you want displayed for your parameter.
 - **Text Field Size** — Enter the size for the text entry field in characters.
3. Return to the Web Service data set and add the parameter.
- Select the Web service data set and then click **Edit Selected Data Set** to launch the Edit Data Set dialog.
 - Select the parameters as shown in [Figure 2-25](#).

Figure 2–30 Entering Parameters for Complex Web Service

The screenshot shows the 'Edit Data Set' dialog box with the following configuration:

- Name:** Complex Web Service
- Complex Type:** True
- WS-Security:** 2002
- Username:** (empty)
- Password:** (empty)
- Time Out:** (empty) (in seconds)
- WSDL URL:** http:example.com:9999/xmlpserver/services
- Web Service:** PublicReportServiceService
- Method:** getFolderContents
- Show optional parameters:** (unchecked)
- ResponseData XPath:** (empty)
- Parameters:**
 - [name=ns1:userID], [type=string] → \${userID}
 - [name=ns1:folderAbsolutePath], [type=string] → \${folderAbsolutePath}
 - [name=ns1:password], [type=string] → \${password}

- To test the Web service, see [Section 2.16, "Testing Data Models and Generating Sample Data."](#)

2.8.3 Additional Information on Web Service Data Sets


There is no metadata available from Web service data sets, therefore grouping and linking are not supported.

2.9 Creating a Data Set Using an LDAP Query

BI Publisher supports queries against Lightweight Directory Access protocol (LDAP) data sources. You can query user information stored in LDAP directories and then use the data model editor to link the user information with data retrieved from other data sources.

For example, to generate a report that lists employee salary information that is stored in the database application and include on the report employee e-mail addresses that are stored in the LDAP directory. You can create a query against each and then link the two in the data model editor to display the information in a single report. [Figure 2–31](#) shows a sample LDAP query.

Figure 2–31 Sample LDAP Query



To create a data set using an LDAP query:

1. Click the **New Data Set** toolbar button and select **LDAP Query**. The New Data Set - LDAP Query dialog launches.
2. Enter a name for this data set.
3. Select the **Data Source** for this data set. Only data sources defined as LDAP connections display in the list.
4. In the Attributes entry box, enter the attributes whose values you want to fetch from the LDAP data source.

For example:

```
mail, cn, givenName
```

5. To filter the query, enter the appropriate syntax in the Filter entry box. The syntax is as follows:

```
(Operator (Filter)through(Filter))
```

For example:

```
(objectclass=person)
```

LDAP search filters are defined in the Internet Engineering Task Force (IETF) Request for Comments document 2254, "The String Representation of LDAP Search Filters," (RFC 2254). This document is available from the IETF Web site at <http://www.ietf.org/rfc/rfc2254.txt>

6. Link the data from this query to the data from other queries or modify the output structure. For instructions on completing this step, see [Chapter 3, "Structuring Data."](#)

2.10 Creating a Data Set Using a XML File

To use an XML file as a data source, perform one of the following actions:

- Place the XML file in a directory that your administrator has set up as a data source. For more information, see "Setting Up a Connection to a File Data Source" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.

- Upload the XML file to the data model from a local directory.

Important: To use BI Publisher's layout editor and interactive viewer, sample data from the XML file source must be saved to the data model.

2.10.1 About Supported XML Files

The following are guidelines for the support of XML files as a data set type in BI Publisher:


- The XML files that you use as input to the BI Publisher data engine must be UTF-8 encoded.
- Do not use the following characters in XML tag names: ~, !, #, \$, %, ^, &, *, +, `, |, :, \", \\, <, >, ?, ,, /. If your data source file contains any of these characters, use the data model editor Structure tab to change the tag names to an acceptable one.
- The XML file must be valid. Oracle provides many utilities and methods for validating XML files.
- There is no metadata available from XML file data sets, therefore grouping and linking are not supported.

2.10.2 Using a XML File Stored in a File Directory Data Source

To create a data set using a XML file from a file directory data source:

1. On the toolbar, click **New Data Set** and select **XML File**. The New Data Set - XML File dialog launches, as shown in [Figure 2-32](#).

Figure 2-32 *New Data Set - XML File Dialog*




2. Enter a name for the data set.
3. Click **Shared** to enable the Data Source list. This is the default selected option.
4. Select the **Data Source** where the XML file resides. The list is populated from the configured File Data Source connections.
5. To the right of File Name, click **Browse** to connect to the data source and browse the available directories. Select the file.
6. Click **OK**.
7. (Required) Save sample data to the data model. See [Section 2.16, "Testing Data Models and Generating Sample Data."](#)

2.10.3 Uploading a XML File Stored Locally

To create a data set using a XML file stored locally:

1. On the toolbar, click **New Data Set** and select **XML File**. The New Data Set - XML File dialog launches, as shown in [Figure 2–33](#).

Figure 2–33 New Data Set - XML File Dialog




2. Enter a name for this data set.
3. Select **Local** to enable the Upload button.
4. Click **Upload** to browse for and upload the XML file from a local directory. If the file has been uploaded to the data model, then it is available for selection in the File Name List.
5. Click **Upload**.
6. Click **OK**.
7. (Required) Save sample data to the data model. See [Section 2.16, "Testing Data Models and Generating Sample Data."](#)

2.10.3.1 Refreshing and Deleting an Uploaded XML File

After uploading the file, it displays on the **Properties** pane of the data model under the **Attachments** region, as shown in [Figure 2–34](#).

Figure 2–34 Attachments Region of the Properties Pane



See [Section 1.7, "Setting Data Model Properties"](#) for more information about the Properties pane.

To refresh the local file in the data model:

1. In the component pane, click **Data Model** to view the **Properties** page.
2. In the **Attachment** region of the page, locate the file in the **Data Files** list.

3. Click **Refresh**.
4. In the **Upload** dialog, browse for and upload the latest version of the file. The file must have the same name or it will not replace the older version.
5. Save the data model.

To delete the local file:

1. In the component pane, click **Data Model** to view the **Properties** page.
2. In the **Attachment** region of the page, locate the file in the **Data Files** list.
3. Click **Delete**.
4. Click **OK** to confirm.
5. Save the data model.

2.11 Creating a Data Set Using a Microsoft Excel File

To use a Microsoft Excel file as a data source, you have the following options for providing the file to BI Publisher:

- Place the file in a directory that your administrator has set up as a data source. See the section "Setting Up a Connection to a File Data Source" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.
- Upload the file to the data model from a local directory.

2.11.1 About Supported Excel Files

Following are guidelines for the support of Microsoft Excel files as a data set type in BI Publisher:

- The Microsoft Excel files must be saved in the Excel 97-2003 Workbook (*.xls) format by Microsoft Excel. Files created by a third party application or library are not supported.
- The source Excel file can contain a single sheet or multiple sheets.
- Each worksheet can contain one or multiple tables. A table is a block of data that is located in the continuous rows and columns of a sheet.

In each table, BI Publisher always considers the first row to be a heading row for the table.

- The data type of the data in the table may be number, text, or date/time.
- If multiple tables exist in a single worksheet, the tables must be identified with a name for BI Publisher to recognize each one. See [Section 2.11.2, "Guidelines for Accessing Multiple Tables per Sheet."](#)
- If all tables in the Excel file are not named, only the data in the first table (the table located in the upper most left corner) is recognized and fetched.
- When the data set is created, BI Publisher truncates all trailing zeros after the decimal point for numbers in all cases. To preserve the trailing zeros in your final report, you must apply a format mask in your template to display the zeroes. For more information about format masks, see the section "Formatting Numbers, Dates, and Currencies" in *Oracle Fusion Middleware Report Designer's Guide for Oracle Business Intelligence Publisher*.

- Single value parameters are supported, but multiple value parameters are not supported.

2.11.2 Guidelines for Accessing Multiple Tables per Sheet

If the Excel worksheet contains multiple tables that you want to include as data sources, then you must define a name for each table in Excel.

Important: The name that you define must begin with the prefix: "BIP_", for example, "BIP_SALARIES".

To define a name for the table in Excel:

1. Insert the table in Excel.
2. Define a name for the table as follows:

Using Excel 2003: Select the table. On the **Insert** menu, click **Name** and then **Define**. Enter a name that is prefixed with "BIP_".


Using Excel 2007: Select the table. On the **Formulas** tab, in the **Defined Names** group, click **Define Name**, then enter the name in the **Name** field. The name you enter appears on the Formula bar.

Tip: You can learn more about defined names and their usage in the Microsoft Excel 2007 document "Define and use names in formulas." at the following URL:

<http://office.microsoft.com/en-us/excel/HA101471201033.aspx>

Figure 2–35 shows how to use the Define Name command in Microsoft Excel 2007 to name a table "BIP_Salaries".

Figure 2–35 Using the Define Name Command in Microsoft Excel



2.11.3 Using a Microsoft Excel File Stored in a File Directory Data Source


Note that to include parameters for your data set, you must define the parameters first, so that they are available for selection when defining the data set. See [Chapter 4, "Adding Parameters and Lists of Values."](#)

Important: The Excel data set type supports one value per parameter. It does not support multiple selection for parameters.

To create a data set using a Microsoft Excel file from a file directory data source:

1. Click the **New Data Set** toolbar button and select **Microsoft Excel File**. The New Data Set - Microsoft Excel File dialog launches.
2. Enter a name for this data set.
3. Click **Shared** to enable the Data Source list.
4. Select the data source where the Microsoft Excel File resides.
5. To the right of the File Name field, click the browse icon to browse for the Microsoft Excel file in the data source directories. Select the file.
6. If the Excel file contains multiple sheets or tables, select the appropriate **Sheet Name** and **Table Name** for this data set, as shown in [Figure 2-36](#).

Figure 2-36 *Selecting the Sheet Name*



7. If you added parameters for this data set, click **Add Parameter**. Enter the **Name** and select the **Value**. The Value list is populated by the parameter Name defined in the Parameters section. Only single value parameters are supported. See [Chapter 4, "Adding Parameters and Lists of Values."](#)
8. Click **OK**.
9. Link the data from this query to the data from other queries or modify the output structure. For more information on linking queries, see [Chapter 3, "Structuring Data."](#)

2.11.4 Uploading a Microsoft Excel File Stored Locally


Note that to include parameters for the data set, you must define the parameters first, so that they are available for selection when defining the data set. See [Chapter 4, "Adding Parameters and Lists of Values."](#)

Important: The Excel data set type supports one value per parameter. It does not support multiple selection for parameters.

To create a data set using a Microsoft Excel file stored locally:

1. Click the **New Data Set** toolbar button and select Microsoft Excel File. The Create Data Set - Excel dialog launches.
2. Enter a name for this data set.
3. Select **Local** to enable the upload button.
4. Click the **Upload** icon to browse for and upload the Microsoft Excel file from a local directory. If the file has been uploaded to the data model, then it is available for selection in the **File Name** list.
5. If the Excel file contains multiple sheets or tables, select the appropriate **Sheet Name** and **Table Name** for this data set, as shown in [Figure 2–37](#).

Figure 2–37 *Creating a Data Set from an Excel Spreadsheet*




6. If you added parameters for this data set, click **Add Parameter**. Enter the **Name** and select the **Value**. The Value list is populated by the parameter Name defined in the Parameters section. Only single value parameters are supported. See [Chapter 4, "Adding Parameters and Lists of Values."](#)
7. Click **OK**.
8. Link the data from this query to the data from other queries or modify the output structure. For more information on linking queries, see [Chapter 3, "Structuring Data."](#)

2.11.4.1 Refreshing and Deleting an Uploaded Excel File

After uploading the file, it displays on the **Properties** pane of the data model under the **Attachments** region, as shown in [Figure 2–38](#).

Figure 2–38 Attachments Region of the Properties Pane



See [Section 1.7, "Setting Data Model Properties"](#) for information about the **Properties** pane.

To refresh the local file in the data model:

1. Click **Data Model** in the component pane to view the **Properties** page.
2. In the **Attachment** region of the page, locate the file in the **Data Files** list.
3. Click **Refresh**.
4. In the **Upload** dialog, browse for and upload the latest version of the file. The file must have the same name or it will not replace the older version.
5. Save the data model.

To delete the local file:

1. Click **Data Model** in the component pane to view the **Properties** page.
2. In the **Attachment** region of the page, locate the file in the **Data Files** list.
3. Click **Delete**.
4. Click **OK** to confirm.
5. Save the data model.

2.12 Creating a Data Set Using a CSV File

To use a CSV file as a data source, perform one of the following actions:

- Place the CSV file in a directory that your administrator has set up as a data source. For more information, see "Setting Up a Connection to a File Data Source" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.
- Upload the CSV file to the data model from a local directory.

2.12.1 About Supported CSV Files

The following are guidelines for the support of CSV files as a data set type in BI Publisher:

- The following CSV file delimiters are supported: Comma, Pipe, Semicolon, and Tab.


- If your CSV file contains headers, the header names are used as the XML tag names. The following characters are not supported in XML tag names: ~, !, #, \$, %, ^, &, *, +, -, \, |, :, \", \\, <, >, ?, ,, /. If your data source file contains any of these characters in a header name, use the data model editor Structure tab to edit the tag names.
- CSV data sets support editing the data type assigned by the data model editor. See [Section 2.12.3.1, "Editing the Data Type"](#) for more information. If you update the data type for an element in the data set, you must ensure that the data in the file is compliant with the data type that you selected.
- The CSV files that you use as input to the BI Publisher data engine must be UTF-8 encoded and cannot contain empty column headers.
- Group breaks, data links, expression and group-level functions are not supported.
- Data fields in CSV files must be in the canonical ISO date format for mapped date elements (for example, 2012-01-01T10:30:00-07:00), and #####.## for mapped number elements.
- No data validation is provided for CSV files.

2.12.2 Using a CSV File Stored in a File Directory Data Source

To create a data set using a CSV file from a file directory data source:

1. On the data model editor toolbar, click **New Data Set** and select **CSV File**. The New Data Set - CSV File dialog launches, as shown in [Figure 2-39](#).

Figure 2-39 New Data Set - CSV File Dialog



2. Enter a name for this data set.
3. Click **Shared** to enable the Data Source list.
4. Select the **Data Source** where the CSV file resides. The list is populated from the configured File Data Source connections.
5. Click **Browse** to connect to the data source and browse the available directories. Select the file.
6. (Optional) Select **The first row a column header** to specify if the first row in the file contains column names. If you do not select this option, the columns are assigned a generic name, for example, Column1, Column2. The XML tag names and display names assigned can be edited in the data model editor Structure tab.


7. Select the **CSV delimiter** used in the file. The default selection is Comma (,).
8. Click **OK**.

2.12.3 Uploading a CSV File Stored Locally

To create a data set using a CSV file stored locally:

1. On the toolbar, click **New Data Set** and select **CSV File**. The New Data Set - CSV File dialog launches, as shown in [Figure 2–40](#).

Figure 2–40 New Data Set - CSV File Dialog



2. Enter a name for this data set.
3. Select **Local** to enable the Upload button.
4. Click **Upload** to browse for and upload the CSV file from a local directory. If the file has been uploaded to the data model, then it is available for selection in the File Name List.
5. (Optional) Select **The first row a column header** to specify if the first row in the file contains column names. If you do not select this option, the columns are assigned a generic name, for example, Column1, Column2. The XML tag names and display names assigned can be edited in the data model editor Structure tab.
6. Select the **CSV Delimiter** used in the file. The default selection is Comma (,).
7. Click **OK**.

2.12.3.1 Editing the Data Type

To edit the data type for a CSV file element, click the data type icon or update it from the element Properties dialog.


The data for an element must be compliant with the data type that you assign. The user interface does not validate the data when you update the data type. If the data does not match, for example, a string value is present for an element you defined as Integer, errors may occur in the layout editing tools and or at runtime.

You can only update the data types for CSV file data sources.

2.12.3.2 Refreshing and Deleting an Uploaded CSV File

After uploading the file, it is displayed on the **Properties** pane of the data model under the **Attachments** region, as shown in [Figure 2–41](#).

Figure 2–41 Attachments Region of the Properties Pane



See [Section 1.7, "Setting Data Model Properties"](#) for more information about the Properties pane.

To refresh the local file in the data model:

1. In the component pane, click **Data Model** to view the **Properties** page.
2. In the **Attachment** region of the page, locate the file in the **Data Files** list.
3. Click **Refresh**.
4. In the **Upload** dialog, browse for and upload the latest version of the file. The file must have the same name or it will not replace the older version.
5. Save the data model.

To delete the local file:

1. In the component pane, click **Data Model** to view the **Properties** page.
2. In the **Attachment** region of the page, locate the file in the **Data Files** list.
3. Click **Delete**.
4. Click **OK** to confirm.
5. Save the data model.

2.13 Creating a Data Set from an HTTP XML Feed

Using the HTTP (XML Feed) data set type, you can create data models from RSS and XML feeds over the Web by retrieving data through the HTTP GET method.

Important: Additional configuration might be required to access external data source feeds depending on your system's security. If the RSS feed is protected by Secure Sockets Layer (SSL) then see the section "Configuring BI Publisher for Secure Socket Layer (SSL) Communication" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.

To include parameters for the data set, it is recommended that you define the parameters first, so that they are available for selection when defining the data set. See [Chapter 4, "Adding Parameters and Lists of Values."](#)

Note that there is no metadata available from HTTP XML feed data sets, therefore grouping and linking are not supported.

In 11.1.1.7.10 the procedure for creating a data set from an HTTP XML feed is enhanced. See the appropriate procedure for your release:

- [Section 2.13.1, "Creating a Data Set from an HTTP XML Data Set in Release 11.1.1.7.10"](#)
- [Section 2.13.2, "Creating a Data Set from an HTTP XML Data Set in Releases Prior to 11.1.1.7.10"](#)

2.13.1 Creating a Data Set from an HTTP XML Data Set in Release 11.1.1.7.10

In Release 11.1.1.7.10, HTTP (XML Feed) data sources can be set up by two different methods:

- On the Administration page
Connections to HTTP data sources can be set up on the Administration page and then used in multiple data models. For more information, see "Setting Up a Connection to a HTTP XML Feed" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.
- As a private data source
You can also set up a private connection accessible only to you. See [Section 1.8, "Managing Private Data Sources"](#) for information about private data source connections.

To create a data set from an HTTP XML feed:

1. On the toolbar, click **New Data Set** and select **HTTP (XML Feed)**. The New Data Set - HTTP (XML Feed) dialog launches, as shown in [Figure 2-42](#).

Figure 2-42 *New Data Set - HTTP (XML Feed) Dialog*

2. Enter a name for this data set.
3. Select a data source.
4. Enter the URL Suffix for the source of the RSS or XML feed.
5. Select the Method: GET.
6. To add a parameter, click **Add Parameter**. Enter the **Name** and select the **Value**. The Value list is populated by the parameter Name defined in the Parameters section. See [Chapter 4, "Adding Parameters and Lists of Values."](#)
7. Click **OK** to close the data set dialog.

2.13.2 Creating a Data Set from an HTTP XML Data Set in Releases Prior to 11.1.1.7.10

To create a data set from an HTTP XML feed:

1. On the toolbar, click **New Data Set** and select **HTTP (XML Feed)**. The New Data Set - HTTP (XML Feed) dialog launches, as shown in [Figure 2–42](#).

Figure 2–43 New Data Set - HTTP (XML Feed) Dialog


2. Enter a name for this data set.
3. Enter the URL for the source of the RSS or XML feed.
4. Select the Method: GET.
5. Enter the Username, Password, and Realm for the URL, if required.
6. To add a parameter, click **Add Parameter**. Enter the **Name** and select the **Value**. The Value list is populated by the parameter Name defined in the Parameters section. See [Chapter 4, "Adding Parameters and Lists of Values."](#)
7. Click **OK** to close the data set dialog.

2.14 Creating a Data Set from an Oracle Endeca Query

Oracle Endeca Information Discovery is an enterprise data discovery platform for advanced exploration and analysis of complex and varied data. Information is loaded from disparate source systems and stored in a faceted data model that dynamically supports changing data. BI Publisher enables Oracle Endeca Information Discovery users to define Endeca Query Language (EQL) queries against the Oracle Endeca Server to retrieve data back to BI Publisher for use in enterprise reporting.

Prerequisite: An administrator must configure the integration with Oracle Endeca Server. For more information, see "Configuring Integration with Oracle Endeca Server" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.

See the *Oracle Endeca Server Query Language Reference* for information about writing EQL queries. [Figure 2–44](#) shows a sample Oracle Endeca query.

Figure 2–44 Sample Oracle Endeca Query

To create a data set using an EQL query against an Oracle Endeca Server data source:

1. Click the **New Data Set** toolbar button and select **Oracle Endeca Query**. The New Data Set - Oracle Endeca Query dialog launches.
2. Enter a name for this data set.
3. Select the **Data Store** for this data set.
4. Enter the EQL query by direct entry or by copying and pasting from another source such as an Oracle Endeca Information Discovery view.
5. Click **OK**.

2.14.1 Additional Notes on Oracle Endeca Query Data Sets

For data sets retrieved from the Oracle Endeca Server, group breaks, data links and group-level functions are not supported.

The following are supported:

- Global level functions
- Setting the value for elements if null
- Group Filters

For more information about the above supported features, see [Chapter 3, "Structuring Data."](#)

2.15 Using Data Stored as a Character Large Object (CLOB) in a Data Model

BI Publisher supports using data stored as a character large object (CLOB) data type in your data models. This feature enables you to use XML data generated by a separate process and stored in your database as input to a BI Publisher data model.

Use the Query Builder to retrieve the column in your SQL query, then use the data model editor to specify how you want the data structured. When the data model is executed, the data engine can structure the data either as:


- A plain character set within an XML tag name that can be displayed in a report (for example, an Item Description)
- Structured XML

Note: Ensure that your data does not include line feeds or carriage returns. Line feeds and carriage returns in your data may not render as expected in BI Publisher report layouts.

To create a data set from data stored as a CLOB:


1. On the toolbar, click **New Data Set** and then select **SQL Query**. The New Data Set - SQL Query dialog launches.
2. Enter a name for the data set.
3. If you are not using the default data source for this data set, select the **Data Source** from the list.
4. Enter the SQL query or use the **Query Builder** to construct your query to retrieve the CLOB data column. See [Section 2.3.3, "Using the SQL Query Builder"](#) for information on the Query Builder utility. [Figure 2–45](#) shows an example query in which the CLOB data is stored in a column named "DESCRIPTION".

Figure 2–45 Sample Query



5. After entering the query, click **OK** to save. BI Publisher validates the query.
6. By default, the data model editor assigns the CLOB column the "CLOB" data type. To change the data type to XML, click the data type icon and select XML, as shown in [Figure 2–46](#).

Figure 2–46 Changing the Data Type to XML



2.15.1 How the Data Is Returned

When you execute the query, if the CLOB column contains well-formed XML, and you select the XML data type, the data engine returns the XML data, structured within the CLOB column tag name.

Example output when data type is XML:

Note the <DESCRIPTION> element contains the XML data stored in the CLOB column, as shown in [Figure 2-47](#).

Figure 2-47 Example Data Structure When the Data Type is XML

```

-<DATA_DS>
  -<G_1>
    <EMPLOYEE_ID>102</EMPLOYEE_ID>
  -<DESCRIPTION>
    -<DATA_DS>
      -<G_Q1>
        <DEPTNO>10</DEPTNO>
        <DNAME>PURCHASE</DNAME>
        <LOC>HQ</LOC>
      -<G_Q2>
        <DEPTNO_1>10</DEPTNO_1>
        <EMPNO>10001</EMPNO>
        <ENAME>SCOTT</ENAME>
        <SAL>5000</SAL>
      </G_Q2>
    +<G_Q2></G_Q2>
    </G_Q1>
  -<G_Q1>
    <DEPTNO>20</DEPTNO>
    <DNAME>FINANCE</DNAME>
    <LOC>HQ</LOC>

```

Example output when data type is CLOB

If you select to return the data as the CLOB data type, the returned data is structured as shown in [Figure 2-48](#).

Figure 2-48 Example Data Structure When Data Type Is CLOB

```

-<DATA_DS>
  -<G_1>
    <EMPLOYEE_ID>102</EMPLOYEE_ID>
  -<DESCRIPTION>
    <DATA_DS> <G_Q1> <DEPTNO>10</DEPTNO>
    <DNAME>PURCHASE</DNAME> <LOC>HQ</LOC> <G_Q2> <DEPTNO_1>10</DEPTNO_1>
    <EMPNO>10001</EMPNO> <ENAME>SCOTT</ENAME> <SAL>5000</SAL> <G_Q2> <G_Q2>
    <DEPTNO_1>10</DEPTNO_1> <EMPNO>10002</EMPNO> <ENAME>SMITH</ENAME>
    <SAL>3000</SAL> </G_Q2> </G_Q1> <G_Q1> <DEPTNO>20</DEPTNO>
    <DNAME>FINANCE</DNAME> <LOC>HQ</LOC> <G_Q2> <DEPTNO_1>20</DEPTNO_1>
    <EMPNO>10003</EMPNO> <ENAME>AMY</ENAME> <SAL>5500</SAL> <G_Q2> <G_Q2>
    <DEPTNO_1>20</DEPTNO_1> <EMPNO>10004</EMPNO> <ENAME>MARLIN</ENAME>
    <SAL>4000</SAL> </G_Q2> </G_Q1> <G_Q1> <DEPTNO>30</DEPTNO>
    <DNAME>CORPORATE</DNAME> <LOC>HQ</LOC> <G_Q1> </DATA_DS>
  </DESCRIPTION>
</G_1>
</DATA_DS>

```

2.15.1.1 Additional Notes on Data Sets Using CLOB Column Data

For specific notes on using CLOB column data in a bursting query, see [Section 7.3](#), "Adding a Bursting Definition to Your Data Model."

2.15.2 Handling XHTML Data Stored in a CLOB Column

BI Publisher can retrieve data stored in the form of XHTML documents stored in a database CLOB column and render the markup in the generated report. To enable the BI Publisher report rendering engine to handle the markup tags, you must wrap the XHTML data in a CDATA section within the XML report data that is passed by the data engine.

It is recommended that you store the data in the database wrapped with the CDATA section. You can then use a simple select statement to extract the data. If the data is not wrapped in the CDATA section, then you must include in your SQL statement instructions to wrap it.

The following sections describe how to extract XHTML data in each case:

- [Retrieving XHTML Data Wrapped in CDATA](#)
- [Wrapping the XHTML Data in CDATA in the Query](#)

To display the markup in a report, you must use the syntax described in "Rendering HTML Formatted Data in a Report" in *Oracle Fusion Middleware Report Designer's Guide for Oracle Business Intelligence Publisher*. This section also describes the supported HTML formats. Rendering the HTML markup in a report is supported for RTF templates only.

2.15.2.1 Retrieving XHTML Data Wrapped in CDATA

Assume you have the following data stored in a database column called "CLOB_DATA":


```
<![CDATA[
<p><font style="font-style: italic; font-weight: bold;" size="3">
<a href="http://www.oracle.com">oracle</a></font> </p>
<p><font size="6"><a href="http://docs.oracle.com/">Oracle Documentation</a>
</font></p>
]]>
```

Retrieve the column data using a simple SQL statement, for example:

```
select CLOB_DATA as "RTECODE"
  from MYTABLE
```

In the data model editor, set the data type of the RTECODE column to XML, as shown in [Figure 2-49](#).

Figure 2-49 Set Data Type to XML



2.15.2.2 Wrapping the XHTML Data in CDATA in the Query

Assume you have the following data stored in a database column called "CLOB_DATA":

```
<p><font style="font-style: italic; font-weight: bold;" size="3">
```

```
<a href="http://www.oracle.com">oracle</a></font> </p>
<p><font size="6"><a href="http://docs.oracle.com/">Oracle Documentation</a>
</font></p>
```

Use the following syntax in your SQL query to retrieve it and wrap it in the CDATA section:

```
select '<![CDATA' || '[' || CLOB_DATA || ']' || '>' as "RTECODE"
from MYTABLE
```

In the data model editor, set the data type of the RTECODE column to XML, as shown in [Figure 2-49](#).


2.16 Testing Data Models and Generating Sample Data

The data model editor enables you to test your data model and view the output to ensure your results are as expected. After running a successful test, you can choose to save the test output as sample data for your data model. You can also use the Export feature to export sample data to a file. If your data model fails to run, you can view the data engine log.

To test your data model:


1. In the data model editor, select the **Data** tab, as shown in [Figure 2-50](#).

Figure 2-50 Select the Data Model Editor Data Tab



2. For SQL Query, Oracle BI Analysis, View Object, and Oracle Endeca Query data sets: On the Data tab, select the number of rows to return as shown in [Figure 2-51](#). If you included parameters, enter the desired values for the test.


Figure 2-51 Select the Number of Rows to Return



3. Click **View** to display the XML that is returned by the data model.
4. Select one of the following options to display the sample data:
 - Use **Tree View** to view the sample data in a data hierarchy. This is the default display option.
 - Use **Table View** to view the sample data in a formatted table like you see in BI Publisher reports.

To save the test data set as sample data for the data model:

1. After the data model has successfully run, click **Save as Sample Data**, as shown in [Figure 2-52](#). The sample data is saved to the data model. See [Section 1.7.2, "Attachments to the Data Model"](#) for more information.

Figure 2–52 Save as Sample Data**To export the test data:**

1. For SQL Query, Oracle BI Analysis, View Object, and Oracle Endeca Query data sets: On the Data tab, select the number of rows to return.
2. After the data model has successfully run, click **Export**. You are prompted to open or save the file to a local directory.

To view the data engine log:

1. Click **View Data Engine Log**. You are prompted to open or save the file to a local directory. The data engine log file is an XML file.

2.17 Including User Information Stored in System Variables in Your Report Data

BI Publisher stores information about the current user that can be accessed by your report data model. The user information is stored in system variables as described in [Table 2–2](#).

Table 2–2 User Information Stored in Variables

System Variable	Description
xdo_user_name	User ID of the user submitting the report. For example: Administrator
xdo_user_roles	Roles assigned to the user submitting the report. For example: XMLP_ADMIN, XMLP_SCHEDULER
xdo_user_report_oracle_lang	Report language from the user's account preferences. For example: ZHS
xdo_user_report_locale	Report locale from the user's account preferences. For example: en-US
xdo_user_ui_oracle_lang	User interface language from the user's account preferences. For example: US
xdo_user_ui_locale	User interface locale from the user's account preferences. For example: en-US

2.17.1 Adding the User System Variables as Elements

To add the user information to the data model, you can define the variables as parameters and then define the parameter value as an element in your data model. Or, you can simply add the variables as parameters then reference the parameter values in your report.

The following query:

```
select
:xdo_user_name as USER_ID,
:xdo_user_roles as USER_ROLES,
:xdo_user_report_oracle_lang as REPORT_LANGUAGE,
:xdo_user_report_locale as REPORT_LOCALE,
:xdo_user_ui_oracle_lang as UI_LANGUAGE,
:xdo_user_ui_locale as UI_LOCALE
from dual
```

returns the following results:

```
<?xml version="1.0" encoding="UTF-8"?>
<! - Generated by Oracle BI Publisher - >
<DATA_DS>
<G_1>
<USER_ROLES>XMLP_TEMPLATE_DESIGNER, XMLP_DEVELOPER, XMLP_ANALYZER_EXCEL, XMLP_
ADMIN, XMLP_ANALYZER_ONLINE, XMLP_SCHEDULER </USER_ROLES>
<REPORT_LANGUAGE>US</REPORT_LANGUAGE>
<REPORT_LOCALE>en_US</REPORT_LOCALE>
<UI_LANGUAGE>US</UI_LANGUAGE>
<UI_LOCALE>en_US</UI_LOCALE>
<USER_ID>administrator</USER_ID>
</G_1>
</DATA_DS>
```

2.17.2 Sample Use Case: Limit the Returned Data Set by User ID

The following example limits the data returned by the user ID:

```
select EMPLOYEES.LAST_NAME as LAST_NAME,
EMPLOYEES.PHONE_NUMBER as PHONE_NUMBER,
EMPLOYEES.HIRE_DATE as HIRE_DATE,
:xdo_user_name as USERID
from HR.EMPLOYEES EMPLOYEES
where lower(EMPLOYEES.LAST_NAME) = :xdo_user_name
```

Notice the use of the lower() function, the xdo_user_name is always be in lowercase format. BI Publisher does not have a USERID so you must use the user name and either use it directly in the query; or alternatively you could query against a lookup table to find a user id.

2.17.2.1 Creating Bind Variables from LDAP User Attribute Values

To bind user attribute values stored in your LDAP directory to a data query you can define the attribute names to BI Publisher to create the bind variables required.

2.17.2.1.1 Prerequisite The attributes that can be used to create bind variables must be defined in the Security Configuration page by an administrator. The attributes are defined in the Attribute Names for Data Query Bind Variables field of the LDAP Security Model definition. See the section "Configuring BI Publisher to Recognize the LDAP Server" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business*

Intelligence Publisher for information about this field. Any attribute defined for users can be used (for example: `memberOf`, `sAMAccountName`, `primaryGroupID`, `mail`).

2.17.2.1.2 How BI Publisher Constructs the Bind Variable

You can reference the attribute names that you enter in the Attribute Names for Data Query Bind Variables field of the LDAP Security Model definition in the query as follows:

```
xdo_<attribute name>
```

Assume that you have entered the sample attributes: `memberOf`, `sAMAccountName`, `primaryGroupID`, `mail`. These can then be used in a query as the following bind variables:

```
xdo_memberof  
xdo_SAMACCOUNTNAME  
xdo_primaryGroupID  
xdo_mail
```

Note that the case of the attribute is ignored; however, the "xdo_" prefix must be lowercase.

Use these in a data model as follows:

```
SELECT  
:xdo_user_name AS USER_NAME,  
:xdo_user_roles AS USER_ROLES,  
:xdo_user_ui_oracle_lang AS USER_UI_LANG,  
:xdo_user_report_oracle_lang AS USER_REPORT_LANG,  
:xdo_user_ui_locale AS USER_UI_LOCALE,  
:xdo_user_report_locale AS USER_REPORT_LOCALE,  
:xdo_SAMACCOUNTNAME AS SAMACCOUNTNAME,  
:xdo_memberof as MEMBER_OF,  
:xdo_primaryGroupID as PRIMARY_GROUP_ID,  
:xdo_mail as MAIL  
FROM DUAL
```

The LDAP bind variables return the values stored in the LDAP directory for the user that is logged in.

Structuring Data

This chapter describes techniques for structuring the data that is returned by BI Publisher's data engine, including grouping, linking, group filters, and group-level and global-level functions.

This chapter includes the following sections:

- [Section 3.1, "Working with Data Models"](#)
- [Section 3.2, "Features of the Data Model Editor"](#)
- [Section 3.3, "About the Interface"](#)
- [Section 3.4, "Creating Links Between Data Sets"](#)
- [Section 3.5, "Creating Element-Level Links"](#)
- [Section 3.6, "Creating Group-Level Links"](#)
- [Section 3.7, "Creating Subgroups"](#)
- [Section 3.8, "Moving an Element Between a Parent Group and a Child Group"](#)
- [Section 3.9, "Creating Group-Level Aggregate Elements"](#)
- [Section 3.10, "Creating Group Filters"](#)
- [Section 3.11, "Performing Element-Level Functions"](#)
- [Section 3.12, "Setting Element Properties"](#)
- [Section 3.13, "Sorting Data"](#)
- [Section 3.14, "Performing Group-Level Functions"](#)
- [Section 3.15, "Performing Global-Level Functions"](#)
- [Section 3.16, "Using the Structure View to Edit Your Data Structure"](#)
- [Section 3.17, "Function Reference"](#)

3.1 Working with Data Models


The Data Model diagram helps you to quickly and easily define data sets, break groups, and totals for a report based on multiple data sets.

3.1.1 About Multipart Unrelated Data Sets

If you do not link the data sets (or queries) the data engine produces a multipart unrelated query data set.


For example, in the data model shown in [Figure 3-1](#), one query selects products and another selects customers. Notice that there is no relationship between the products and customers.

Figure 3-1 Multipart Unrelated Data Set



This results in the data structure shown in [Figure 3-2](#).


Figure 3-2 Data Structure of Multipart Unrelated Data Set




3.1.2 About Multipart Related Data Sets

In many cases, the data fetched for one part of the data set (or query) is determined by the data fetched for another part. This is often called a "master/detail," or "parent/child," relationship, and is defined with a data link between two data sets (or queries). When you run a master/detail data model, each row of the master (or parent) query causes the detail (or child) query to be executed, retrieving only matching rows.

In the example shown in [Figure 3-3](#), two data sets are linked by the element Customer ID. The Orders data set a child of the Customers data set.

Figure 3–3 Multipart Related Data Sets

This produces the data structure shown in [Figure 3–4](#).

Figure 3–4 Data Structure of Multipart Related Data Set

3.1.3 Guidelines for Working with Data Sets

Following are recommended guidelines for building data models:

- Reduce the number of data sets or queries in your data model as much as possible. In general, the fewer data sets and queries you have, the faster your data model will run. While multiquery data models are often easier to understand, single-query data models tend to execute more quickly. It is important to understand that in parent-child queries, for every parent, the child query is executed.
- You should only use multiquery data models in the following scenarios:
 - To perform functions that the query type, such as a SQL query, does not support directly.

- To support complex views (for example, distributed queries or GROUP BY queries).
- To simulate a view when you do not have or want to use a view.

3.2 Features of the Data Model Editor

The data model editor enables you to combine data from multiple data sets into a single XML data structure. Data sets from multiple data sources can be merged either as sequential XML or at line-level to create a single combined hierarchical XML. Using the data model editor you can easily combine data from the following data set types: SQL query, OLAP (MDX query), LDAP, and Microsoft Excel.

The data model editor supports the following


- **Group data** — Groups are created to organize the columns in your report. Groups can do two things: separate a query's data into sets, and filter a query's data.

When you create a query, the data engine creates a group that contains the columns selected by the query; you can create groups to modify the hierarchy of the data appearing in a data model. Groups are used primarily when you want to treat some columns differently than others. For example, you create groups to produce subtotals or create breaks.

- **Link data** — Define master-detail links between data sets to group data at multiple levels.
- **Aggregate data** — Create group level totals and subtotals.
- **Transform data** — Modify source data to conform to business terms and reporting requirements.
- **Create calculations** — Compute data values that are required for your report that are not available in the underlying data sources.

The data model editor provides functions at the element level, the group level, and the global level. Note that not all data set types support all functions. See the Important Notes section that accompanies your data set type for limitations. [Figure 3-5](#) highlights some of the features and actions available in the data model editor.


Figure 3–5 Features of Data Model Editor



3.3 About the Interface

By default, the data sets that you created are shown in the Diagram View as separate objects, as seen in Figure 3–6.

Figure 3–6 Diagram View



The data set structure builder has three views:

- Diagram View** — (Shown in Figure 3–6) This view displays your data sets and enables you to graphically create links and filters, add elements based on expressions, add aggregate functions and global-level functions, edit element properties, and delete elements. The Diagram View is typically the view you use to build your data structure.
- Structure View** — This view has two modes:
 - Table View and Output

The table view displays element properties in a table and enables you to update XML element alias names, presentation names of the elements, sorting, null


values, and reset options. [Figure 3-7](#) shows the structure Table View.

Figure 3-7 Structure Table View

Table View Output					
	XML View			Business View	
Data Source	XML Tag Name	Sorting	Value If Null	Display Name	Data Type
Report Data					
Data Structure	DATA_D5				
Departments	G_1			G_1	
DEPARTMENT_ID	DEPARTMENT_ID			DEPARTMENT_ID	999
MANAGER_ID	MANAGER_ID			MANAGER_ID	999
DEPARTMENT_NAME	DEPARTMENT_NAME			DEPARTMENT_NAME	abc
Employees	G_2			G_2	
EMPLOYEE_ID	EMPLOYEE_ID			EMPLOYEE_ID	999
FIRST_NAME	FIRST_NAME			FIRST_NAME	abc
LAST_NAME	LAST_NAME			LAST_NAME	abc
EMAIL	EMAIL			EMAIL	abc
PHONE_NUMBER	PHONE_NUMBER			PHONE_NUMBER	abc
HIRE_DATE	HIRE_DATE			HIRE_DATE	
JOB_ID	JOB_ID			JOB_ID	abc

The **Output** view provides a clear view of the XML structure that is generated. The Output view cannot be updated. [Figure 3-8](#) shows the Output view.

Figure 3-8 Output View



- Code View** — This view displays the data structure code created by the data structure builder that is read by the data engine. The code view cannot be updated. [Figure 3-9](#) shows the code view.

Figure 3–9 Code View

```

<output rootName="DATA_DS" uniqueRowName="false">
<nodeList name="data-structure">
<dataStructure tagName="DATA_DS">
<group name="G_1" label="G_1" source="Departments">
<element name="DEPARTMENT_ID" value="DEPARTMENT_ID" label="DEPARTMENT_ID" dataType="xsd:integer" breakOrder="" fieldOrder="1"/>
<element name="DEPARTMENT_NAME" value="DEPARTMENT_NAME" label="DEPARTMENT_NAME" dataType="xsd:string" breakOrder="" fieldOrder="2"/>
<element name="MANAGER_ID" value="MANAGER_ID" label="MANAGER_ID" dataType="xsd:integer" breakOrder="" fieldOrder="3"/>
</group>
<group name="G_2" label="G_2" source="Employees">
<element name="EMPLOYEE_ID" value="EMPLOYEE_ID" label="EMPLOYEE_ID" dataType="xsd:integer" breakOrder="" fieldOrder="1"/>
<element name="FIRST_NAME" value="FIRST_NAME" label="FIRST_NAME" dataType="xsd:string" breakOrder="" fieldOrder="2"/>
<element name="LAST_NAME" value="LAST_NAME" label="LAST_NAME" dataType="xsd:string" breakOrder="" fieldOrder="3"/>
<element name="EMAIL" value="EMAIL" label="EMAIL" dataType="xsd:string" breakOrder="" fieldOrder="4"/>
<element name="PHONE_NUMBER" value="PHONE_NUMBER" label="PHONE_NUMBER" dataType="xsd:string" breakOrder="" fieldOrder="5"/>
<element name="MANAGER_ID" value="MANAGER_ID" label="MANAGER_ID" dataType="xsd:integer" breakOrder="" fieldOrder="6"/>
<element name="DEPARTMENT_ID" value="DEPARTMENT_ID" label="DEPARTMENT_ID" dataType="xsd:integer" breakOrder="" fieldOrder="7"/>
</group>
</dataStructure>
</nodeList>
</output>

```

3.4 Creating Links Between Data Sets

Joining and structuring data at the source into one combined data set is sometimes not possible. For example, you cannot join data at the source when data resides in disparate sources such as Microsoft SQL Server and an Oracle database. You can use the BI Publisher data engine to combine and structure data after you extract it from the data source. Even if your data is coming from the same source, if you are creating large reports or documents with potentially hundreds of thousands of rows or pages, structuring your data so that it matches the intended layout optimizes document generation.

Create a link to define a master-detail (or parent-child) relationship between two data sets. You can create links as element-level links or group-level links. The resulting, hierarchical XML data is the same. Creating links as element-level links is the preferred method. Group-level links are provided for backward compatibility with data templates from earlier versions of BI Publisher.

A data link (or parent-child relationship) relates the results of multiple queries. A data link can establish these relationships:

- Between one query's column and another query's column
- Between one query's group and another query's group (this is useful when you want the child query to know about its parent's data)

3.4.1 About Element-Level Links

Element-level links create a bind (join) between two data sets and define a master-detail (parent-child) relationship between them. This is the preferred method of defining master detail relationships between data sets. The simplest way to link data sets is by creating element-level links because they do not require you to code a join between the two data sets through a bind variable.

3.4.2 About Group-Level Links

Group-level links also determine the way data sets are structured as hierarchical XML, but lack the join information that the data engine needs to execute the master and detail queries. When you define a group-level link, you must also update your query with a link between the two data sets through a unique bind variable.


3.5 Creating Element-Level Links

Link data sets to define a master-detail (or parent-child) relationship between two data sets. Defining an element-level link enables you to establish the binding between the elements of the master and detail data sets.

To define an element-level link, do one of the following:


- Open the element action menu and click **Create Link**.

Figure 3–10 *Creating a Link Using the Element Action Menu*




The **Create Link** dialog launches and displays the elements from the other data sets. Choose the element and click **OK** to create the link. The Create Link dialog is shown in [Figure 3–11](#).

Figure 3–11 *Create Link Dialog*




- Alternatively, from the parent group, click and drag the element you want to bind to the matching element in the child group, as shown in [Figure 3–12](#).

Figure 3–12 Creating a Link by Dragging and Dropping the Bind Element



- After dropping the element from the parent data set to the matching element on the child data set, a connector displays between the data sets. Pause your cursor over the connector to display the link (as shown in Figure 3–13).

Figure 3–13 Displaying the Link



3.5.1 Deleting Element-Level Links

To delete an element link:

1. Pause your cursor over the element connector to display the linked element names and the delete button.
2. Click the delete button.


Or, alternatively:

1. Open the element action menu for either element and click **Delete Link**.

3.6 Creating Group-Level Links

A group-level link defines a master-detail relationship between two data sets. The following figure shows two data sets with a group-level link defined. Next to the data sets the resulting XML data structure is shown, as in [Figure 3-14](#).


Figure 3-14 Resulting XML Data Structure




To define a group-level link:

1. In the parent group, click **Menu** (in the upper right corner of the object).
2. Click **Create Group Link** as shown in [Figure 3-15](#).

Figure 3-15 Creating a Group Link



3. In the **Create Group Link** dialog, select the child group and click **OK**. The **Create Link** dialog is shown in [Figure 3-16](#).

Figure 3–16 Create Link Dialog

4. Click **Menu** and then click **Edit Data Set** to add the bind variables to your query.
An example is shown in [Table 3–1](#).

Table 3–1 Example: Edit Data Set

Data Set: DEPT	Data Set: EMP
<pre>Select DEPT.DEPTNO as DEPTID, DEPT.DNAME as DNAME, DEPT.LOC as LOC from OE.DEPT DEPT</pre>	<pre>Select EMP.EMPNO as EMPNO, EMP.ENAME as ENAME, EMP.JOB as JOB, EMP.MGR as MGR, EMP.HIREDATE as HIREDATE, EMP.SAL as SAL, EMP.COMM as COMM, EMP.DEPTNO as DEPTNO from OE.EMP EMP where DEPTNO=:DEPTID</pre>

Important: A unique bind variable must be defined in the child query.

3.6.1 Deleting Group-Level Links

To delete a group link:

1. In the parent group, click **Menu** (in the upper right corner of the object).
2. Click **Delete Group Link**.
3. In the **Delete Group Link** dialog, select the **Child Group** from the list and click **OK**.


3.7 Creating Subgroups

In addition to creating parent-child structures by linking two data sets, you can also group elements in the same data set by other elements. This might be helpful if your query returns data that has header data repeated for each detail row. By creating a subgroup you can shape the XML data for better, more efficient document generation.

To create a subgroup:


1. Select the element by which you want to group the other elements in the data set.
2. Click the element action menu icon to open the menu and select **Group by** as shown in [Figure 3–17](#).

Figure 3–17 Creating a Subgroup



This creates a new group within the displayed data set. The following figure shows the G_3 data set grouped by the element COMPANY. This creates a new group called G_4, that contains the other four elements in the data set. [Figure 3–18](#) shows how the grouped data set is displayed in the Diagram View along with the structure.

Figure 3–18 Subgroup Data Structure



You can perform any of the group actions on the new group you have created.

To remove a subgroup:


1. On the group's title bar, click **Menu** and then click **Ungroup**.

3.8 Moving an Element Between a Parent Group and a Child Group

Once you have created a group within your data set, two new options display on the element action menu that enable you to move elements between the parent and child groups.

For the element that you want to move, click the element action icon to open the menu. If the element is in the parent group and you want to move it to the child group, and then **Move this element to Child Group**.

If the element is in the child group and you want to move it to the parent group, select and then **Move this element to Parent Group**. In [Figure 3–19](#), the element action menu for OFFICE_DSC displays the option to move the element to the parent group.

Figure 3–19 Moving Element from Child Group to Parent Group

Important: Before moving an element be aware of any dependencies on other elements.

3.9 Creating Group-Level Aggregate Elements

You can use the data model editor to aggregate data at the group or report level. For example, if you group sales data by Customer Name, you can aggregate sales to get a subtotal for each customer's sales. Note that you can only aggregate data for at the parent level for a child element.

The aggregate functions are:


- **Average** — Calculates the average of all the occurrences of an element.
- **Count** — Counts the number of occurrences of an element.
- **First** — Displays the value of the first occurrence of an element in the group.
- **Last** — Displays the value of the last occurrence of an element in the group.
- **Maximum** — Displays the highest value of all occurrences of an element in the group.
- **Minimum** — Displays the lowest value of all occurrences of an element in a group.
- **Summary** — Sums the value of all occurrences of an element in the group.

To create group-level aggregate elements:

1. Drag the element to the **Drop here for aggregate function** field in the parent group.

[Figure 3–20](#) shows creating a group-level aggregate function in the G_DEPT based on the SALARY element.


Figure 3–20 Creating a Group-Level Aggregate Function



Once you drop the element, a new element is created in the parent group. By default, the Count function is applied. The icon next to the name of the new aggregate element indicates the function. Pause your cursor over the icon to display the function.


Figure 3–21 shows the new aggregate element, CS_1, with the default Count function defined.

Figure 3–21 New Element Created by Group-Level Aggregate Function




- To change the function: Click the function icon to view a list of available functions and choose from the list, as shown in Figure 3–22.

Figure 3–22 Choosing a Function



- To rename the element or update other properties, click the element's **Action** menu icon. On the menu, click **Properties**. The **Properties** dialog is shown in [Figure 3–23](#).

Figure 3–23 Properties Dialog



Important: Be careful when renaming an element as it can have dependency on other elements.

Set the properties described in [Table 3–2](#) as needed.

Table 3–2 Element Properties

Property	Description
Column Name	The internal name assigned to the element by the BI Publisher data model editor. This name cannot be updated.
Alias (XML Tag Name)	BI Publisher assigns a default tag name for the element in the XML data file. You can update this tag name to assign a more user-friendly name within the data file.
Display Name	The Display Name appears in the report design tools. Update this name to be meaningful to your business users.
Function	If you have not already selected the desired function, then you can select it from the list here.
Data Type	BI Publisher assigns a default data type of Integer or Double depending on the function. Some functions also provide the option of Float.
Value if Null	If the value returned from the function is null, you can supply a default value here to prevent having a null in your data.
Round	By default, the value is rounded to the nearest third decimal. You can change the round value, if needed.
Do Not Reset	By default, the function resets at the group level. For example, if your data set is grouped by DEPARTMENT_ID, and you have defined a sum function for SALARY, then the sum is reset for each group of DEPARTMENT_ID data, giving you the sum of SALARY for that department only. If instead you want the function to reset only at the global level, and not at the group level, select Do Not Reset . This creates a running total of SALARY for all departments. Note that this property is for group level functions only.

3.10 Creating Group Filters


Filters enable you to conditionally remove records selected by your queries. Groups can have two types of filters:

- Expression — Create an expression using predefined functions and operators
- PL/SQL Function — Create a custom filter

To create a group filter:

1. Click **Menu**, and then select **Create Group Filter**. The **Edit Group Filter** dialog is displayed as shown in [Figure 3–24](#).

Figure 3–24 Edit Group Filter Dialog



2. Select the Group Filter Type: **Expression** or **PL/SQL**.

Note: For PL/SQL filters, you must first specify the PL/SQL Package as the **Oracle DB Default Package** in the data model properties. See [Section 1.7, "Setting Data Model Properties."](#)

3. Enter the Filter:

- To enter an expression, select the elements and click the shuttle button to move the element to the Group Filter definition box. Click the predefined functions and operators to insert them in the Group Filter box.


Refer to [Section 3.17, "Function Reference"](#) for a description of the available functions.

Click **Validate Expression** to ensure that the entry is valid.

- To enter a PL/SQL function, select the PL/SQL package from the Available box and click the shuttle button to move the function to the Group Filter box.

Your PL/SQL function in the default package must return a Boolean type.

After you have added the group filter, the data set object displays the filter indicator, as shown in [Figure 3–25](#).

Figure 3–25 Filter Indicator

To edit or delete a group filter:

1. Click **Menu** for the data set.
2. Choose the appropriate action:
 - To edit the group filter, choose **Edit Group Filter** to launch the Group Filter dialog for editing.
 - To delete the group filter, choose **Delete Group Filter**.

3.11 Performing Element-Level Functions

You can perform the following functions at the element level:

- Group by an element to create a subgroup, as described in [Section 3.7, "Creating Subgroups"](#)
- Create element-level links between data sets, as described in [Section 3.5, "Creating Element-Level Links"](#)
- Set element properties, as described in [Section 3.12, "Setting Element Properties"](#)


3.12 Setting Element Properties

You can set properties for individual elements. Note that these properties are also editable from the Structure View. If you need to update multiple element properties, it may be more efficient to use the Structure View. See [Section 3.16, "Using the Structure View to Edit Your Data Structure."](#)

To set element-level properties using the element dialog:

1. Click the element's action menu icon. From the menu, select **Properties**. The Properties dialog is shown in [Figure 3–26](#).

Figure 3–26 Properties Dialog



2. Set the properties as needed, as described in [Table 3–3](#).

Table 3–3 Element Properties

Property	Description
Alias	BI Publisher assigns a default tag name to the element in the XML data file. You can update this tag name to assign a more user-friendly name within the data file.
Display Name	The Display Name appears in the report design tools. Update this name to be meaningful to your business users.
Data Type	BI Publisher assigns a default data type of Integer or Double depending on the function. Some functions also provide the option of Float.
Sort Order	You can sort XML data in a group by one or more elements. For example, if in a data set employees are grouped by department and manager, you can sort the XML data by department. Within each department you can group and sort data by manager, and within each manager subgroup, employees can be sorted by salary. If the element is not in a parent group, the Sort Order property is not available.
Value if Null	If the value returned from the function is null, you can supply a default value here to prevent having a null in your data.

3.13 Sorting Data


Sorting is supported for parent group break columns only. For example, if a data set of employees is grouped by department and manager, you can sort the XML data by department. Within each department you can group and sort data by manager. If you know how the data should be sorted in the final report, you specify sorting at data generation time to optimize document generation.

To apply a sort order to a group:

1. Click the action menu icon of the element you want to sort by. From the menu, select **Properties**.
2. Select the **Sort Order**.

[Figure 3–27](#) shows the **Properties** dialog for the DEPARTMENT_ID element with the Sort Order list displayed.

Figure 3–27 Properties Dialog Showing Sort Order List



3.14 Performing Group-Level Functions

This section describes how to perform group-functions. It includes the following topics:

- [Section 3.14.1, "The Group Action Menu"](#)
- [Section 3.14.2, "Editing the Data Set"](#)
- [Section 3.14.3, "Removing Elements from the Group"](#)
- [Section 3.14.4, "Editing the Group Properties"](#)


3.14.1 The Group Action Menu

The **Menu** button is available at the group level and enables you to perform the following:

- Create and delete group links, as described in [Section 3.6, "Creating Group-Level Links"](#)
- Create, edit, and delete group filters, as described in [Section 3.10, "Creating Group Filters"](#)
- Add an element to the group based on an expression, as described in [Section 3.15.2, "Adding a Group-Level or Global-Level Element by Expression"](#)
- Edit the data set, as described in [Section 3.14.2, "Editing the Data Set"](#)
- Remove elements from the group, as described in [Section 3.14.3, "Removing Elements from the Group"](#)
- Edit group properties, as described in [Section 3.14.4, "Editing the Group Properties"](#)

The group-level Menu button is shown in [Figure 3–28](#).

Figure 3–28 Group-Level Actions Menu



3.14.2 Editing the Data Set

To edit the underlying data set:

1. Click **Edit Data Set** to launch the data set editor.

See the appropriate section for the data set type in [Chapter 2, "Creating Data Sets"](#) for more information.


3.14.3 Removing Elements from the Group

To remove an element from the group:

1. On the element row, click the menu and then click **Remove Element**. An example is shown in [Figure 3–29](#).

Note: You can only remove elements added as a group function (sum, count, and so on) or added as an expression.

Figure 3–29 Removing an Element



3.14.4 Editing the Group Properties

To edit the group properties:

1. Click **Menu** and select **Properties**.
2. Edit the **Group Name** and click **OK**, as shown in [Figure 3–30](#).

Figure 3–30 Edit the Group Name


3.15 Performing Global-Level Functions

The Global Level Functions object enables you to add elements to your report data set at the top report level. You can add the following types of elements as top-level data:

- Elements based on aggregate functions
- Elements based on expressions
- Elements based on PL/SQL statements (for Oracle Database data sources)

Important: If you select a data type of Integer for any calculated element and the expression returns a fraction, the data is not truncated.

The **Global Level Functions** object is shown in [Figure 3–31](#). To add elements based on aggregate functions, drag the element to the "Drop here for aggregate function" space of the object. To add an element based on an expression or PL/SQL, click **Menu**, and choose the appropriate action.

Figure 3–31 Global Level Functions Object


3.15.1 Adding a Global-Level Aggregate Function

To add a global aggregate function:

1. Drag and drop the data element from the data set to the "Drop here for aggregate function" area of the Global Level Functions object.

For example, [Figure 3–32](#) shows creating a global level aggregate function based on the Salary element.

Figure 3–32 Creating Global-Level Aggregate Function




2. When you release the mouse, the data model editor assigns a default name to the aggregate element and assigns Count as the default function. Available functions are:

- Count
- Average
- First
- Last
- Maximum
- Minimum
- Summary

To change the function, click the function icon to the left of the new element name and choose the function from the list.

Figure 3–33 shows the function for the new global level element CS_1 being modified from Count to Average.

Figure 3–33 Applying a Function



3. To change the default name, click the actions icon to the right of the element name and click **Properties** to launch the **Edit Properties** dialog, See [Section 3.12, "Setting Element Properties."](#) for more about the properties available on this dialog.


3.15.2 Adding a Group-Level or Global-Level Element by Expression

To add a group-level or global-level element by expression:

1. To add a group-level element: On the **Group** object, click **Menu** and select **Add Element by Expression**.

To add a global level element: On the **Global Level Functions** object, click **Menu** and select **Add Element by Expression**, as shown in [Figure 3–34](#).

Figure 3–34 Add Element: by Expression



2. In the **Add Element by Expression** dialog, enter the fields, as shown in [Figure 3–35](#).

Figure 3–35 Add Element by Expression Dialog




Table 3–4 Add Element by Expression Dialog Fields

Field	Description
Name	Enter a name for this element.
Display Name	The Display Name appears in the report design tools. Enter a name that is meaningful to your business users.
Data Type	Select from the list of data types: String, Integer, Double, Float, or Date.

3. Enter the expression.

Use the shuttle arrow to move the data elements required for the expression from the **Available** box to the **Expression** box.

Click an operator to insert it in the **Expression** box, or choose from the function list.

Refer to [Section 3.17, "Function Reference"](#) for a description of the available functions.

4. Click **Validate Expression** to validate.

3.15.3 Adding a Global-Level Element by PL/SQL

The PL/SQL function must return a VARCHAR data type.

To add a global-level element by PL/SQL:

1. On the Properties page, specify the PL/SQL Package as the **Oracle DB Default Package** in the data model properties. See [Section 1.7, "Setting Data Model Properties."](#)
2. On the **Global Level Functions** object, click **Menu**, and then click **Add Element by PL/SQL**.
3. In the **Add Element by PL/SQL** dialog, enter the fields, as shown in [Figure 3–36](#) and as described in [Table 3–5](#).

Figure 3–36 Add Element by PL/SQL Dialog




Table 3–5 Add Element by PL/SQL Dialog Fields

Field	Description
Name	Enter a name for this element.
Display Name	The Display Name appears in the report design tools. Enter a name that is meaningful to your business users.
Data Type	Must select String.

4. Select the PL/SQL package from the Available box and click the shuttle button to move the function to the Group Filter box.

3.16 Using the Structure View to Edit Your Data Structure

The Structure view enables you to preview the structure of your data model. The Data Source column displays the date elements in a hierarchical tree that you can collapse and expand. Use this view to verify the accuracy of the data model structure. The Structure view is shown in [Figure 3–37](#).

Figure 3–37 Structure View

Diagram Structure Data Code					
Table View Output					
		XML View		Business View	
Data Source		XML Tag Name	Sorting	Value If Null	Data Type
Report Data					
Data Structure		DATA_DS			
Departments		G_1			G_1
DEPARTMENT_ID	999	DEPARTMENT_ID			DEPARTMENT_ID 999
DEPARTMENT_NAME	abc	DEPARTMENT_NAME			DEPARTMENT_NAME abc
MANAGER_ID	999	MANAGER_ID			MANAGER_ID 999
Employees		G_2			G_2
EMPLOYEE_ID	999	EMPLOYEE_ID			EMPLOYEE_ID 999
FIRST_NAME	abc	FIRST_NAME			FIRST_NAME abc
LAST_NAME	abc	LAST_NAME			LAST_NAME abc
EMAIL	abc	EMAIL			EMAIL abc
PHONE_NUMBER	abc	PHONE_NUMBER			PHONE_NUMBER abc
MANAGER_ID	999	MANAGER_ID			MANAGER_ID 999
DEPARTMENT_ID	999	DEPARTMENT_ID			DEPARTMENT_ID 999

3.16.1 Renaming Elements

Use the Structure page to define user-friendly names for elements in the data model. You can rename both the XML element tag name (XML View) and the name that displays in the report layout tools (Business View). Figure 3–38 shows renaming the DEPARTMENT_ID element to display as Department Number.

Figure 3–38 Editing the Display Name of an Element

Diagram Structure Data Code					
Table View Output					
		XML View		Business View	
Data Source		XML Tag Name	Sorting	Value If Null	Data Type
Report Data					
Data Structure		DATA_DS			
Departments		G_1			G_1
DEPARTMENT_ID	999	DEPARTMENT_ID			DEPARTMENT_ID 999
DEPARTMENT_NAME	abc	DEPARTMENT_NAME			DEPARTMENT_NAME abc
MANAGER_ID	999	MANAGER_ID			MANAGER_ID 999
Employees		G_2			G_2
EMPLOYEE_ID	999	EMPLOYEE_ID			EMPLOYEE_ID 999

3.16.2 Adding Value for Null Elements

The Structure also enables you to enter a value to use for an element if the data model returns a null value for the element.

Enter the value to use in the **Value if Null** field for the element.

3.17 Function Reference

Table 3–6 describes the usage of supported functions available from the **Add Element by Expression** dialog and the **Edit Group Filter** dialog.

Table 3–6 Supported Functions from the Add Element by Expression Dialog

Function	Description	Syntax	Example
IF	Logical IF operator Evaluates <code>boolean_expr</code> , and returns <code>true_return</code> if <code>boolean_expr</code> is true, and <code>false_return</code> if <code>boolean_expr</code> is false.	IF (<code>boolean_expr</code> , <code>true_return</code> , <code>false_return</code>)	IF (<code>G_1.DEPARTMENT_ID == 10</code> , 'PASSED', 'FAIL') returns 'PASSED' if <code>DEPARTMENT_ID = 10</code> , otherwise returns 'FAIL'
NOT	Logical NOT operator Evaluates <code>boolean_expr</code> , and returns true if <code>boolean_expr</code> is false.	STRING(NOT(<code>boolean_expr</code>))	STRING(NOT(<code>G_1.JOB_ID == 'MANAGER'</code>)) returns 'TRUE' if <code>JOB_ID = MANAGER</code> , otherwise returns 'FALSE'
AND	Logical AND operator Evaluates <code>boolean_expr1</code> and <code>boolean_expr2</code> , and returns true if both boolean expressions are true, otherwise returns false.	STRING(AND(<code>boolean_expr1</code> , <code>boolean_expr2</code> , ...))	STRING(AND (<code>G_1.JOB_ID == 'MANAGER'</code> , <code>G_1.DEPARTMENT_ID == 10</code>)) returns 'TRUE' if both <code>JOB_ID = MANAGER</code> and <code>DEPARTMENT_ID = 10</code> , otherwise returns 'FALSE'
&&	Logical AND operator Evaluates <code>boolean_expr1</code> and <code>boolean_expr2</code> , and returns true if both boolean expressions are true, otherwise returns false.	STRING(<code>boolean_expr1 && boolean_expr2</code>)	STRING(<code>G_1.JOB_ID == 'MANAGER' && G_1.DEPARTMENT_ID == 10</code>) returns 'TRUE' if both <code>JOB_ID = MANAGER</code> and <code>DEPARTMENT_ID = 10</code> , otherwise returns 'FALSE'
	Logical OR operator Evaluates <code>boolean_expr1</code> and <code>boolean_expr2</code> and returns true if both boolean expressions are true, otherwise returns false.	STRING(OR(<code>boolean_expr1</code> , <code>boolean_expr2</code>))	STRING(OR (<code>G_1.JOB_ID == 'MANAGER'</code> , <code>G_1.DEPARTMENT_ID == 10</code>)) returns 'TRUE' if either <code>JOB_ID = MANAGER</code> or <code>DEPARTMENT_ID = 10</code> , otherwise returns 'FALSE'
MAX	Returns the maximum value of the element in the set.	MAX(<code>expr1</code> , <code>expr2</code> , <code>expr3</code> , ...)	MAX(<code>G1_Salary</code> , 10000) returns max of salary or 10000
MIN	Returns the minimum value of the element in the set.	MIN(<code>expr1</code> , <code>expr2</code> , <code>expr3</code> , ...)	MIN(<code>G1_Salary</code> , 5000) returns min of salary or 5000

Table 3–6 (Cont.) Supported Functions from the Add Element by Expression Dialog

Function	Description	Syntax	Example
ROUND	Returns a number rounded to the integer places right of the decimal point.	ROUND(number[,integer]) If integer is omitted, number is rounded to 0 places. Integer can be negative to round off digits left of the decimal point. Integer must be an integer.	ROUND(2.777) returns 3 ROUND(2.777, 2) returns 2.78
FLOOR	Returns the smallest integer equal to or less than n.	FLOOR(n)	FLOOR(2.777) returns 2
CEILING	Returns the largest integer greater than or equal to n.	CEILING(n)	CEILING(2.777) returns 3
ABS	Returns the absolute value of n.	ABS(n)	ABS(-3) returns 3
AVG	Returns the average value of the expression.	AVG(expr1, expr2, expr3, ...)	AVG(G_1.SALARY,G_1.COMMISSION_PCT*G_1.SALARY) returns the average of SALARY and COMMISSION For example, if SALARY = 14000 and COMMISSION_PCT = .4, the expression evaluates to 9800.0
LENGTH	Returns the length of an array. The LENGTH function calculates the length using characters as defined by the input character set. If char is null, the function returns null. If char is an array, it returns the length of the array.	LENGTH(expr)	Example to return the length of an array: LENGTH(1, 2, 4, 4) returns 4 Example to return the length of a string: LENGTH('countries') returns 9
SUM	Returns the sum of the value of the expression.	SUM(expr1, expr2, ...)	SUM (G_1.SALARY, G_1.COMMISSION_PCT*G_1.SALARY) returns sum of salary and commission For example, if SALARY = 14000 and COMMISSION_PCT =.4, the expression evaluates to 19,600.0

Table 3–6 (Cont.) Supported Functions from the Add Element by Expression Dialog

Function	Description	Syntax	Example
NVL	Replaces null (returned as a blank) with a string in the results of a query.	NVL(expr1, expr2) If expr1 is null, then NVL returns expr2. If expr1 is not null, then NVL returns expr1.	NVL(G_1.COMMISSION_PCT, .3) returns .3 when G_1.COMMISSION_PCT is null
CONCAT	Returns char1 concatenated with char2.	CONCAT(char1, char2)	CONCAT(CONCAT(First_Name, ' '), Last_Name) where First_Name = Joe and Last_Name = Smith returns Joe Smith
STRING	Returns char as a string data type.	STRING(expr)	STRING(G1_SALARY) where salary = 4400 returns 4400 as a string
SUBSTRING	Extracts a substring from a string.	SUBSTRING(string, start_pos, end_pos) string is the source string. start_pos is the position to start the extraction. end_pos is the end position of the string to extract (optional).	SUBSTRING('this is a test', 5, 7) returns "is" (that is, characters 6 through 7) SUBSTRING('this is a test', 5) returns "is a test"
INSTR	Returns the position/location of the first character of a substring in a string.	INSTR(string1, string2) string1 is the string to search. string2 is the substring to search for in string1.	INSTR('this is a test', 'is a') returns 5
DATE	Converts a valid Java date string to a date data type in canonical format.	DATE(char, format_string) where (1) char is any valid Java date string (for example, 13-JAN-2013) (2) format_string is the Java date format of the input string (for example, dd-MMM-yyyy) The input and format strings must be a valid Java date format string.	DATE('01-Jan-2013', 'dd-MMM-yyyy') returns 2013-01-01T08:00:00.000+00:00

Table 3–6 (Cont.) Supported Functions from the Add Element by Expression Dialog

Function	Description	Syntax	Example
FORMAT_DATE	Converts a date argument in the Java date format to a formatted string.	FORMAT_DATE(date,format_string)	FORMAT_DATE(SYSDATE,'dd-MM-yyyy') where the value of SYSDATE = 2013-01-24T16:32:45.000-08:00 returns 24-Jan-2013
FORMAT_NUMBER	Converts a number or numeric string to a string in the specified number format.	FORMAT_NUMBER(number,format_string)	FORMAT_NUMBER(SOME_NUMBER, '\$9,999.00') where the value of SOME_NUMBER = 12345.678 returns \$12,345.68
DECODE	Replaces the value of an expression with another value based on the specified search and replace criteria.	DECODE(expr, search, result [, search, result]...[, default])	DECODE(PROD_FAMILY_CODE,100,'Colas',200,'Root Beer',300,'Cream Sodas',400,'Fruit Sodas','Other') returns (1) 'Colas' if PROD_FAMILY_CODE = 100 (2) 'Root Beer' if PROD_FAMILY_CODE = 200 (3) 'Cream Sodas' if PROD_FAMILY_CODE = 300 (4) 'Fruit Sodas' if PROD_FAMILY_CODE = 400 (5) 'Other' if PROD_FAMILY_CODE is any other value
REPLACE	Replaces a sequence of characters in a string with another set of characters.	REPLACE(expr,string1,string2) where string1 is the string to search for and string2 is the string to replace.	REPLACE(G_1.FIRST_NAME,'B','L') where G_1.FIRST_NAME = Barry returns Larry

Adding Parameters and Lists of Values

This chapter describes how to add parameters and lists of values to a BI Publisher data model.

This chapter includes the following sections:

- [Section 4.1, "About Parameters"](#)
- [Section 4.2, "Adding a New Parameter"](#)
- [Section 4.3, "About Lists of Values"](#)
- [Section 4.4, "Adding Lists of Values"](#)
- [Section 4.5, "Adding Flexfield Parameters"](#)

4.1 About Parameters

Adding parameters to a data model enables users to interact with data when they view reports.

BI Publisher supports the following parameter types:

- **Text** — the user enters a text string to pass as the parameter.
- **Menu** — the user makes selections from a list of values. A list of values can contain fixed data that you specify or the list can be created using a SQL query that is executed against any of the defined data sources. This option supports multiple selections, a "Select All" option, and partial page refresh for cascading parameters.

To create a menu type parameter, define the list of values first; then define the parameter and associate it to the list of values. See [Section 4.4, "Adding Lists of Values."](#)

- **Date** — the user selects a date as a parameter. Note that the data type must also be "Date" and the format must be Java date format.

Once you have defined the parameters in the data model, you can further configure how the parameters are displayed in the report as a report-level setting. For more information about the report-level settings, see the section "Configuring Parameter Settings for the Report" in *Oracle Fusion Middleware Report Designer's Guide for Oracle Business Intelligence Publisher*.

Support for parameters varies based on the data set type. SQL Query data sets support the full set of available parameter features. Other types of data sets may support all, none, or a subset of these features. [Table 4-1](#) summarizes what is supported for each data set type.

Table 4–1 Parameter Support by Data Set Type


Data Set Type	Parameter Support	Multiple Selection	Can Select All	Refresh Other Parameters on Change
SQL Query	Yes	Yes	Yes	Yes
MDX Query	No	No	No	No
Oracle BI Analysis	Inherited from Oracle BI Analysis	Yes (via Oracle BI Dashboards)	Yes (via Oracle BI Dashboards)	Yes (via Oracle BI Dashboards)
View Object	Yes, provided that the view object supports and is designed for it	No	No	Yes (view object parameters only)
Web Service	Yes	No	No	No
LDAP Query	Yes	No	No	No
XML File	No	No	No	No
Microsoft Excel File	Yes	No	No	No
CSV File	No	No	No	No
HTTP (XML Feed)	Yes	No	No	No
Oracle Endeca Query	No	No	No	No

4.2 Adding a New Parameter

To add a new parameter:

1. On the Data Model components pane, click **Parameters** and then click **Create new Parameter**, as shown in [Figure 4–1](#).

Figure 4–1 Create New Parameter



2. Enter a **Name** for the parameter. The name must match any references to this parameter in the data set.

Note: The parameter name you choose must not exceed the maximum length allowed for an identifier by your database. Refer to your database documentation for identifier length limitations.

3. Select the **Data Type** from the list. A **Date** data type only support a **Date Parameter Type**. The other data types support a **Parameter Type** of either **Text** or **Menu**:
 - String
 - Integer

Note: The Integer data type for parameters is a 64-bit sign integer. It has a value range of -9,223,372,036,854,775,808 to a maximum value of 9,223,372,036,854,775,807 (inclusive).

- Boolean
 - Date
 - Float
4. Enter a **Default Value** for the parameter. This is recommended to prevent long running queries. Default parameter values are also used to preview the report output when you design report layouts using BI Publisher Layout Editor.
 5. Select the **Parameter Type**. Supported types are:
 - **Text** — Allows the user to enter a text entry to pass as the parameter. See [Section 4.2.1, "Defining a Text Parameter."](#)
 - **Menu** — Presents a list of values to the user. See [Section 4.2.2, "Defining a Menu Parameter."](#)
 - **Date** — Passes a date parameter. The **Data Type** must also be Date. See [Section 4.2.3, "Defining a Date Parameter."](#)

Note: BI Publisher supports parameters that are of type text entry or menu (list of values) but not both. That is, you cannot define a "combination" parameter that enables a user to either enter a text value or choose from a menu list of values.


6. **Row Placement** - this setting configures the number of rows for displaying the parameters and in which row to place each parameter. For example, if your report has six parameters, you can assign each parameter to a separate row, 1 - 6, with one being the top row; or, you can assign two parameters each to rows 1, 2, 3. By default, all parameters are assigned to row 1.

Row placement can also be configured at the report level. The report definition supports additional display options for parameters. For more information, see "Configuring Parameter Settings for the Report" in *Oracle Fusion Middleware Report Designer's Guide for Oracle Business Intelligence Publisher*.

4.2.1 Defining a Text Parameter

The **Text** type parameter provides a text box to prompt the user to enter a text entry to pass as the parameter to the data source. [Figure 4–2](#) shows a text parameter definition.

Figure 4–2 Text Parameter Definition




To define a Text type parameter:

1. Select Text from the Parameter Type list. The lower pane displays the appropriate fields for the selection.
2. Enter the **Display Label**. The display label is the label that displays to users when they view the report. For example: Department.
3. Enter the **Text Field Size** as an integer. This field determines the number of characters that the user can enter into the text box. For example: 25.
4. Enable the following **Options** if required:
 - **Text field contains comma-separated values** — Select this option to enable the user to enter multiple comma-delimited values for this parameter. The parameter in your data source must be defined to support multiple values.
 - **Refresh other parameters on change** — Performs a partial page refresh to refresh any other parameters whose values are dependent on the value of this one.

[Figure 4–3](#) shows how the Department parameter displays to the report consumer.

Figure 4–3 Text Type Parameter as Displayed in the Report




4.2.2 Defining a Menu Parameter

A **Menu** type parameter presents a list of values to the user. You must define the list of values first. See [Section 4.4, "Adding Lists of Values."](#) The Menu type parameter supports the data types of String and Integer only.

The Menu parameter definition includes the options:

[Figure 4–4](#) shows the menu parameter definition.


Figure 4–4 Menu Type Parameter Definition



To define a Menu type parameter:

1. Select **Menu** from the **Parameter Type** list. The lower pane displays the appropriate fields. Choose the **Data Type** (must be **String** or **Integer**).
2. Enter the **Display Label**. The display label is the label that displays to users when they view the report. For example: Department.
3. Enter the **Number of Values to Display in List**. If the number of values in the list exceeds the entry in this field, the user must click **Search** to find a value not displayed, as shown in [Figure 4–5](#). This field defaults to 100.

Figure 4–5 Search Feature Enabled When Number of Values Exceeds Setting



4. Select the **List of Values** that you defined for this parameter.
5. Enable the following **Options** if required:
 - **Multiple Selection** — Allows the user to select multiple entries from the list. Your data source must be able to support multiple values for the parameter. The display of a menu parameter that supports multiple selection differs. See [Figure 4–6](#) and [Figure 4–7](#).
 - **Can select all** — Inserts an "All" option in the list. When the user selects "All" from the list of values, you have the option of passing a null value for the parameter or all list values. Choose **NULL Value Passed** or **All Values Passed**.

Note: Using * passes a null, so you must handle the null in your data source. A method to handle the null would be the standard Oracle NVL command, for example:

where customer_id = nvl(:cstid, customer_id)

where cstid is a value passed from the LOV and when the user selects All it passes a null value.

- **Refresh other parameters on change** — Performs a partial page refresh to refresh any other parameters whose values are dependent on the value of this one.

[Figure 4–6](#) shows how the Department menu type parameter displays to the report consumer when multiple selection is not enabled.

Figure 4–6 Department Menu Type Parameter with Multiple Selection Disabled





Figure 4–7 shows how the Department menu type parameter displays to the report consumer when multiple selection is enabled.

Figure 4–7 Department Menu Type Parameter with Multiple Selection Enabled




4.2.2.1 Customizing the Display of Menu Parameters

The display of menu parameters in the report can be further customized in the report definition. Menu type parameters support the additional display option as a static list of checkboxes or radio buttons. For more information, see "Configuring Parameter Settings for the Report" in the *Oracle Fusion Middleware Report Designer's Guide for Oracle Business Intelligence Publisher*.

4.2.3 Defining a Date Parameter

The **Date** type parameter provides a date picker to prompt the user to enter a date to pass as the parameter to the data source. Figure 4–8 shows the date parameter definition.

Figure 4–8 Date Parameter Definition




To define a Date type parameter:

1. Select Date from the Parameter Type list. The lower pane displays the appropriate fields for your selection.
2. Enter the **Display Label**. The display label is the label that displays to users when they view the report. For example: Hire Date.

3. Enter the **Text Field Size** as an integer. This field determines the number of characters that the user can enter into the text box for the date entry. For example: 10.
4. Enter the **Date Format String**. The format must be a Java date format (for example, MM-dd-yyyy).
5. Optionally, enter a **Date From** and **Date To**. The dates entered here define the date range that are presented to the user by the date picker. For example if you enter the **Date From** as 01-01-1990, the date picker does not allow the user to select a date before 01-01-1990. Leave the **Date To** blank to enable all future dates.

Figure 4–9 shows how the Hire Date parameter displays to the report consumer.

Figure 4–9 Hire Date Parameter



4.3 About Lists of Values

A list of values is a defined set of values that a report consumer can select from to pass a parameter value to your data source. If you define a menu type parameter, the list of values that you define here provides the menu of choices. You must define the list of values before you define the menu parameter.

Populate the list using one of the following methods:


- **Fixed Data** — Manually enter the list of values.
- **SQL Query** — Retrieve the values from a database using a SQL query.
- **Flexfield**— Retrieve the values from a key flexfield defined in Oracle E-Business Suite. This option is only available when BI Publisher is using the Oracle E-Business Suite security model. For more information, see [Section 4.5, "Adding Flexfield Parameters."](#)

4.4 Adding Lists of Values

To add a List of Values:

1. On the Data Model components pane, click **List of Values** and then click **Create new List of Values**, as shown in [Figure 4–10](#).

Figure 4–10 Create New List of Values



2. Enter a **Name** for the list and select a **Type**: SQL Query or Fixed Data.

4.4.1 Creating a List from a SQL Query


The data engine expects a (display) name-value pair from the list of values query. In the list of values select statement, the column listed first is used as the display name (what is shown to the user) and the second is used for the value that is passed to the parameter in the data set query by the data engine.

If the query returns only one column, then the same column value is used both as the list of values display name shown to the user and as the value that is passed to the parameter.

To create a list from a SQL query:


1. Select a **Data Source** from the list.
2. In the lower pane, select **Cache Result** (recommended) if you want the results of the query cached for the report session.
3. Enter the SQL query or use the Query Builder. See [Section 2.3.3, "Using the SQL Query Builder"](#) for information on the Query Builder utility. [Figure 4–11](#) shows a SQL query type list of values.

Figure 4–11 SQL Query Type List of Values



The SQL query shown in [Figure 4-11](#) selects only the DEPARTMENT_NAME column from the DEPARTMENTS table. In this case the list of values both displays the results of the query in the list and passes the same value to the parameter in the data set. [Figure 4-12](#) shows the list of values display entries and the values passed to the data set. Note that the menu items and the values shown for P_DEPT are the DEPARTMENT_NAME values.

Figure 4-12 Sample Data Showing the Same LOV Display Names and Values




If instead you wanted to pass the DEPARTMENT_ID to the parameter in the data set yet still display the DEPARTMENT_NAME in the list, construct your SQL query as follows:

```
Select "DEPARTMENTS"."DEPARTMENT_NAME" as "DEPARTMENT_NAME",
       "DEPARTMENTS"."DEPARTMENT_ID" as "DEPARTMENT_ID"
from "DEMO"."DEPARTMENTS" "DEPARTMENTS"
```

[Figure 4-13](#) shows the list of values display entries and the values passed to the data set. Note that the menu lists the DEPARTMENT_NAME while the values shown for P_DEPT are the DEPARTMENT_ID values.

Figure 4–13 LOV Display Names and Values




4.4.2 Creating a List from a Fixed Data Set

To create a list from a fixed data set:

1. In the lower pane, click the **Create new List of Values** icon to add a Label and Value pair. The label is displayed to the user in the list. The value is passed to the data engine.
2. Repeat for each label-value pair required.

Figure 4–14 shows fixed data type list of values.

Figure 4–14 Fixed Data Type List of Values




4.5 Adding Flexfield Parameters

Oracle E-Business Suite customers who have configured BI Publisher to use E-Business Suite security can create reports that leverage key flexfields as parameters. When you define a data model to pass a key flexfield as a parameter, BI Publisher presents a dialog to the report consumer to make selections for the flexfield segments to pass as parameters to the report, similar to the way flexfields are presented when running reports through the concurrent manager in the E-Business Suite.


The flexfield list of values displays in the report viewer as shown in [Figure 4–15](#).

Figure 4–15 Flexfield List of Values Display



The flexfield list of values displays as a dialog from which you select the segment values as shown in [Figure 4–16](#).

Figure 4–16 Flexfield Segment Selection Dialog



4.5.1 Prerequisites for Using Flexfields

When defining a list of values, E-Business Suite customers see a list Type called "Flexfield". To enable the flexfield type list of values, BI Publisher must be configured to use E-Business Suite Security. The flexfield must already be defined in the E-Business Suite.

For information about flexfields in the E-Business Suite, see *Oracle E-Business Suite Flexfields Guide*. For information about setting up E-Business Suite security for BI Publisher, see "Integrating with Oracle E-Business Suite" in *Oracle Fusion Middleware Administrator's Guide for Oracle Business Intelligence Publisher*.

4.5.2 Adding a Flexfield Parameter and List of Values

To add a flexfield parameter complete the following tasks. Each task is described in detail in the subsequent sections:

1. Add the flexfield list of values (LOV). The flexfield type list of values retrieves the flexfield metadata definition to present the appropriate values for each segment in the flexfield list of values selection dialog.
2. Add a parameter and associate it with the flexfield LOV by selecting your flexfield list of values as the source menu for the parameter.

3. Add the Flexfield component to the data model. Use the flexfield parameter to pass values to the Flexfield defined in the Data Model.
4. Reference the Flexfield in your SQL query using the `&flexfield_name` syntax. At runtime the `&flexfield_name` reference is replaced with the lexical code constructed based on the values in the Flexfield component definition.


4.5.2.1 Adding the Flexfield List of Values

To add a list of values retrieved from a flexfield definition:

1. On the Data Model components pane, click **List of Values** and then click **Create new List of Values**.
2. Enter a **Name** for the list and choose Flexfields as the **Type**. When you choose Flexfields as the Type, the **Data Source** option is no longer editable. All flexfields type lists of values use the Oracle E-Business Suite as the data source.
3. In the lower pane, enter the following:
 - **Application Short Name** - the E-Business Suite application short name, for example: SQLGL.
 - **ID Flex Code** - the flexfield code defined for this flexfield in the Register Key Flexfield form, for example: GL#.
 - **ID Flex Number** - the name of the source column or parameter that contains the flexfield structure information, for example: 101 or :STRUCT_NUM. If you use a parameter, ensure that you define the parameter in the data model.

Figure 4–17 shows a sample flexfield type LOV.

Figure 4–17 Defining the Flexfield List of Values



4.5.2.2 Adding the Menu Parameter for the Flexfield List of Values


Define the parameter to display the flexfield list of values and capture the values selected by the user. The Flexfield type parameter definition includes an additional field called **Range** to support range flexfields. A range flexfield supports low and high values for each key segment rather than just single values.

To define the parameter for the flexfield list of value:

1. On the Data Model components pane, click **Parameters** and then click **Create new Parameter**.
2. Select **Menu** from the **Parameter Type** list. Choose the **Data Type** (must be **String** or **Integer**).
3. Enter a **Default Value** for the flexfield parameter. The default value can also be customized in the report definition.
4. Enter the **Row Placement**. The row placement determines where this parameter appears in the report viewer. Row placement can also be customized in the report definition.
5. Enter the **Display Label**. The display label is the label that displays to users when they view the report. For example: Account From. The display label can also be customized in the report definition.
6. Select the **List of Values** that you defined for this parameter. When you select a list of values that is the Flexfield type, an additional field labeled **Range** displays. To pass a range of flexfield segment values see [Section 4.5.2.5, "Passing a Range of Values."](#)
7. The following options are disabled for flexfield parameters: **Number of Values to Display in List**, **Multiple Selection**, **Can select all**, and **Refresh other parameters on change**.

Figure 4–18 shows a parameter definition for the flexfield list of values.

Figure 4–18 Defining the Parameter for the Flexfield List of Values



4.5.2.3 Using the Flexfield Parameter to Pass Values to a Flexfield Defined in the Data Model

Now you can pass the parameter values to a flexfield component in the data model. [Chapter 6, "Adding Flexfields"](#) covers adding a flexfield component in detail. The simplified procedure is provided here to complete the example.

To define the Flexfield in the data model:

1. On the Data Model components pane, click **Flexfields** and then click **Create new Flexfield**.

2. Enter the following:
 - **Name** — Enter a name for the flexfield component.
 - **Type** — Select the flexfield type from the list. The type you select here determines the additional fields required. See [Section 6.2.1, "Entering Flexfield Details."](#)
 - **Application Short Name** — Enter the short name of the Oracle Application that owns this flexfield (for example, GL).
 - **ID Flex Code** — Enter the flexfield code defined for this flexfield in the Register Key Flexfield form (for example, GL#).
 - **ID Flex Number** — Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, :PARAM_STRUCT_NUM.
3. In the lower region of the page, enter the details for the type of flexfield you selected. For the field that is to take the parameter value, enter the parameter name prefixed with a colon, for example, :P_Acct_List.

In [Figure 4–19](#) the Flexfield component is defined as a "Where" **Type**. The parameter :P_Acct_List is entered in the Operand1 field. At runtime, values selected by the user for the parameter P_Acct_List will be used to create the where clause.

Figure 4–19 Example Flexfield Component Using Flexfield Parameters

The screenshot shows the 'Account Analysis' application window. On the left is a 'Data Model' tree with categories like Data Sets, Event Triggers, Flexfields, List of Values, Parameters, and Bursting. The 'Flexfields' category is expanded, showing 'Acct_Flex' selected. The main area displays the configuration for 'Acct_Flex' with the following details:


Name	Type	Application Short Name	ID Flex Code	ID Flex Number	Reorder
Acct_Flex	Where	SQLGL	GL#	:P_STRUCT_NUM	

Below the table, the configuration for 'Acct_Flex: Type: Where' is shown:

- Code Combination Table Alias:
- Segments: ALL
- Operator: =
- Operand1: :P_Acct_List
- Operand2:
- Metadata Type: Above Prompt of Segments

4.5.2.4 Referencing the Flexfield in the SQL Query

Finally, create the SQL query against the E-Business Suite database. Use the lexical syntax in the query as described in [Section 6.2, "Adding Key Flexfields."](#) In [Figure 4–20](#) &Acct_Flex is the Flexfield lexical called in the where condition of the SQL query.


Figure 4–20 Flexfield Lexical in SQL Query

4.5.2.5 Passing a Range of Values

To define the parameters for the flexfield lists of values when you want to pass a range of values you create two menu parameters that both reference the same flexfield LOV. At runtime users choose a high value from the list of values and a low value from the same list of values. These two values are then passed as operands to the flexfield component of the data model.

1. Create one flexfield LOV as described in [Section 4.5.2.1, "Adding the Flexfield List of Values."](#)
2. Create the high range parameter following the steps in [Section 4.5.2.2, "Adding the Menu Parameter for the Flexfield List of Values."](#) For the Range field, select High to designate this parameter as the high value.
3. Create the low range parameter following the steps in [Section 4.5.2.2, "Adding the Menu Parameter for the Flexfield List of Values."](#) For the Range field, select Low to designate this parameter as the low value. Both parameters reference the flexfield list of values that you created in Step 1. [Figure 4–21](#) shows creating the parameters to define the range.

Figure 4–21 Defining the Range Parameters




4. Create the Flexfield in the data model, as described in Section 4.5.2.3, "Using the Flexfield Parameter to Pass Values to a Flexfield Defined in the Data Model."

In the lower region of the page, enter the details for the type of flexfield you selected. Enter the parameter prefixed with a colon for example, :P_Acct_List.

In Figure 4–19 the Flexfield component is defined as a "Where" **Type**. The parameters :P_FLEX_LOW and :P_FLEX_HIGH are entered in the Operand1 and Operand2 fields. At runtime, values selected by the user for the parameters P_FLEX_LOW and P_FLEX_HIGH will be used to create the where clause.

Figure 4–22 Example Flexfield Component Using Flexfield Parameters




When the report associated with this data model is displayed in the report viewer, the report consumer sees the two flexfield parameters as shown in Figure 4–23.

Figure 4–23 Flexfield Range Parameters Displayed in the Report Viewer



When the report consumer clicks either the high or low flexfield indicator (...), a dialog launches enabling input of both the high and low values as shown in Figure 4–24.

Figure 4–24 Flexfield Range Parameter Dialog



The display characteristics in the report viewer of the range flexfield parameter resemble closely the presentation of range flexfields in the E-Business Suite.

Adding Event Triggers

BI Publisher data models support before data and after data event triggers and schedule triggers. This chapter describes how to define triggers in your data model.

This chapter includes the following sections:

- [Section 5.1, "About Triggers"](#)
- [Section 5.2, "Adding Before Data and After Data Triggers"](#)
- [Section 5.3, "Creating Schedule Triggers"](#)

5.1 About Triggers

The BI Publisher data model supports the following types of triggers:

- Before Data — fires before the data set is executed.
- After Data — fires after the data engine executes all data sets and generates the XML.
- Schedule Trigger - fires when a report job is scheduled to run.

An event trigger checks for an event and when the event occurs, it runs the code associated with the trigger. The BI Publisher data model supports before data and after data triggers that execute a PL/SQL function stored in a PL/SQL package in your Oracle Database. The return data type for a PL/SQL function inside the package must be a Boolean type and the function must explicitly return TRUE or FALSE.

A schedule trigger is associated with a schedule job. It is a SQL query that executes at the time a report job is scheduled to run. If the SQL returns any data, the report job runs. If the SQL query returns no data, the job instance is skipped.

5.2 Adding Before Data and After Data Triggers

To add before data or after data event triggers:


1. On the data model **Properties** pane, enter the **Oracle DB Default Package** that contains the PL/SQL function signature to execute when the trigger fires. See [Section 1.7, "Setting Data Model Properties."](#)
2. From the task pane, click **Event Triggers**.
3. From the **Event Triggers** pane, click **Create New Event Trigger**.
4. Enter the following for the trigger:
 - **Name**

- **Type** — Select Before Data or After Data.
- **Language** — Select PL/SQL.

The lower pane displays the available functions in the Oracle DB Default Package that you entered in the data model Properties in Step 1.

Figure 5–1 shows an event trigger.

Figure 5–1 Event Trigger



5. Select the package from the **Available Functions** box and click the arrow to move a function to the **Event Trigger** box. The name appears as PL/SQL <package name>.<function name>.

Important: If you define a default package then you must define all parameters as a global PL/SQL variable in the PL/SQL package. You can then explicitly pass parameters to your PL/SQL function trigger or all parameters are available as a global PL/SQL variable.

5.2.1 Order of Execution

If you define multiple triggers of the same type, they fire in the order that they appear in the table (from top to bottom).

To change the order of execution:

1. Use the **Reorder** arrows to place the triggers in the correct order.

5.3 Creating Schedule Triggers

A schedule trigger fires when a report job is scheduled to run. Schedule triggers are of type SQL Query. When a report job is scheduled to run, the schedule trigger executes the SQL statement defined for the trigger. If data is returned, then the report job is

submitted. If data is not returned from the trigger SQL query, the report job is skipped.

The schedule trigger that you associate with a report job can reside in any data model in the catalog. You do not need to create the schedule trigger in the data model of the report for which you which to execute it. You can therefore reuse schedule triggers across multiple report jobs.


To add a Schedule Trigger:

1. In the data model editor task pane, click **Event Triggers**.
2. From the **Event Triggers** pane, click the **Create New** icon.
3. Enter the following for the trigger:
 - **Name** - enter a name for the trigger.
 - **Type** — select Schedule.
 - **Language** — defaults to SQL Query.
4. In the lower pane, enter the following:
 - **Options** - select this box to cache the results of the trigger query.
 - **Data Source** - select the data source for the trigger query.
 - **SQL Query** - enter the query in the text area, or click **Query Builder** to use the utility to construct the SQL query. For information, see [Section 2.3.3, "Using the SQL Query Builder."](#)

You can include parameters in the trigger query. Define the parameter in the same data model as the trigger. Enter parameter values when you schedule the report job.

If the SQL query returns any results, the scheduled report job executes. [Figure 5–2](#) shows a schedule trigger to test for inventory levels based on a parameter value that can be entered at runtime.

Figure 5–2 Schedule Trigger



For information on implementing the schedule trigger in the report job, see "Defining the Schedule for a Job" in the *Oracle Fusion Middleware User's Guide for Oracle Business Intelligence Publisher*.

Adding Flexfields

This chapter describes support for flexfields in the BI Publisher data model.

This chapter includes the following sections:


- [Section 6.1, "About Flexfields"](#)
- [Section 6.2, "Adding Key Flexfields"](#)
- [Section 6.3, "Adding Descriptive Flexfields"](#)

6.1 About Flexfields

A flexfield is a flexible data field that your organization can customize to your business needs without programming. Oracle applications (Oracle E-Business Suite and Oracle Fusion Applications) use two types of flexfields: key flexfields and descriptive flexfields. A key flexfield is a field you can customize to enter multi-segment values such as part numbers, account numbers, and so on. A descriptive flexfield is a field you customize to enter additional information for which your Oracle applications product has not already provided a field.

If you are reporting on data from Oracle applications, use the Flexfield component of the data model to retrieve flexfield data. When BI Publisher is integrated with Oracle Fusion Applications, both key flexfields and descriptive flexfields are supported. When BI Publisher is integrated with Oracle E-Business Suite only key flexfields are supported.

Figure 6–1 *The Flexfield Component of the Data Model*



Before including flexfields in your reports you should understand flexfields in your applications. See your Oracle E-Business Suite or Oracle Fusion Applications documentation.

6.1.1 Using Flexfields in Your Data Model

To use flexfields in your SQL-based data model:

- Add the **Flexfield** component to the data model as described in this chapter.
- Define the SQL SELECT statement against the applications data tables.
- Within the SELECT statement, define each flexfield as a lexical. Use the `&LEXICAL_TAG` to embed flexfield related lexicals into the SELECT statement.

6.2 Adding Key Flexfields

You can use key flexfield references to replace the clauses appearing after SELECT, FROM, WHERE, ORDER BY, or HAVING. Use a flexfield reference when you want the parameter to replace multiple values at runtime. The data model editor supports the following flexfield types:

- **Where** — This type of lexical is used in the WHERE section of the statement. It is used to modify the WHERE clause such that the SELECT statement can filter based on key flexfield segment data.
- **Order by** — This type of lexical is used in the ORDER BY section of the statement. It returns a list of column expressions so that the resulting output can be sorted by the flex segment values.
- **Select** — This type of lexical is used in the SELECT section of the statement. It is used to retrieve and process key flexfield (kff) code combination related data based on the lexical definition.
- **Filter** — This type of lexical is used in the WHERE section of the statement. It is used to modify the WHERE clause such that the SELECT statement can filter based on Filter ID passed from Oracle Enterprise Scheduling Service.
- **Segment Metadata** — Use this type of lexical to retrieve flexfield-related metadata. Using this lexical, you are not required to write PL/SQL code to retrieve this metadata. Instead, define a dummy SELECT statement, then use this lexical to get the metadata. This lexical should return a constant string.

After you set up the flexfield components of your data model, create a flexfield lexical reference in the SQL query using the following syntax:

```
&LEXICAL_TAG ALIAS_NAME
```

for example:

```
&FLEX_GL_BALANCING alias_gl_balancing
```


After entering the SQL query, when you click OK

To add a key flexfield:

1. Enter the following:
 - **Lexical Name** — Enter a name for the flexfield component.
 - **Flexfield Type** — Select Key Flexfield.
 - **Lexical Type** — Select the type from the list. Your selection here determines the additional fields required. See [Section 6.2.1, "Entering Flexfield Details."](#)
 - **Application Short Name** — Enter the short name of the Oracle Application that owns this flexfield (for example, GL).

- **Flexfield Code** — Enter the flexfield code defined for this flexfield. In Oracle E-Business Suite this code is defined in the Register Key Flexfield form (for example, GL#).
- **ID Flex Number** — Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, :PARAM_STRUCT_NUM.

Figure 6–2 Key Flexfield



6.2.1 Entering Flexfield Details

The Details region displays appropriate fields depending on the Lexical Type you chose.

Fields for Key Flexfield Type: Segment Metadata




Table 6–1 Detail Fields for Segment Metadata

Field	Description
Structure Instance Number	Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, :PARAM_STRUCT_NUM.
Segments	(Optional) Identifies for which segments this data is requested. Default value is "ALL". See <i>Oracle E-Business Suite Developer's Guide</i> for syntax.
Show Parent Segments	Select this box to automatically display the parent segments of dependent segments even if it is specified as not displayed in the segments attribute.
Metadata Type	Select the type of metadata to return: Above Prompt of Segments — Above prompt of segment(s). Left Prompt of Segments — Left prompt of segment(s)

Fields for Key Flexfield Type: Select

KFF_SELECT: Type: Select

Enable Multiple Structure Instances

Code Combination Table Alias

Structure Instance Number

Segments

Show Parent Segments


Output Type

Table 6–2 shows the detail fields for the Select flexfield type.

Table 6–2 Detail Fields for Select

Field	Description
Enable Multiple Structure Instances	Indicates whether this lexical supports multiple structures. Checking this box indicates all structures are potentially used for data reporting. The data engine uses <code_combination_table_alias>.<set_defining_column_name> to retrieve the structure number.
Code Combination Table Alias	Specify the table alias to prefix to the column names. Use TABLEALIAS if your SELECT joins to other flexfield tables or uses a self-join.
Structure Instance Number	Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, :PARAM_STRUCT_NUM.
Segments	(Optional) Identifies for which segments this data is requested. Default value is "ALL". See <i>Oracle E-Business Suite Developer's Guide</i> for syntax.
Show Parent Segments	Select this box to automatically display the parent segments of dependent segments even if it is specified as not displayed in the segments attribute.
Output Type	Select from the following: <ul style="list-style-type: none"> ■ Value — Segment value as it is displayed to user. ■ Padded Value — Padded segment value as it is displayed to user. Number type values are padded from the left. String type values are padded on the right. ■ Description — Segment value's description up to the description size defined in the segment definition. ■ Full Description — Segment value's description (full size). ■ Security — Returns Y if the current combination is secured against the current user, N otherwise.

Fields for Key Flexfield Type: Where



KFF_Where Type: Where

Code Combination Table Alias

Structure Instance Number

Segments

Operator

Operand1

Operand2


Metadata Type

Table 6–3 shows the detail fields for the Where key flexfield type.

Table 6–3 Detail Fields for Where

Field	Description
Code Combination Table Alias	Specify the table alias to prefix to the column names. You use TABLEALIAS if your SELECT joins to other flexfield tables or uses a self-join.
Structure Instance Number	Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, :PARAM_STRUCT_NUM.
Segments	(Optional) Identifies for which segments this data is requested. Default value is "ALL". See <i>Oracle E-Business Suite Developer's Guide</i> for syntax.
Operator	Select the appropriate operator.
Operand1	Enter the value to use on the right side of the conditional operator.
Operand2	(Optional) High value for the BETWEEN operator.

Fields for Key Flexfield Type: Order By



KFF_ORDER_BY: Type: Order By

Enable Multiple Structure Instances

Code Combination Table Alias

Structure Instance Number

Segments

Show Parent Segments

Table 6–4 shows the detail fields for the Order by flexfield type.

Table 6–4 Detail Fields for Order By

Field	Description
Enable Multiple Structure Instances	Indicates whether this lexical supports multiple structures. Selecting this box indicates all structures are potentially used for data reporting. The data engine uses <code_combination_table_alias>.<set_defining_column_name> to retrieve the structure number.

Table 6–4 (Cont.) Detail Fields for Order By

Field	Description
Structure Instance Number	Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, :PARAM_STRUCT_NUM.
Code Combination Table Alias	Specify the table alias to prefix to the column names. You use TABLEALIAS if your SELECT joins to other flexfield tables or uses a self-join.
Segments	(Optional) Identifies for which segments this data is requested. Default value is "ALL". See <i>Oracle E-Business Suite Developer's Guide</i> for syntax.
Show Parent Segments	Select this box to automatically display the parent segments of dependent segments even if it is specified as not displayed in the segments attribute.

Fields for Key Flexfield Type: Filter

KFF_FILTER: Type: Filter

Code Combination Table Alias

Structure Instance Number

Table 6–5 shows the detail fields for the Filter flexfield type.

Table 6–5 Detail Fields for Filter

Field	Description
Code Combination Table Alias	Specify the table alias to prefix to the column names. You use TABLEALIAS if your SELECT joins to other flexfield tables or uses a self-join.
Structure Instance Number	Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, :PARAM_STRUCT_NUM.

6.3 Adding Descriptive Flexfields

Reporting on descriptive flexfields is supported only for Oracle Fusion Applications.

To add a descriptive flexfield:

1. Enter the basic flexfield information:
 - **Name** — Enter a name for the flexfield component.
 - **Flexfield Type** — Select **Descriptive Flexfield**.
 - **Lexical Type** - only Select is supported.
 - **Application Short Name** — Enter the short name of the Oracle Application that owns this flexfield (for example, FND).
 - **Flexfield Code** — Enter the flexfield code defined for this flexfield in the Register Descriptive Flexfield form (for example, FND_DFF1).

Figure 6–3 Descriptive Flexfield Entry

*Lexical Name	Flexfield Type	Lexical Type	Application Short Name	Flexfield Code	Reorder
DFF_SELECT	Descriptive Flexfield	Select	FND	FLEX_DFF1	

2. Enter the flexfield details:
 - **Table Alias** - Specify the table alias to prefix to the column names. Use TABLEALIAS if your SELECT joins to other flexfield tables or uses a self-join.
 - **Flexfield Usage Code** - (Optional) Identifies for which segments this data is requested. Default value is "ALL".
3. If your descriptive flexfield definition includes parameters, you can enter the parameters in the Parameters region.

To enter parameters, click + to add each parameter. Enter a **Label** and a **Value** for each parameter. The Label must match exactly the label in the descriptive flexfield definition.

Figure 6–4 Descriptive Flexfield Details

DFF_SELECT: Type: Select

Table Alias: FND_DF_DFF1_T1

Flexfield Usage Code: FLEX_DFF1

Parameters

*Label	*Value
ALL_SEGMEI	3


6.3.1 Including Descriptive Flexfield Reference in SQL Queries

When you create the SQL data set, include the descriptive flexfield using the ampersand symbol, for example:

```
&DFF_SELECT
```


an example is shown in [Figure 6–5](#).

Figure 6–5 Referencing the Descriptive Flexfield in a SQL Query



When you click OK, the diagram of your data set shows the columns that are returned from your descriptive flexfield as shown in [Figure 6–6](#).

Figure 6–6 Columns Returned by &DFF_SELECT



The columns that are returned from the key flexfield have the following limitations:

- Element properties are disabled
- In the data model Structure tab, you cannot edit the following fields: XML Tag Name, Value if Null, Display Name, Data Type
- Subgrouping of descriptive flexfield elements is not supported
- Element linking is not supported

Adding Bursting Definitions

This chapter describes BI Publisher's support for bursting reports and how to define a bursting definition in the data model to split and deliver your report to multiple recipients.

This chapter includes the following sections:

- [Section 7.1, "About Bursting"](#)
- [Section 7.2, "What is the Bursting Definition?"](#)
- [Section 7.3, "Adding a Bursting Definition to Your Data Model"](#)
- [Section 7.4, "Defining the Query for the Delivery XML"](#)
- [Section 7.5, "Passing a Parameter to the Bursting Query"](#)
- [Section 7.6, "Defining the Split By and Deliver By Elements for a CLOB/XML Data Set"](#)
- [Section 7.7, "Configuring a Report to Use a Bursting Definition"](#)
- [Section 7.8, "Sample Bursting Query"](#)
- [Section 7.9, "Creating a Table to Use as a Delivery Data Source"](#)

7.1 About Bursting

Bursting is a process of splitting data into blocks, generating documents for each block, and delivering the documents to one or more destinations. The data for the report is generated by executing a query once and then splitting the data based on a "Key" value. For each block of the data, a separate document is generated and delivered.

Using BI Publisher's bursting feature you can split a single report based on an element in the data model and deliver the report based on a second element in the data model. Driven by the delivery element, you can apply a different template, output format, delivery method, and locale to each split segment of the report. Example implementations include:

- Invoice generation and delivery based on customer-specific layouts and delivery preference
- Financial reporting to generate a master report of all cost centers, splitting out individual cost center reports to the appropriate manager
- Generation of pay slips to all employees based on one extract and delivered through e-mail

7.2 What is the Bursting Definition?

A bursting definition is a component of the data model. After you have defined the data sets for the data model, you can set up one or more bursting definitions. When you set up a bursting definition, you define the following:

- The **Split By** element is an element from the data that governs how the data is split. For example, to split a batch of invoices by each invoice, you may use an element called `CUSTOMER_ID`. The data set must be sorted or grouped by this element.
- The **Deliver By** element is the element from the data that governs how formatting and delivery options are applied. In the invoice example, it is likely that each invoice has delivery criteria determined by customer; therefore, the Deliver By element would also be `CUSTOMER_ID`.
- The **Delivery Query** is a SQL query that you define for BI Publisher to construct the delivery XML data file. The query must return the formatting and delivery details.

7.3 Adding a Bursting Definition to Your Data Model

Prerequisites:

- You have defined the data set for this data model
- The data set is sorted or grouped by the element by which you want to split the data in your bursting definition
- The delivery and formatting information is available to BI Publisher. The information can be provided at runtime to BI Publisher in one of the following ways:
 - The information is stored in a database table available to BI Publisher (for a dynamic delivery definition)
 - The information is hard coded in the delivery SQL (for a static delivery definition)
- The report definition for this data model has been created and includes the layouts to be applied to the report data.

To add a bursting definition:

1. On the component pane of the data model editor, click **Bursting**.
2. On the Bursting definition table, click the **Create new Bursting** button.
3. Enter the following for this bursting definition:


Name — For example, "Burst to File"

Type — SQL Query is currently the only supported type

Data Source — Select the data source that contains the delivery information

Figure 7-1 shows a Bursting definition.

Figure 7-1 Bursting Definition



4. In the lower region, enter the following for this bursting definition:


Split By — Select the element from the data set by which to split the data.

Deliver By — Select the element from the data set by which to format and deliver the data.

Note: If the Split By and Deliver By elements reside in an XML document stored as a CLOB in your database, you must enter the full XPATH in the Split By and Delivery By fields. For more information, see [Section 7.6, "Defining the Split By and Deliver By Elements for a CLOB/XML Data Set."](#)

SQL Query — Enter the query to construct the delivery XML. For information on how to construct the bursting query, see [Section 7.4, "Defining the Query for the Delivery XML."](#) Figure 7-2 shows a sample bursting query.

Figure 7-2 Sample Bursting Query



7.4 Defining the Query for the Delivery XML

The bursting query is a SQL query that you define to provide BI Publisher with the required information to format and deliver the report. BI Publisher uses the results from the bursting query to create the delivery XML.

The BI Publisher bursting engine uses the delivery XML as a mapping table for each Deliver By element. The structure of the delivery XML required by BI Publisher is as follows:

```
<ROWSET>
<ROW>
<KEY></KEY>
<TEMPLATE></TEMPLATE>
<LOCALE></LOCALE>
<OUTPUT_FORMAT></OUTPUT_FORMAT>
<DEL_CHANNEL></DEL_CHANNEL>
<TIMEZONE></TIMEZONE>
<CALENDAR></CALENDAR>
<OUTPUT_NAME></OUTPUT_NAME>
<SAVE_OUTPUT></SAVE_OUTPUT>
<PARAMETER1></PARAMETER1>
<PARAMETER2></PARAMETER2>
<PARAMETER3></PARAMETER3>
<PARAMETER4></PARAMETER4>
<PARAMETER5></PARAMETER5>
<PARAMETER6></PARAMETER6>
<PARAMETER7></PARAMETER7>
<PARAMETER8></PARAMETER8>
<PARAMETER9></PARAMETER9>
<PARAMETER10></PARAMETER10>
</ROW>
```


</ROWSET>

- **KEY** — The Delivery key and must match the **Deliver By** element. The bursting engine uses the key to link delivery criteria to a specific section of the burst data. Ensure that you use double quotes around "KEY" in the select statement, for example:


```
select d.department_name as "KEY",
```
- **TEMPLATE** — The name of the Layout to apply. Note that the value is the Layout name (for example, 'Customer Invoice'), not the template file name (for example, invoice.rtf).
- **LOCALE** — The template locale, for example, 'en-US'.
- **OUTPUT_FORMAT** — The output format. For a description of each type, see the section "Selecting Output Formats" in *Oracle Fusion Middleware Report Designer's Guide for Oracle Business Intelligence Publisher*. [Table 7-1](#) shows the valid values to enter for the bursting query.

Table 7-1 Values to Enter for OUTPUT_FORMAT

Output Format	Value to Enter in Bursting Query	Template Types That Can Generate This Output Format
Interactive	N/A	Not supported for bursting
HTML	html	BI Publisher, RTF, XSL Stylesheet (FO)
PDF	pdf	BI Publisher, RTF, PDF, Flash, XSL Stylesheet (FO)
RTF	rtf	BI Publisher, RTF, XSL Stylesheet (FO)
Excel (mhtml)	excel	BI Publisher, RTF, Excel, XSL Stylesheet (FO)
Excel (html)	excel2000	BI Publisher, RTF, Excel, XSL Stylesheet (FO)
Excel (*.xlsx)	xlsx	BI Publisher, RTF, XSL Stylesheet (FO)
PowerPoint (mhtml)	ppt	BI Publisher, RTF, XSL Stylesheet (FO)
PowerPoint (*.pptx)	pptx	BI Publisher, RTF, XSL Stylesheet (FO)
MHTML	mhtml	BI Publisher, RTF, Flash, XSL Stylesheet (FO)
PDF/A	pdfa	BI Publisher, RTF, XSL Stylesheet (FO)
PDF/X	pdfx	BI Publisher, RTF, XSL Stylesheet (FO)
Zipped PDFs	pdfz	BI Publisher, RTF, PDF, XSL Stylesheet (FO)
FO Formatted XML	xslfo	BI Publisher, RTF, XSL Stylesheet (FO)
Data (XML)	xml	BI Publisher, RTF, PDF, Excel, Flash, XSL Stylesheet (FO), Etext, XSL Stylesheet (HTML XML/Text)
Data (CSV)	csv	BI Publisher, RTF, PDF, Excel, Flash, XSL Stylesheet (FO), XSL Stylesheet (HTML XML/Text), Etext
XML	xml	XSL Stylesheet (HTML XML/Text)
Text	text	XSL Stylesheet (HTML XML/Text), Etext
Flash	flash	Flash

- **SAVE_OUTPUT** — Indicates whether to save the output documents to BI Publisher history tables that the output can be viewed and downloaded from the **Report Job History** page.

Valid values are 'true' (default) and 'false'. If this property is not set, the output is saved.

- **DEL_CHANNEL** — The delivery method. Valid values are:
 - EMAIL
 - FAX
 - FILE
 - FTP
 - PRINT
 - WEBDAV

- **TIMEZONE** — The time zone to use for the report. Values must be in the Java format, for example: 'America/Los_Angeles'. If time zone is not provided, then the system default time zone is used to generate the report.

- **CALENDAR** — The calendar to use for the report. Valid values are:
 - GREGORIAN
 - ARABIC_HIJRAH
 - ENGLISH_HIJRAH
 - JAPANESE_IMPERIAL
 - THAI_BUDDHA
 - ROC_OFFICIAL (Taiwan)

If not provided, the value 'GREGORIAN' is used.

- **OUTPUT_NAME** — The name to assign to the output file in the report job history.

- **Delivery parameters by channel** — The values required for the parameters depend on the delivery method chosen. The parameter values mappings for each method are shown in [Table 7-2](#). Not all delivery channels use all the parameters.

Table 7-2 Parameter Values Mapping by Method

Delivery Channel	PARAMETER Values
Email	PARAMETER1: Email address PARAMETER2: cc PARAMETER3: From PARAMETER4: Subject PARAMETER5: Message body PARAMETER6: Attachment value ('true' or 'false'). If your output format is PDF, you must set this parameter to "true" to attach the PDF to the e-mail. PARAMETER7: Reply-To PARAMETER8: Bcc (PARAMETER 9-10 are not used)

Table 7–2 (Cont.) Parameter Values Mapping by Method


Delivery Channel	PARAMETER Values
Printer	<p>PARAMETER1: Printer group</p> <p>PARAMETER2: Printer name or for a printer on CUPS, the printer URI, for example: ipp://myserver.com:631/printers/printer1</p> <p>PARAMETER3: Number of Copies</p> <p>PARAMETER4: Sides. Valid values are:</p> <ul style="list-style-type: none"> ▪ "d_single_sided" for single-sided ▪ "d_double_sided_l" for duplex/long edge ▪ "d_double_sided_s" for tumble/short edge <p>If the parameter is not specified, single-sided is used.</p> <p>PARAMETER5: Tray. Valid values are:</p> <ul style="list-style-type: none"> ▪ "t1" for "Tray 1" ▪ "t2" for "Tray 2" ▪ "t3" for "Tray 3" <p>If not specified, the printer default is used.</p> <p>PARAMETER6: Print range. For example "3" prints page 3 only, "2-5" prints pages 2-5, "1,3-5" prints pages 1 and 3-5 (PARAMETER 7-10 are not used)</p>
Fax	<p>PARAMETER1: Fax server name</p> <p>PARAMETER2: Fax number (PARAMETER 3-10 are not used)</p>
WebDAV	<p>PARAMETER1: Server Name PARAMETER2: Username</p> <p>PARAMETER3: Password PARAMETER4: Remote Directory</p> <p>PARAMETER5: Remote File Name</p> <p>PARAMETER6: Authorization type, values are 'basic' or 'digest' (PARAMETER 7-10 are not used)</p>
File	<p>PARAMETER1: Directory</p> <p>PARAMETER2: File Name (PARAMETER 3-10 are not used)</p>
FTP and SFTP	<p>PARAMETER1: Server name PARAMETER2: Username</p> <p>PARAMETER3: Password</p> <p>PARAMETER4: Remote Directory</p> <p>PARAMETER5: Remote File Name</p> <p>PARAMETER6: Secure (set this value to 'true' to enable Secure FTP) (PARAMETER 7-10 are not used)</p>

7.5 Passing a Parameter to the Bursting Query

You can pass the value for an element of your bursting XML using a parameter defined in the data model. For example, if you want to be able to select the template at the time of submission, you can define a parameter in the data model and use the `:parameter_name` syntax in your query. The following example demonstrates this use case of a parameter in a bursting query.


Assume your report definition includes three layouts: layout1, layout2, and layout3. At submission time you want to select the layout (or TEMPLATE, as defined in the bursting query) to use. In your data model, define a list of values with the layout names. The following figure shows a data model with the layout list of values:

Figure 7–3 Defining the List of Values




Next create a menu type parameter, here named P1:

Figure 7–4 Defining a Parameter



In the bursting query, pass the parameter value to the TEMPLATE field using :P1 as shown in the following figure:

Figure 7-5 Updating the Bursting Query to Accept the P1 Parameter



7.6 Defining the Split By and Deliver By Elements for a CLOB/XML Data Set

If the split-by and deliver-by elements required for your bursting definition reside in a data set retrieved from a CLOB column in a database, BI Publisher cannot parse the XML to present the elements in the **Split By** and **Deliver By** lists. You therefore must manually enter the XPath to locate each element in the retrieved XML data set. To ensure that you enter the path correctly, use the data model editor's **Get XML Output** feature to view the XML that is generated by the data engine.

For example, the sample XML code, shown in [Figure 7-6](#), was stored in a CLOB column in the database called "XMLTEXT", and extracted as an XML data set:

Figure 7-6 Sample Data Extract of Data Stored as CLOB


```

<!--Generated by Oracle BI Publisher -->
-<DATA_DS>
  -<G_1>
    -<XMLTEXT>
      -<DATA_DS>
        -<G_1>
          <DEPARTMENT_ID>10</DEPARTMENT_ID>
          <DEPARTMENT_NAME>Administration</DEPARTMENT_NAME>
          <MANAGER_ID>200</MANAGER_ID>
          <LOCATION_ID>1700</LOCATION_ID>
        -<G_2>
          <EMPLOYEE_ID>200</EMPLOYEE_ID>
          <FIRST_NAME>Jennifer</FIRST_NAME>
          <LAST_NAME>Whalen</LAST_NAME>
          <EMAIL>JWHALEN</EMAIL>
          <PHONE_NUMBER>515.123.4444</PHONE_NUMBER>
          <HIRE_DATE>1987-09-17T00:00:00.000-07:00</HIRE_DATE>
          <JOB_ID>AD_ASST</JOB_ID>
          <SALARY>4400</SALARY>
          <MANAGER_ID_1>101</MANAGER_ID_1>
          <DEPARTMENT_ID_1>10</DEPARTMENT_ID_1>
    
```

For this example, you want to add a bursting definition with split by and deliver by element based on the DEPARTMENT_ID, which is an element within the CLOB/XML data set.


When you add the bursting definition, the Split By and Deliver By lists cannot parse the structure beneath the XMLTEXT element. Therefore, the list does not display the elements available beneath the XMLTEXT node, as shown in Figure 7-7.

Figure 7-7 Split By List Presents Only Top-Level Nodes



To use the DEPARTMENT_ID element as the Split By element, manually type the XPath into the field as shown in Figure 7-8.

Figure 7-8 Manually Entering the XPath into the Split By Field



7.7 Configuring a Report to Use a Bursting Definition

Although you can define multiple bursting definitions for a single data model, you can enable only one for a report.

Enable a report to use a bursting definition on the **Report Properties** dialog of the report editor. For more information see the section "Configuring Report Properties" in *Oracle Fusion Middleware Report Designer's Guide for Oracle Business Intelligence Publisher*.

After you configure the report to use the bursting definition, when you schedule a job for this report you can choose to use the bursting definition to format and deliver the report. For more information see the section "Creating a Bursting Job" in *Oracle Fusion Middleware User's Guide for Oracle Business Intelligence Publisher*.

You can also opt not to use the bursting definition and choose your own output and destination as a regular scheduled report.

7.8 Sample Bursting Query

The following example is based on an invoice report. This report is to be delivered by CUSTOMER_ID to each customer's individual e-mail address.

This example assumes that the delivery and formatting preferences for each customer are contained in a database table named "CUSTOMERS". The CUSTOMERS table includes the following columns that will be retrieved to create the delivery XML dynamically at runtime:

- CST_TEMPLATE
- CST_LOCALE
- CST_FORMAT
- CST_EMAIL_ADDRESS

The CUSTOMER_ID will be used as the KEY and also to define the output file name.

The SQL code to generate the delivery data set for this example is as follows:

```
select distinct
CUSTOMER_ID as "KEY",
CST_TEMPLATE TEMPLATE,
CST_LOCALE LOCALE,
CST_FORMAT OUTPUT_FORMAT,
CUSTOMER_ID OUTPUT_NAME,
'EMAIL' DEL_CHANNEL,
CST_EMAIL_ADDRESS PARAMETER1,
'accounts.receivable@example.com' PARAMETER2,
'bip-collections@example.com' PARAMETER3,
'Your Invoices' PARAMETER4,
'Hi' || CUST_FIRST_NAME || chr(13) || 'Please find attached your
invoices.' PARAMETER5,
'true' PARAMETER6,
'donotreply@mycompany.com' PARAMETER7
from CUSTOMERS
```

7.9 Creating a Table to Use as a Delivery Data Source

If the delivery information is not easily available in the existing data sources, then you can consider creating a table to use for the query to create the delivery XML. Following is a sample:

Important: If the JDBC driver that you use does not support column alias, when you define the bursting control table, the columns must match exactly the control XML tag name. For example, the KEY column must be named "KEY", upper case is required. PARAMETER1 must be named "PARAMETER1", not "parameter1" nor "param1", and so on.

```

CREATE TABLE "XXX"."DELIVERY_CONTROL"
( "KEY" NUMBER,
  "TEMPLATE" VARCHAR2(20 BYTE),
  "LOCALE" VARCHAR2(20 BYTE),
  "OUTPUT_FORMAT" VARCHAR2(20 BYTE),
  "DEL_CHANNEL" VARCHAR2(20 BYTE),
  "PARAMETER1" VARCHAR2(100 BYTE),
  "PARAMETER2" VARCHAR2(100 BYTE),
  "PARAMETER3" VARCHAR2(100 BYTE),
  "PARAMETER4" VARCHAR2(100 BYTE),
  "PARAMETER5" VARCHAR2(100 BYTE),
  "PARAMETER6" VARCHAR2(100 BYTE),
  "PARAMETER7" VARCHAR2(100 BYTE),
  "PARAMETER8" VARCHAR2(100 BYTE),
  "PARAMETER9" VARCHAR2(100 BYTE),
  "PARAMETER10" VARCHAR2(100 BYTE),
  "OUTPUT_NAME" VARCHAR2(100 BYTE),
  "SAVE_OUTPUT" VARCHAR2(4 BYTE),
  "TIMEZONE" VARCHAR2(300 BYTE),
  "CALENDAR" VARCHAR2(300 BYTE)
) PCTFREE 10 PCTUSED 40 INITRANS 1 MAXTRANS 255 NOCOMPRESS LOGGING
STORAGE(INITIAL 65536 NEXT 1048576 MINEXTENTS 1 MAXEXTENTS 2147483645
PCTINCREASE 0 FREELISTS 1 FREELIST GROUPS 1 BUFFER_POOL DEFAULT)
TABLESPACE "EXAMPLES";

```

Tips for creating a creating bursting delivery table:

- If the split data set does not contain a DELIVERY_KEY value, then the document is neither delivered nor generated. For example, using the preceding example, if customer with ID 123 is not defined in the bursting delivery table, this customer's document is not generated.
- To enable a split data set to generate more than one document or deliver to more than one destination, duplicate the DELIVERY_KEY value and provide different sets of OUTPUT_FORMAT, DEL_CHANNEL, or other parameters. For example, customer with ID 456 wants his document delivered to two e-mail addresses. To achieve this, insert two rows in the table, both with 456 as the DELIVERY_KEY and each with its own e-mail address.

Index

A

ABS, 3-27
Actions menu
 group, 3-10
aggregate elements
 group level, 3-13
 setting properties, 3-15
analysis
 See Oracle BI analysis, 1-3
AVG, 3-27

B

backup data source
 using for data model, 1-6
bind variables
 adding, 2-4, 2-14
bursting
 setting up, 7-2
bursting definition
 defining for CLOB data set, 7-9

C

CEILING, 3-27
CLOB
 adding bursting definitions for, 7-9
 using as a data source, 2-49
code view, 3-6
CONCAT, 3-28

D

data model
 component definitions, 1-1
data model editor
 launching, 1-4
data sets
 creating, 2-1
 editing, 2-3
 guidelines for multiquery data models, 3-3
 linking, 3-7
 supported types, 2-2
 what is supported for each type, 1-2
data sources
 supported types, 1-2

Database Fetch Size property, 1-6
DATE, 3-28
default data source property, 1-5
diagram view, 3-5

E

element properties
 setting, 3-17
element-level links, 3-7
 deleting, 3-9
elements
 renaming, 3-25
Endeca, 2-48
Excel data source files
 refreshing local files, 1-7

F

filters
 creating for groups, 3-16
 deleting, 3-17
 editing, 3-17
find variables
 user information, 2-54
FLOOR, 3-27
FORMAT_DATE, 3-29
FORMAT_NUMBER, 3-29
functions
 element level, 3-17
 global level, 3-21
 reference, 3-25

G

global-level functions, 3-21
group filters
 creating, 3-16
 deleting, 3-17
 editing, 3-17
group link
 Actions menu, 3-10
group-level links, 3-7
 creating, 3-10
 deleting, 3-11

H

- HTTP XML feed
 - creating data set from, 2-46
- HTTP XML feed data sets
 - limitations on structuring, 2-46

I

- INSTR, 3-28

L

- LDAP
 - creating bind variables from user attributes, 2-55
 - using as data source, 2-35
- LENGTH, 3-27
- links
 - creating between data sets, 3-7
 - element-level, 3-7
 - group-level, 3-7
- list of values
 - adding to data model, 4-8

M

- master-detail links, 3-7
- MAX, 3-26
- Microsoft Excel
 - creating a data set based on, 2-39
 - data source from system directory, 2-41
 - deleting an uploaded data source file, 2-43
 - refreshing an uploaded data source file, 2-43
 - uploading a local file to use as a data source, 2-42
- MIN, 3-26
- multiquery data models
 - when to use, 3-3

N

- null elements
 - setting value for, 3-25
- NVL, 3-28

O

- OLAP data sources
 - limitations, 2-20
 - querying, 2-19
- Oracle BI analysis
 - creating a data set, 2-24
 - limitations as data set, 2-25
- Oracle DB Default Package property, 1-5
- output view, 3-6

P

- parameters
 - adding to data model, 4-1
 - date, 4-7
 - menu, 4-5

- text, 4-4
- parent-child groups
 - moving element between, 3-12
- parent-child links, 3-7
- PL/SQL
 - add element, 3-21
 - PL/SQL filters, 3-16
- properties
 - aggregate elements, 3-15
 - setting, 1-5
- properties pane, 1-4

Q

- Query Builder
 - join conditions, 2-12
 - joining objects, 2-13
 - supported column types, 2-10
 - using, 2-8

R

- renaming elements, 3-25
- ROUND, 3-27
- RSS feed
 - creating data set from, 2-46

S

- sample data
 - attaching to data model, 1-7
 - exporting, 2-54
 - generating and saving for a data model, 2-53
- sorting
 - apply to group, 3-18
 - support, 3-18
- SQL query
 - defining as data set, 2-3
 - editing, 2-14
- STRING, 3-28
- Structure view, 3-5, 3-24
- subgroups
 - creating in data models, 3-11
 - removing, 3-12
- SUBSTRING, 3-28
- SUM, 3-27
- system variables
 - including in a data model, 2-54

T

- toolbar, 1-4

U

- user ID
 - including in data model, 2-54
- user information
 - including in data model, 2-54
- user preferences
 - including in data model, 2-54

user roles
including in data model, 2-54

V

value if null, 3-25
view object
creating a data set from, 2-25
limitations as data set, 2-26

W

Web service
limitations on structuring, 2-35
supported formats, 2-26

X

XML feed
creating data set from over HTTP, 2-46
XML file
using as a data source, 2-36
XML output
viewing from data model editor, 1-5
XML output options
setting, 1-6
XML tag display
setting upper or lower case, 1-6

